

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001010000-N	200	SELECT TREE REMOVAL	25 EA		
0004	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	790 TON		
0008	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	2,460 SY		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,408 LF		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,544 LF		
0011	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	560 LF		
0012	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	96 LF		
0013	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	48 LF		
0014	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	316 LF		
0015	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	396 LF		
0016	0995000000-E	340	PIPE REMOVAL	1,742 LF		
0017	1099500000-E	505	SHALLOW UNDERCUT	350 CY		
0018	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	709 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	1,500 TON		
0020	1330000000-E	607	INCIDENTAL MILLING	500 SY		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,400 TON		
0022	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4,000 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	435 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	250 TON		
0025	2209000000-E	838	ENDWALLS	29 CY		
0026	2253000000-E	840	PIPE COLLARS	0.5 CY		
0027	2275000000-E	SP	FLOWABLE FILL	13 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	121 EA		
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	15.79 LF		
0030	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	38 EA		
0031	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	28 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	27 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	23 EA		
0036	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	9,640 LF		
0038	2591000000-E	848	4" CONCRETE SIDEWALK	2,610 SY		
0039	2605000000-N	848	CONCRETE CURB RAMP	10 EA		
0040	2612000000-E	848	6" CONCRETE DRIVEWAY	970 SY		
0041	2830000000-N	858	ADJUSTMENT OF MANHOLES	19 EA		
0042	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	19 EA		
0043	2875000000-N	859	CONVERT EXISTING CATCH BASIN TO DROP INLET	1 EA		
0044	3628000000-E	876	RIP RAP, CLASS I	76 TON		
0045	3649000000-E	876	RIP RAP, CLASS B	16 TON		
0046	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,169 SY		
0047	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0048	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	534 SF		
0049	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
0050	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	125 SF		
0051	4430000000-N	1130	DRUMS	600 EA		
0052	4435000000-N	1135	CONES	30 EA		
0053	4445000000-E	1145	BARRICADES (TYPE III)	152 LF		
0054	4450000000-N	1150	FLAGGER	1,800 HR		
0055	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	9,738 LF		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	119	LF	
0057	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	27	EA	
0058	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	24,144	LF	
0059	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	38	LF	
0060	6000000000-E	1605	TEMPORARY SILT FENCE	4,410	LF	
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	495	TON	
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	595	TON	
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	1,170	TON	
0064	6015000000-E	1615	TEMPORARY MULCHING	4	ACR	
0065	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0066	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
0067	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	
0068	6029000000-E	SP	SAFETY FENCE	1,300	LF	
0069	6030000000-E	1630	SILT EXCAVATION	1,725	CY	
0070	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,540	SY	
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	2,180	LF	
0072	6070000000-N	1639	SPECIAL STILLING BASINS	8	EA	
0073	6071010000-E	SP	WATTLE	360	LF	
0074	6071020000-E	SP	POLYACRYLAMIDE (PAM)	135	LB	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6071030000-E	1640	COIR FIBER BAFFLE	250 LF		
0076	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0077	6087000000-E	1660	MOWING	3 ACR		
0078	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0079	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0080	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0081	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0082	6111000000-E	SP	IMPERVIOUS DIKE	80 LF		
0083	6114500000-N	1667	SPECIALIZED HAND MOWING	5 MHR		
0084	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		

1415/May10/Q90435.29/D283082270000/E84

Total Amount Of Bid For Entire Project :

Contract No. C203279

County (ies): Nash

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General