

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (34+28-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	700 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	739 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	2,300 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	1,180 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	85 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	260 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	36 LF		
0013	0335300000-E	305	18" DRAINAGE PIPE	80 LF		
0014	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0015	0343000000-E	310	15" SIDE DRAIN PIPE	140 LF		
0016	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	240 LF		
0017	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	104 LF		
0018	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	56 LF		
0019	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	120 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0995000000-E	340	PIPE REMOVAL	214 LF		
0021	1099500000-E	505	SHALLOW UNDERCUT	500 CY		
0022	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	1,000 TON		
0023	1121000000-E	520	AGGREGATE BASE COURSE	100 TON		
0024	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0025	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0026	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,570 TON		
0027	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,475 TON		
0028	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,325 TON		
0029	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	262 TON		
0030	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	70 TON		
0031	2022000000-E	815	SUBDRAIN EXCAVATION	115 CY		
0032	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85 CY		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0034	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0035	2077000000-E	815	6" OUTLET PIPE	6 LF		
0036	2209000000-E	838	ENDWALLS	8 CY		
0037	2253000000-E	840	PIPE COLLARS	2 CY		
0038	2264000000-E	840	PIPE PLUGS	1 CY		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	2275000000-E	SP	FLOWABLE FILL	3 CY		
0040	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0041	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0042	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0043	2462000000-E	SP	*** SLUICE GATE (18")	3 EA		
0044	2556000000-E	846	SHOULDER BERM GUTTER	190 LF		
0045	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		
0046	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0047	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0048	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0049	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (W-BEAM)	2 EA		
0050	3628000000-E	876	RIP RAP, CLASS I	63 TON		
0051	3649000000-E	876	RIP RAP, CLASS B	57 TON		
0052	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,184 SY		
0053	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	120 LF		
0054	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0055	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0056	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	9 EA		
0057	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	104 SF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	176 SF		
0059	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	26 SF		
0060	4430000000-N	1130	DRUMS	53 EA		
0061	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0062	4450000000-N	1150	FLAGGER	1,200 HR		
0063	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6 EA		
0064	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	2 EA		
0065	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	1,090 LF		
0066	4505000000-E	1170	RESET PORTABLE CONCRETE BARRIER (ANCHORED)	560 LF		
0067	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	62 EA		
0068	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,893 LF		
0069	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,938 LF		
0070	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	730 LF		
0071	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	1,060 LF		
0072	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	16,730 LF		
0073	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	2 EA		
0074	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	24 EA		
0075	6000000000-E	1605	TEMPORARY SILT FENCE	2,800 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	450 TON		
0077	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	465 TON		
0078	6012000000-E	1610	SEDIMENT CONTROL STONE	660 TON		
0079	6015000000-E	1615	TEMPORARY MULCHING	6 ACR		
0080	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0081	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.25 TON		
0082	6024000000-E	1622	TEMPORARY SLOPE DRAINS	360 LF		
0083	6029000000-E	SP	SAFETY FENCE	800 LF		
0084	6030000000-E	1630	SILT EXCAVATION	2,500 CY		
0085	6036000000-E	1631	MATTING FOR EROSION CONTROL	14,000 SY		
0086	6037000000-E	SP	COIR FIBER MAT	800 SY		
0087	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,000 SY		
0088	6042000000-E	1632	1/4" HARDWARE CLOTH	475 LF		
0089	6045000000-E	SP	*** TEMPORARY PIPE (18")	70 LF		
0090	6069000000-E	1638	STILLING BASINS	100 CY		
0091	6070000000-N	1639	SPECIAL STILLING BASINS	18 EA		
0092	6071010000-E	SP	WATTLE	575 LF		
0093	6071020000-E	SP	POLYACRYLAMIDE (PAM)	200 LB		
0094	6071030000-E	1640	COIR FIBER BAFFLE	700 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095	6071050000-E	SP	*** SKIMMER (1-1/2")	7 EA		
0096	6084000000-E	1660	SEEDING & MULCHING	6 ACR		
0097	6087000000-E	1660	MOWING	3 ACR		
0098	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0099	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0100	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		
0101	6108000000-E	1665	FERTILIZER TOPDRESSING	4.25 TON		
0102	6111000000-E	SP	IMPERVIOUS DIKE	75 LF		
0103	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0104	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		

CULVERT ITEMS

0105	8126000000-N	414	CULVERT EXCAVATION, STA ***** (39+86.00-L-)	Lump Sum	L.S.	
0106	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	37 TON		
0107	8196000000-E	420	CLASS A CONCRETE (CULVERT)	59.2 CY		
0108	8245000000-E	425	REINFORCING STEEL (CULVERT)	7,936 LB		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0109	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (34+28.00-L-)	Lump Sum	L.S.	
0110	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (34+28.00-L-)	Lump Sum	L.S.	
0111	8096000000-E	450	PILE EXCAVATION IN SOIL	113 LF		
0112	8097000000-E	450	PILE EXCAVATION NOT IN SOIL	97 LF		
0113	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	49 LF		
0114	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	56 LF		
0115	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	45 LF		
0116	8113000000-N	411	SID INSPECTIONS	1 EA		
0117	8114000000-N	411	SPT TESTING	1 EA		
0118	8115000000-N	411	CSL TESTING	1 EA		
0119	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	10,284 SF		
0120	8161000000-E	420	GROOVING BRIDGE FLOORS	10,130 SF		
0121	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	173.9 CY		
0122	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (34+28.00-L-)	Lump Sum	L.S.	
0123	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,568 LB		
0124	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,461 LB		
0125	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	1,025.18 LF		
0126	8364000000-E	450	HP12X53 STEEL PILES	210 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	8503000000-E	460	CONCRETE BARRIER RAIL	564 LF		
0128	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	595 TON		
0129	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	660 SY		
0130	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0131	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
			Total Amount Of Bid For Entire Project :			
0906/May01/Q143660.03/D580730900000/E131						

Contract No. **C203156**

County (ies): **Stanly**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General