

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (12+53.00)	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (21+36.25)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	843 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	3,697 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	850 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	850 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	40 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	100 SY		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	120 LF		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	144 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,830 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,330 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,110 TON		
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	215 TON		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0020	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0021	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0023	2070000000-N	815	SUBDRAIN PIPE OUTLET	2 EA		
0024	2077000000-E	815	6" OUTLET PIPE	12 LF		
0025	2264000000-E	840	PIPE PLUGS	0.09 CY		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0028	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	390 LF		
0029	2556000000-E	846	SHOULDER BERM GUTTER	132 LF		
0030	2570000000-N	SP	MODIFIED CONCRETE FLUME	4 EA		
0031	2612000000-E	848	6" CONCRETE DRIVEWAY	30 SY		
0032	3030000000-E	862	STEEL BM GUARDRAIL	537.5 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0036	3635000000-E	876	RIP RAP, CLASS II	20 TON		
0037	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,205 SY		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (A)	39 SF		
0039	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (OVERLAY SIGN)	572 SF		
0040	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	27 LF		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0042	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	2 EA		
0043	4115000000-N	904	SIGN ERECTION, OVERLAY (OVER- HEAD)	3 EA		
0044	4116000000-N	904	SIGN ERECTION, OVERLAY (GROUND MOUNTED)	5 EA		
0045	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	9 EA		
0046	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	5 EA		
0047	4360000000-N	SP	GENERIC SIGNING ITEM TEMP SIGN COVERINGS TYPE A	8 EA		
0048	4360000000-N	SP	GENERIC SIGNING ITEM TEMP SIGN COVERINGS TYPE D	1 EA		
0049	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	602 SF		
0050	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	110 SF		
0051	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0052	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0053	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	5 EA		
0054	4430000000-N	1130	DRUMS	100 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4445000000-E	1145	BARRICADES (TYPE III)	116		LF
0056	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,980		LF
0057	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,249		LF
0058	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	48		LF
0059	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	7		EA
0060	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	721		LF
0061	6000000000-E	1605	TEMPORARY SILT FENCE	2,950		LF
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	500		TON
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	140		TON
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	215		TON
0065	6015000000-E	1615	TEMPORARY MULCHING	3		ACR
0066	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100		LB
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5		TON
0068	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400		LF
0069	6029000000-E	SP	SAFETY FENCE	1,800		LF
0070	6030000000-E	1630	SILT EXCAVATION	330		CY
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,325		SY
0072	6037000000-E	SP	COIR FIBER MAT	200		SY

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0074	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	435 SY		
0075	6070000000-N	1639	SPECIAL STILLING BASINS	4 EA		
0076	6071012000-E	SP	COIR FIBER WATTLE	210 LF		
0077	6071020000-E	SP	POLYACRYLAMIDE (PAM)	35 LB		
0078	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0079	6087000000-E	1660	MOWING	1.25 ACR		
0080	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0081	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0082	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0083	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0084	6111000000-E	SP	IMPERVIOUS DIKE	265 LF		
0085	6114500000-N	1667	SPECIALIZED HAND MOWING	20 MHR		
0086	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	50 EA		
0087	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	200 LF		
0088	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	100 LF		
0089	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	3 EA		
0090	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	555 LF		
0091	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	500 LF		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0092	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+53.00-L-)	Lump Sum	L.S.	
0093	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+36.00-L-)	Lump Sum	L.S.	
0094	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+53.00-L-)	Lump Sum	L.S.	
0095	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21+36.00-L-)	Lump Sum	L.S.	
0096	8156000000-E	SP	CONCRETE WEARING SURFACE	6,923 SF		
0097	8161000000-E	420	GROOVING BRIDGE FLOORS	8,249 SF		
0098	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	94.8 CY		
0099	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+53.00-L-)	Lump Sum	L.S.	
0100	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+36.00-L-)	Lump Sum	L.S.	
0101	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,122 LB		
0102	8364000000-E	450	HP12X53 STEEL PILES	595 LF		
0103	8475000000-E	460	TWO BAR METAL RAIL	300 LF		
0104	8517000000-E	460	1'-***"X *****" CONCRETE PARA- PET (1'-2" X 2'11-1/2")	150 LF		
0105	8517000000-E	460	1'-***"X *****" CONCRETE PARA- PET (1'-2" X 3'1-1/8")	180 LF		
0106	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	700 TON		
0107	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	777 SY		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0109	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
0110	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	2,445 LF		
1235/May01/Q75222.29/D511804732000/E110			Total Amount Of Bid For Entire Project :			

Contract No. **C203157**

County (ies): **Wilson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General