

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	681 CY		
0003	0255000000-E	SP	GENERIC GRADING ITEM AGGREGATE SHOULDER BORROW	5,466 TON		
0004	1220000000-E	545	INCIDENTAL STONE BASE	275 TON		
0005	1243000000-E	SP	SHOULDER CONSTRUCTION	1.18 SMI		
0006	1245000000-E	SP	SHOULDER RECONSTRUCTION	47.22 SMI		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	11,877 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	2,732 SY		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 3")	1,690 SY		
0010	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (1-1/2" TO 3")	10,019 SY		
0011	1330000000-E	607	INCIDENTAL MILLING	4,859 SY		
0012	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,644 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	19,139 TON		
0014	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	3,210 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	8,128 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,962 TON		
0017	1704000000-E	SP	PATCHING EXISTING PAVEMENT	2,345 TON		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1771000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #6M STONE	48,530 SY		
0019	1880000000-E	SP	GENERIC PAVING ITEM JOINT REPAIR	322 TON		
0020	1891000000-E	SP	GENERIC PAVING ITEM ASPHALT SURFACE TREATMENT, TRIPLE SEAL	24,360 SY		
0021	2830000000-N	858	ADJUSTMENT OF MANHOLES	24 EA		
0022	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	14 EA		
0023	4366000000-E	SP	GENERIC SIGNING ITEM WORK ZONE ADVANCE / GENERAL WARNING SIGNING	2,822.4 SF		
0024	4510000000-N	SP	LAW ENFORCEMENT	120 HR		
0025	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0026	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	161,550 LF		
0027	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	141,584 LF		
0028	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,203 LF		
0029	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	100 LF		
0030	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,673 LF		
0031	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16 EA		
0032	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	43 EA		
0033	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	423,998 LF		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	600 LF		
0035	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,241 EA		
0036	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	524 EA		
0037	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0038	6000000000-E	1605	TEMPORARY SILT FENCE	95 LF		
0039	6071010000-E	SP	WATTLE	50 LF		
0040	6084000000-E	1660	SEEDING & MULCHING	3.16 ACR		
0041	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	600 LF		

0905/Jun13/Q883550.96/D127862110000/E41

Total Amount Of Bid For Entire Project :

Contract No. **C203402**

County (ies): **Chatham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General