

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+01.00)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+06.50)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	200 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	20 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	50 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	128 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	40 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	430 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	660 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	65 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	535 LF		
0021	3030000000-E	862	STEEL BM GUARDRAIL	500 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0025	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0026	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	495 SY		
0027	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	397 SF		
0028	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0029	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0030	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,440 LF		
0031	6000000000-E	1605	TEMPORARY SILT FENCE	3,160 LF		
0032	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0033	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	15 TON		
0034	6012000000-E	1610	SEDIMENT CONTROL STONE	130 TON		
0035	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0036	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0037	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0039	6029000000-E	SP	SAFETY FENCE	1,500 LF		
0040	6030000000-E	1630	SILT EXCAVATION	100 CY		
0041	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,400 SY		
0042	6037000000-E	SP	COIR FIBER MAT	525 SY		
0043	6042000000-E	1632	1/4" HARDWARE CLOTH	600 LF		
0044	6071012000-E	SP	COIR FIBER WATTLE	135 LF		
0045	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0046	6087000000-E	1660	MOWING	0.5 ACR		
0047	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0048	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0049	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0050	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0051	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0052	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

STRUCTURE ITEMS

0053	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (21+06.50-L-)	Lump Sum	L.S.	
0054	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+00.00-L-)	Lump Sum	L.S.	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+06.50-L-)	Lump Sum	L.S.	
0056	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+00.00-L-)	Lump Sum	L.S.	
0057	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21+06.50-L-)	Lump Sum	L.S.	
0058	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	11.6 CY		
0059	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+00.00-L-)	Lump Sum	L.S.	
0060	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+06.50-L-)	Lump Sum	L.S.	
0061	8217000000-E	425	REINFORCING STEEL (BRIDGE)	820 LB		
0062	8364000000-E	450	HP12X53 STEEL PILES	1,400 LF		
0063	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	1,400 LF		
0064	8393000000-N	450	PILE REDRIVES	26 EA		
0065	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	585.25 LF		
0066	8590000000-E	876	RIP RAP, CLASS ** (1, 2'-0" THICK)	252 TON		
0067	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	281 SY		
0068	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0069	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,213.38 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	8867000000-E	SP	GENERIC STRUCTURE ITEM 3'-0" X 2'-6" PRESTRESSED CONCRETE BENT CAPS	261.31 LF		

1121/May29/Q31023.29/D337750412000/E70

Total Amount Of Bid For Entire Project :

Contract No. **C203208**

County (ies): **Robeson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General