Preliminary Site Assessment
Page Distributing Company, Inc.
Parcel #169
Fayetteville, Cumberland County, NC

H&H Job No. ROW-203 State Project U-2810C WBS Element # 34866.1.1 January 6, 2009



2923 South Tryon Street Suite 100 Charlotte, NC 28203 704-586-0007

3334 Hillsborough Street Raleigh, NC 27607 919-847-4241

# Preliminary Site Assessment Report Page Distributing Company, Inc. Parcel #169 Fayetteville, Cumberland County, North Carolina H&H Project ROW-203

#### **Table of Contents**

Section Pa	ge No.
3.0 Analytical Results	3
4.0 Summary and Regulatory Considerations	3
Section 1.0 Introduction	4
List of Tables	
Table 1 Soil Analytical Results – Page Distributing Company, Inc. Parcel #169	
List of Figures	
Figure 1 Site Location Map	
Figure 2 Site Map and Soil Analytical Results	
List of Appendices	
Appendix A NC DOT Preliminary Plan	
Appendix B Schnabel Engineering Geophysical Survey Report	
Appendix C Soil Boring Logs	
Appendix D Laboratory Analytical Report	

Preliminary Site Assessment Report
Page Distributing Company, Inc. Parcel #169
Fayetteville, Cumberland County, North Carolina
H&H Project ROW-203

#### 1.0 Introduction

Hart & Hickman, PC (H&H) has prepared this Preliminary Site Assessment (PSA) report documenting assessment activities performed at the Page Distributing Company, Inc. property (Parcel #169) located at 2612 Camden Rd. in Fayetteville, Cumberland County, North Carolina. This assessment was conducted on behalf of the North Carolina Department of Transportation (NC DOT) in accordance with H&H's November 17, 2008 proposal.

The purpose of this assessment was to determine the presence or absence of impacted soil at the subject property in proposed right-of-way construction areas related to the widening of Camden Road (State Project U-2810C). A site location map is included as Figure 1 and a site map is presented as Figure 2. The NC DOT preliminary plan of the Camden Road widening area near the Page Distributing Company, Inc. property is attached as Appendix A.

The subject site currently operates as an auto sales and repair shop. Based on information provided by NC DOT, the subject site may have operated as a gas station at some unspecified time in the past. H&H's visual inspection of the site identified a building foundation on the northeast portion of the property that appears to have been a gas station or repair shop. No facility ID or incidents have been identified with this site. H&H did not observe surface evidence of current USTs or evidence of UST removal on the property.

#### 2.0 Site Assessment

#### Soil Assessment Field Activities

H&H mobilized to the Page Distributing Company, Inc. property on December 10, 2008 to advance ten soil borings (169-1 through 169-10) by direct push technology (DPT). Prior to advancing the soil borings, H&H reviewed a geophysical survey performed at the subject site by Schnabel Engineering (Schnabel) between November 18 and 25, 2008. Schnabel utilized ground penetrating

radar (GPR) and time domain electromagnetic (TDEM) technology to identify potential geophysical anomalies and potential USTs at the site. The survey results indicate the presence of utilities, buried metal debris, and a potential UST located to the north of the proposed fill line in the northeast portion of the property. The potential UST appears to be buried approximately 1 to 2 ft below ground surface and is approximately 10.5 ft long and 4 ft in diameter with an estimated capacity of 1,000 gallons. Schnabel's report, including site maps depicting the results of the GPR and TDEM results, is provided in Appendix B.

Prior to conducting soil borings, utilities were marked by NC One Call. Borings were also cleared to a depth of five ft by hand auger. H&H utilized Subsurface Environmental Investigations, LLC (SEI) of Statesville, North Carolina to advance soil borings 169-1 through 169-10 by DPT (see Figure 2). To facilitate the selection of soil samples for laboratory analysis, soil from each boring was screened continuously for the presence of volatile organic compounds (VOCs) with an organic vapor analyzer (OVA). Additionally, H&H observed the soil for visual and olfactory indications of petroleum impacts. No significant OVA readings were measured in soil samples collected from Parcel 169. In general, the soil sample from each boring that exhibited potential visual and/or olfactory indications of petroleum impacts was selected for laboratory analysis. The sample for laboratory analysis was collected from a depth of 0-2 ft in boring 169-2 and 4-6 ft in borings 169-6 and 169-10; otherwise, samples were collected from 2-4 ft. SEI attempted several boring locations on the southwest end of the potential UST; however, no soil samples were collected due to hand auger refusal at depths of 1 to 2 ft in four locations. Soil boring logs are included in Appendix C.

H&H submitted ten soil samples (169-1 through 169-10) for laboratory analysis. Soil samples are identified by the NC DOT Parcel number, soil boring, and the depth interval in ft. Samples were sent to SGS Environmental Services, Inc. of Wilmington, North Carolina using standard chain-of-custody protocol for analysis of total petroleum hydrocarbons (TPH) for gasoline-range organics (GRO) and diesel-range organics (DRO) by EPA Method 8015B. The GRO samples were prepared using EPA Method 5035. Sample depths and analytical results are summarized in Table 1. Laboratory analytical data sheets for Parcel 169 soil samples and chain-of-custody documentation for this site are provided in Appendix D. The analytical results are discussed below.

#### 3.0 Analytical Results

Target analytes were detected in soil samples collected from Parcel 169. The low concentrations of TPH DRO were detected in soil samples 169-2 and 169-5 above the DENR Action Level of 10 mg/kg, if related to UST systems. Concentrations of TPH DRO and GRO were not detected above the laboratory reporting limits in the remaining soil samples analyzed.

Based on laboratory analytical results, low level TPH DRO impacts are present within the proposed right of way. H&H estimates that there are roughly 130 cubic yards (200 tons) of impacted soil between the surface and 4 ft north of the proposed fill line in the northeast portion of the property in the vicinity of the potential UST. Impacted soil may also be present at depths greater than 4 ft in the vicinity of the UST. In addition, there are roughly 200 cubic yards (300 tons) east of the proposed fill line between the surface and a depth of 6 ft.

#### 4.0 Summary and Regulatory Considerations

H&H has reviewed geophysical survey results and collected soil samples at Parcel 169. One UST appears to be present within the proposed right of way in the northeast portion of the property. Analytical results indicate low-level concentrations of TPH DRO above DENR Action Levels. H&H estimates that there are roughly 330 cubic yards (500 tons) of impacted soil between the surface and 6 ft at Parcel 169. The impacted soil is located in the northeast portion of the property. Impacted soil may also be present at greater depths in the vicinity of the potential UST. DOT plans indicate proposed fill in this area. Because this is a fill area, most of the impacted soil will not likely be disturbed. However, impacted soil will be generated by UST removal work, any soil grading work below the existing grade, and during utility line installations in the aforementioned areas. Impacted soil that is removed should be properly managed and disposed at a permitted facility. The UST system and its contents should also be removed and disposed in accordance with NCDENR regulations.

#### 5.0 Signature Page

This report was prepared by:

Dave Graham Project Geologist for Hart and Hickman, PC

This report was reviewed by:

Matt Bramblett, PE

Principal and Project Manager for


Hart and Hickman, PC

#### Table 1 Soil Analytical Results Page Distributing Company, Inc., Parcel #169 Fayetteville, North Carolina H&H Job No. ROW-203

Sample ID	169-1	169-2	169-3	169-4	169-5	169-6	169-7	169-8	169-9	169-10	NCDENR
Sample Depth (ft)	2-4	0-2	2-4	2-4	2-4	4-6	2-4	2-4	2-4	4-6	Action
Sample Date Units	12/10/2008	12/10/2008	12/10/2008	12/10/2008	12/10/2008	12/10/2008	12/10/2008	12/10/2008	12/10/2008	12/10/2008	Level
OTING	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
TPH-DRO/GRO (8015B) Diesel-Range Organics (DRO) Gasoline-Range Organics (GRO)	<6.17 <5.82	<b>13.4</b> <6.01	<6.59 <6.62	<6.67 <5.08	<b>32.9</b> <5.39	<6.09 <6.72	<6.47 <5.70	<6.18 <5.89	<6.62 <5.83	<6.54 <5.96	10 10

EPA Method follows parameter in parenthesis; Bold indicates concentration exceeds the NC DENR Action Level TPH=total petroleum hydrocarbons

GRO samples were prepared using EPA Method 5035.







U.S.G.S. QUADRANGLE MAP

FAYETTEVILLE, NC 1957/1987

7.5 MINUTE SERIES (TOPOGRAPHIC)

TITLE

SITE LOCATION MAP

PROJECT

PARCEL #169 FAYETTEVILLE, NORTH CAROLINA



DATE:

12-16-08

**REVISION NO:** 


JOB NO: **ROW-203**  FIGURE:


1

0

Appendix A

NC DOT Preliminary Plan





## Appendix B

Schnabel Engineering Geophysical Survey Report





Phone (336) 274-9456 Fax (336) 274-9486 www.schnabel-eng.com

December 16, 2008

Mr. Matt Bramblett, P.E. Hart & Hickman, PC 2923 South Tryon Street, Suite 100 Charlotte, NC 28203

Via email (pdf)

RE:

State Project: U-2810C

WBS Element: 34866.1.1 County: Cumberland

Description: SR 1003 (Camden Road) from SR 1290 (King Charles Road) to north

of SR 1007 (Owen Drive)

SUBJECT:

Report on Geophysical Surveys of Parcel 169

Schnabel Engineering Project No. 08210020.06

Dear Mr. Bramblett:

This letter contains our report on the geophysical surveys we conducted on the subject property. We understand this letter report will be included as an appendix in your report to the NCDOT. The report includes one 8.5x11 color figure and two 11x17 color figures.

#### 1.0 INTRODUCTION

Schnabel Engineering conducted geophysical surveys on November 18, 20, 24, and 25, 2008, in the accessible areas of the proposed right-of-way (ROW) sections of Parcel 169 (Page Distributing Company, Inc. Property, Jason's Auto Sales) under our 2008 contract with the NCDOT. Parcel 169 is located on the southwest quadrant of the intersection SR 1003 (Camden Road) and SR 1007 (Owen Drive). The work was conducted at the location indicated by Hart & Hickman and the NCDOT to support their environmental assessment of the subject parcel. The purpose of the geophysical surveys was to locate possible metal underground storage tanks (UST's) and associated metal product lines in the accessible areas of the site.

#### 2.0 FIELD METHODOLOGY

Locations of geophysical data points were obtained using a sub-meter Trimble Pro-XRS DGPS system. References to direction and location in this report are based on the US State Plane 1983 system, North Carolina 3200 zone, using the NAD 83 datum, with units in US survey feet. The locations of existing site features (building, curbs, signs, etc.) were recorded for later correlation with the geophysical data and for location references to the NCDOT drawings. The geophysical investigation consisted of an electromagnetic (EM) induction survey using a Geonics EM61-MK2 instrument, and a ground-penetrating radar survey using a Geophysical Survey Systems SIR-3000 system equipped with a 400 MHz antenna.

The EM61 data were collected along parallel survey lines spaced about 2.5 feet apart. The EM61 and DGPS data were recorded digitally using a field computer and later transferred to a desktop computer for data processing. The GPR data were collected along survey lines spaced one to two feet apart in orthogonal directions over anomalous EM readings not attributed to known metallic features. One possible UST was located and marked on the ground at this site. Pictures of the location of this possible UST as marked in the field are shown in Figure 1.

Preliminary results were sent to David Graham and Wil Pineda of Hart & Hickman on December 5, 2008.

#### 3.0 <u>DISCUSSION OF RESULTS</u>

The contoured EM61 data are shown on Figures 2 and 3. The EM61 early time gate results are plotted on Figure 2. The early time gate data provide the most sensitive detection of metal object targets, regardless of size. Figure 3 shows the difference between the response of the top and bottom coils of the EM61 instrument (differential response). The difference is taken to remove the effect of surface and very shallowly buried metallic objects. Typically, the differential response emphasizes anomalies from deeper and larger objects such as UST's.

The early time gate and differential results show several anomalies not attributed to known site features (Figures 2 and 3). Eight areas were surveyed with GPR, and the GPR data indicated the

presence of utilities and buried metal debris. The GPR data also indicated a possible UST located inside of the NCDOT ROW/easement on the northern side of the parcel at 2,027,804E, 461,408N. An example GPR image showing the reflection from the possible UST is shown on Figures 2 and 3. Figures 2 and 3 also include the location of the possible UST as marked in the field. The GPR data indicate that the possible UST is buried approximately 1 to 2 feet below the ground surface, and it is about 4 feet in diameter and about 10.5 feet long, equivalent to a capacity of about 1000 gallons.

#### 4.0 CONCLUSIONS

Our evaluation of the geophysical data collected on Parcel 169 of Project U-2810C in Fayetteville, NC indicates the following:

• The geophysical data indicate the presence of a possible UST inside of the NCDOT ROW/easement on Parcel 169. The possible UST is about 1000-gallon capacity and is buried approximately 1 to 2 feet below ground surface.

#### 5.0 <u>LIMITATIONS</u>

These services have been performed and this report prepared for Hart & Hickman and the North Carolina Department of Transportation in accordance with generally accepted guidelines for conducting geophysical surveys. It is generally recognized that the results of geophysical surveys are non-unique and may not represent actual subsurface conditions.

Thank you for the opportunity to serve you on this project. Please call if you need additional information or have any questions.

Sincerely,

SCHNABEL ENGINEERING SOUTH, P.C.

Jeremy S. Strohmeyer, P.G.


Project Manager

Edward D. Billington, P.G.


Senior Vice President

JW/JS/NB

Attachment: Figures (2)
FILE: G-2008 PROJECTS 08210020 (NCDOT 2008 GEOTECH UNIT SERVICES) 08210020 06 (U-2810C, CUMBERLAND COUNTY) REPORT PARCEL 135 REPORT ON PARCEL 135 DOC



Parcel 169 – Jason's Auto Sales, looking southeast UST: 4' x 10.5'




Parcel 169 – Jason's Auto Sales, looking northeast UST: 4' x 10.5'



NC Department of Transportation Geotechnical Engineering Unit

State Project No. U-2810C Cumberland County, North Carolina PARCEL 169
PHOTOS OF PROBABLE
UST LOCATION

FIGURE 1




Note: The contour plot shows the earliest and most sensitive time gate of the EM61 bottom coil/channel in millivolts (mV). The EM data were collected on November 18 and 20, 2008, using a Geonics EM61-MK2 instrument. Positioning for the EM61 survey was provided using a submeter Trimble ProXRS DGPS system. Coordinates are in the US State Plane 1983 System, North Carolina Zone 3200, using the NAD 1983 datum. GPR data were acquired on November 24 and 25, 2008, using a Geophysical Survey Systems SIR 3000 equipped with a 400 MHz antenna.



State Project No. U-2810C Cumberland County, North Carolina PARCEL 169 EM61 EARLY TIME GATE RESPONSE

FIGURE 2



Note: The contour plot shows the difference, in millivolts (mV), between the readings from the top and bottom coils of the EM61. The difference is taken to reduce the effect of shallow metal objects and emphasize anomalies caused by deeper metallic objects, such as drums and tanks. The EM data were collected on November 18 and 20, 2008, using a Geonics EM61-MK2 instrument. Positioning for the EM61 survey was provided using a submeter Trimble ProXRS DGPS system. Coordinates are in the US State Plane 1983 System, North Carolina 3200 Zone, using the NAD 1983 datum. GPR data were acquired on November 24 and 25, 2008, using a Geophysical Survey Systems SIR 3000 equipped with a 400 MHz antenna.



NC Department of Transportation Geotechnical Engineering Unit

State Project No. U-2810C Cumberland County, North Carolina PARCEL 169 EM61 DIFFERENTIAL RESPONSE

FIGURE 3

Appendix C

**Soil Boring Logs** 



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-1**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

DEPTH (ft)	OVERT (%)	BLOW COUNT		OVA (ppm)	LITHOLOGY	MAT	TERIAL DESCRIPTION		WELL DIAGRAM	DEPTH
	7	BLC	BKG.	SAMP.	5					
- 10	00		0	0		(SW-SM) Tan-brown, fin	e SAND, trace silt, dry			
- 10 -	00		0	0						-
5 - 10	00		0	0						-
- - 10 -	00		0	0						
- - 10	00		0	0		(SW) Tan, fine SAND, dr	у			-
- - 10	00		0	0						-
-						Botton	n of borehole at 12.0 feet.			-
										-
15-										_
-										-
										-
_										
20-										-2
	G CC	ONTRAC	TOR:	SEI		BORING	S STARTED 12/10/08	Remar	 ks:	
	IG/ N NG M D BY	METHOD: METHOD:	Geo	probe		Push Sleeve BORING TOTAL SURFAGE	G COMPLETED: 12/10/08 DEPTH: 12 CE ELEV: TO WATER:	1	ole hand-augered to 5 feet. e collected from 2-4 feet.	

#### Remarks:



3334 Hillsborough St... Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-2**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

DEPTH (ft)	RECOVERY (%)	BLOW COUNT		OVA (ppm)	LITHOLOGY	MATERIAL DESCRIPTION	WELL DIAGRAM	DEPTH (ft)
	REC	BL(	BKG	SAMP.	=			
-	100		0	0.1		(SW-SM) Tan-brown, fine SAND, trace silt, dry		-
	100		0	0				
5 -	100		0	0				- - 5 -
-	100		0	0		(C)A) Top See CAND		_
10	100		0	0		(SW) Tan, fine SAND, dry		- - - -10
- - -	100		0	0				-
-						Bottom of borehole at 12.0 feet.		- 1
-								-
-	- 1							-
15-								-15
-								-
								-
-								_
-								-
								-
20-	1							-20
DDU	1110	ONTRAG	700	251		DODING STARTER 45/45/65	<del></del>	

DRILLING CONTRACTOR: SEI

DRILL RIG/ METHOD: Geoprobe / Direct-Push Sleeve

SAMPLING METHOD: DPT Sleeves

LOGGED BY GAB

DRAWN BY:

-06 OF

BORING - HART HICKMAN GDT - 12/23/08 10:12 - S:VAAA-MASTER GINT PROJECTSIROW-203/PARCEL 169.GPJ

BORING STARTED 12/10/08 BORING COMPLETED: 12/10/08

TOTAL DEPTH: 12 SURFACE ELEV: DEPTH TO WATER: Remarks:



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-3**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

						EGGATION. 1 ayetteville, NC		
DEPTH (ft)	RECOVERY (%) BLOW COUNT			OVA (ppm)	LITHOLOGY	MATERIAL DESCRIPTION	WELL DIAGRAM	DEPTH (ft)
_0_	REC	BLC	BKG.	SAMP.	5			
- -	100		0	0		(SW-SM) Tan-brown, fine SAND, trace silt, dry		- - -
-	100		0	0				-
5 -	100		0	0				- - 5 -
	100		0	0		(SW) Tan, fine SAND, dry		-
10-	100		0	0				- 10
- - -	100		0	0				-10 - - -
-						Bottom of borehole at 12.0 feet.		
-								E
- 15-								- -15
-								- 13
-								-
-								-
								F
20								-
20-	"""	CNITDAC				PORING STARTER 40/40/00		-20

DRILLING CONTRACTOR: SEI

DRILL RIG/ METHOD: Geoprobe / Direct-Push Sleeve

SAMPLING METHOD: DPT Sleeves

**LOGGED BY GAB** 

OG OF BORING - HART HICKMAN, GDT - 12/23/08 10:12 - S.YAAA-MASTER GINT PROJECTS/ROW-203/PARCEL 169, GPJ DRAWN BY:

**BORING STARTED 12/10/08 BORING COMPLETED: 12/10/08** 

**TOTAL DEPTH: 12** SURFACE ELEV: **DEPTH TO WATER:**  Remarks:



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-4**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

		1	,					
DEPTH (ft)	RECOVERY (%)	BLOW COUNT		OVA (ppm)	LITHOLOGY	MATERIAL DESCRIPTION	WELL DIAGRAM	DEPTH (ft)
	REC	BL(	BKG.	SAMP.				
-	100		0	0		CONCRETE (SW-SM) Tan-brown, fine SAND, trace silt, dry		-
	100		0	0				-
5 -	100		0	0				- - 5 -
	100		0	0		(SW) Tan-white, fine SAND, dry		-
-	100		0	0				_
10- - - -	100		0	0				-10 - - -
						Bottom of borehole at 12.0 feet.		
_								_
22								<del></del>
15~								-15
4								
-								-
_								_
1 -								-
20-								
20-								-20

**DRILLING CONTRACTOR: SEI** 

DRILL RIG/ METHOD: Geoprobe / Direct-Push Sleeve

SAMPLING METHOD: DPT Sleeves

LOGGED BY GAB

OG OF BORING - HART HICKMAN, GDT - 12/23/08 10:12 - S. AAA-MASTER GINT PROJECTSIROW-2031PARCEL 169, GPJ DRAWN BY:

**BORING STARTED 12/10/08** 

**BORING COMPLETED: 12/10/08 TOTAL DEPTH**: 12

SURFACE ELEV: DEPTH TO WATER: Remarks:



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-5**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

DEPTH (ft)	RECOVERY (%)	BLOW COUNT		OVA (ppm)	LITHOLOGY	MATERIAL DESCRIPTION	WELL DIAGRAM	DEPTH (ft)
	REC	BLC	BKG.	SAMP.				<u> </u>
-	100		0	0	9 4 9 9	CONCRETE (SW-SM) Tan-brown, fine SAND, trace silt, dry		
	100		0	0				
5 -	100		0	0				_ _ 5 _
	100		0	0				
10-	100		0	0				- - - -10
-	100		0	0				
-						Bottom of borehole at 12.0 feet.		- 1
_								
								-
15-								-15
-								- 1
7.7								+
-								-
20-								-20
DRILL	ING C	ONTRAC	TOR.	SEL		BORING STARTED 12/10/08 Pemar	kei	

**DRILLING CONTRACTOR: SEI** 

DRILL RIG/ METHOD: Geoprobe / Direct-Push Sleeve

**SAMPLING METHOD: DPT Sleeves** 

OG OF BORING - HART HICKMAN, GDT - 12/23/08 10:12 - S:VAAA-MASTER GINT PROJECTSIROW-203/PARCEL 169.GPJ **LOGGED BY GAB** 

DRAWN BY:

**BORING STARTED** 12/10/08 **BORING COMPLETED: 12/10/08** 

**TOTAL DEPTH: 12** SURFACE ELEV: **DEPTH TO WATER:** 



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-6**

**PROJECT:** Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

DEPTH (ft)  RECOVERY (%)	BLOW COUNT		OVA (ppm)	гітно <u>г</u> ову	WE MATERIAL DESCRIPTION	LL DIAGRAM
REC	BLC	BKG.	SAMP.			
- - 100		0	0		(GP) GRAVEL	-
100		0	0		(SW-SM) Tan-brown, fine SAND, trace silt, dry	- - -
5 — 100		0	0.2			
100		0	0.2			
100		0	0			-
- - 100		0	0			-
					Bottom of borehole at 12.0 feet.	- - - -
15-						-
						E
20-						- - -:
DRILLING C DRILL RIG/ SAMPLING LOGGED B' DRAWN BY:	METHOD: METHOD: 'GAB	: Geo	probe		BORING STARTED 12/10/08 Push Sleeve BORING COMPLETED: 12/10/08 TOTAL DEPTH: 12 SURFACE ELEV: DEPTH TO WATER:  Remarks: Borehole hand-aug Sample collected fi	ered to 5 feet. rom 4-6 feet.

#### Remarks:



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-7**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

			_					1
DEРТН (ft)	RECOVERY (%)	BLOW COUNT		OVA (ppm)	LITHOLOGY	MATERIAL DESCRIPTION	WELL DIAGRAM	DEPTH (ft)
	REC	BLO	BKG.	SAMP.	5			
-0- - -	100		0	0		(SW-SM) Tan-brown, fine SAND, trace silt, dry		-
-	100		0	0				_ _ _
5	100		0	0				- - 5
-	100		0	. 0		(SW) Tan-white, fine SAND, dry		
-	100		0	0				
10	100		0	0				-10 -
						Bottom of borehole at 12.0 feet.		
								_
-								-
15-								-15
-								-
-								
-								-
-								-
20-								-20
DRIL	LING	CONTRAC	TOR:	SEI		BORING STARTED 12/10/08 Re	marks:	-
DRILI	L RIG		: Geo	probe			rehole hand-augered to 5 feet. mple collected from 2-4 feet.	

**LOGGED BY GAB** 

DRAWN BY:

-0G OF

TOTAL DEPTH: 12 SURFACE ELEV: **DEPTH TO WATER:** 



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-8**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

DEPTH (ft)	RECOVERY (%)	BLOW COUNT		OVA (ppm)	LITHOLOGY	MA	TERIAL DESCRIPTION		WELL DIAGRAM	DEPTH		
	REC	BL(	BKG.	SAMP.								
-	100		0	0		(SW) Tan-brown, fine S	AND, dry					
	100		0	0						- - -		
5 -	100		0	0						 5 		
	100		0	0		(SW) Tan, fine SAND, d	ry			-		
10	100		0	0								
10	100		0	0						-10  -		
-						Bottor	m of borehole at 12.0 feet.			-		
_												
-												
15-										15		
-												
	3 T											
1-										-		
7-												
-										-		
-										L		
20-										-20		
DRILL		CONTRAC					G STARTED 12/10/08	Rema	rks:			
DRILL		METHOD METHOD					G COMPLETED: 12/10/08 DEPTH: 12	Boreh	ole hand-augered to 5 feet. le collected from 2-4 feet.			
LOGG	ED B	Y GAB				SURFA	CE ELEV:	Janipi	is collected from 2-4 lest.			
DRAV	VN BY	<b>7</b> :				DEPTH	TO WATER:					

#### Remarks:



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

#### **BORING NUMBER 169-9**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

			,				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
DEPTH (ft)	RECOVERY (%)	BLOW COUNT		OVA (ppm)	LITHOLOGY	MA	TERIAL DESCRIPTION	WELL DIAGRAM	DEPTH (ft)
	REC	BLC	BKG.	SAMP.	] 5				
-	100		0	0		(SW-SM) Tan-brown, fi	ne SAND, trace silt, dry		
	100		0	0.1					
5 — - -	100		0	0.1					- - 5 -
	100		0	0.1		(SW) Tan-white, fine SA	AND, dry		
- - 10-	100		0	0					_ _ _ _10
;- ;-	100		0	0					_
-						Botto	m of borehole at 12.0 feet.		-
=									-
15-									- -15
-									-
-								-	-
-									
_									_
20-									- -20
DD11 1				0-1					

DRILLING CONTRACTOR: SEI

DRILL RIG/ METHOD: Geoprobe / Direct-Push Sleeve

**SAMPLING METHOD: DPT Sleeves** 

OG OF BORING - HART HICKMAN GDT - 12/23/08 10:12 - 5/4AA-MASTER GINT PROJECTSIROW-203/PARCEL 169.GPJ **LOGGED BY GAB** DRAWN BY:

**BORING STARTED 12/10/08 BORING COMPLETED: 12/10/08** 

**TOTAL DEPTH: 12** SURFACE ELEV: **DEPTH TO WATER:** 

#### Remarks:



3334 Hillsborough St. Raleigh, North Carolina 27607 919-847-4241(p) 919-847-4261(f)

### **BORING NUMBER 169-10**

PROJECT: Cumberland County PSAs

JOB NUMBER: ROW-203 LOCATION: Fayetteville, NC

								_
DEPTH (ft)	RECOVERY (%)	BLOW COUNT		OVA (ppm)	LITHOLOGY	MATERIAL DESCRIPTION	WELL DIAGRAM	(ft)
	REC	BLC	BKG.	SAMP.	5			-0-
-	100		0	0		(SM) Brown-black, silty fine SAND, dry		
-	100		0	0				
5 — -	100		0	0.1		(SW) Tan, fine SAND, dry		5
	100		0	0.1				
- - 10-	100		0	0		(SW) White, fine SAND, dry	-1	10
	100		0	0.1			-	
-						Bottom of borehole at 12.0 feet.	-	
-							-	
15-							_1	15
							[ E	
							<u> </u>	
-							-	
-								
20-	1						-2	20

**DRILLING CONTRACTOR: SEI** 

DRILL RIG/ METHOD: Geoprobe / Direct-Push Sleeve

**SAMPLING METHOD: DPT Sieeves** 

OG OF BORING - HART HICKMAN, GDT - 12/23/08 10:12 - S.\AAA-MASTER GINT PROJECTS/ROW-203/PARCEL 169.GPJ **LOGGED BY GAB** 

DRAWN BY:

**BORING STARTED 12/10/08 BORING COMPLETED: 12/10/08** 

**TOTAL DEPTH: 12 SURFACE ELEV: DEPTH TO WATER:** 

#### Remarks:

Appendix D

**Laboratory Analytical Report** 



Mr. David Graham Hart & Hickman 2923 S. Tryon St. Suite 100 Charlotte NC 28203 Report Number: G609-46

Client Project: Row-203

Dear Mr. Graham:

Enclosed are the results of the analytical services performed under the referenced project. The samples are certified to meet the requirements of the National Environmental Laboratory Accreditation Conference Standards. Copies of this report and supporting data will be retained in our files for a period of five years in the event they are required for future reference. Any samples submitted to our laboratory will will be retained for a maximum of thirty (30) days from the date of this report unless other arrangements are requested.

If there are any questions about the report or the services performed during this project, please call SGS at (910) 350-1903. We will be happy to answer any questions or concerns which you may have.

Thank you for using SGS Environmental Services for your analytical services. We look forward to working with you again on any additional analytical needs which you may have.

Sincerely,

SGS Environmental Services, Inc.

Project Manager

Lori Lockamy

#### SGS Environmental Services, Inc.

# List of Reporting Abbreviations And Data Qualifiers

B = Compound also detected in batch blank

BOL = Below Quantification Limit (RL or MDL)

DF = Dilution Factor

Dup = Duplicate

P/D = Detected, but RPD is > 25/40% between results in dual column method.

E = Estimated concentration, exceeds calibration range.

J = Estimated concentration, below calibration range and above MDL

LCS(D) = Laboratory Control Spike (Duplicate)

MDL = Method Detection Limit

MS(D) = Matrix Spike (Duplicate)

PQL = Practical Quantitation Limit

RL/CL = Reporting Limit / Control Limit

RPD = Relative Percent Difference

mg/kg = milligram per kilogram, ppm, parts per million

ug/kg = micrograms per kilogram, ppb, parts per billion

mg/L = milligram per liter, ppm, parts per million

ug/L = micrograms per liter, ppb, parts per billion

% Rec = Percent Recovery

% soilds = Percent Solids

#### Special Notes:

- 1) Metals and mercury samples are digested with a hot block, see the standard operating procedure document for details.
- 2) Uncertainty for all reported data is less than or equal to 30 percent.

#### SGS Environmental Services, Inc.

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-1 (2-4)

Client Project ID: Row-203

Lab Sample ID: G609-46-1A

Lab Project ID: G609-46 Report Basis: Dry Weight Analyzed By: DVG

Date Collected: 12/10/2008 11:45

Date Received: 12/12/2008

Matrix: Soil Solids 93.63

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	5.82		mg/Kg	1	12/18/08 15:04
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits
BFB		100	100	99.9	i iug	70-130

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015 Instrument ID: GC4

Analyst: DVG

Prep Method: 5035 Initial Wt/Vol: 5.51 g Final Volume: 5 mL

Analyst: 014

Reviewed By: M

NC Certification #481 N.C. Certification #481

#### SGS Environmental Services, Inc.

#### Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-2 (0-2)

Client Project 1D: Row-203

Lab Sample ID: G609-46-2A

Lab Project ID: G609-46

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected: 12/10/2008 12:00

Date Received: 12/12/2008

Matrix: Soil

Solids 92.88

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL.	6.01		mg/Kg	1	12/18/08 17:17
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits
BFB		100	95	95.5		70-130
Comments:						

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015 Instrument ID: GC4

Analyst: DVG

Prep Method: 5035 Initial Wt/Vol: 5.37 g Final Volume: 5 mL

Reviewed By: GRO

Page 4 of 31

NC Certification #481 N.C. Certification #481

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-3 (2-4)

Client Project ID: Row-203

Lab Sample ID: G609-46-3A

Lab Project ID: G609-46

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected: 12/10/2008 12:20

Date Received: 12/12/2008

Matrix: Soil

Solids 91.71

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	6.62		mg/Kg	1	12/18/08 18:36
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits
BFB		100	100	99.6	9	70-130

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015

Instrument ID: GC4

Analyst: DVG

Prep Method: 5035 Initial Wt/Vol: 4.94 g

Final Volume: 5 mL

Analyst: DVA

Reviewed By: GRO

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-4 (2-4)

Client Project ID: Row-203

Lab Sample ID: G609-46-4A

Lab Project ID: G609-46

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected: 12/10/2008 12:35

Date Received: 12/12/2008

Matrix: Soil

Solids 91.98

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	5.08		mg/Kg	1	12/18/08 19:30
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits
BFB		100	100	99.5	riag	70-130

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015 Instrument ID: GC4

Analyst: DVG

Prep Method: 5035 Initial Wt/Vol: 6.42 g

Final Volume: 5 mL

Analyst: 0V4

Reviewed By: Market

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-5 (2-4)

Client Project ID: Row-203

Lab Sample ID: G609-46-5A

Lab Project ID: G609-46

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected: 12/10/2008 12:50

Date Received: 12/12/2008

Matrix: Soil

Solids 92.85

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	5.39		mg/Kg	1	12/18/08 19:56
Surrogate Spike Results		الماماما	Donald	Denever	Ela «	Limito
BFB		Added 100	<b>Result</b> 95	<b>Recovery</b> 94.8	Flag	<b>Limits</b> 70-130

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015

Instrument ID: GC4

Analyst: DVG

Prep Method: 5035

Initial Wt/Vol: 5.99 g

Final Volume: 5 mL

DUG Analyst: \_\_\_

Reviewed By: <u>(</u>

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-6 (4-6)

Client Project ID: Row-203

Lab Sample ID: G609-46-6A

Lab Project ID: G609-46

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected: 12/10/2008 13:10

Date Received: 12/12/2008

Matrix: Soil

Solids 95.42

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	6.72		mg/Kg	1	12/18/08 20:23
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits
BFB		100	98	98.3	riag	70-130

#### Comments:

#### Batch Information

Analytical Batch: VP121808 Analytical Method: 8015

Instrument ID: GC4

Analyst: DVG

Prep Method: 5035

Initial Wt/Vol: 4.68 g

Final Volume: 5 mL

Analyst:

Reviewed By: 1 Page 8 of 31

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Analyzed By: DVG

Client Sample ID: 169-7 (2-4)

Client Project ID: Row-203 Date Collected: 12/10/2008 13:45

Lab Sample ID: G609-46-7A Date Received: 12/12/2008

Lab Project ID: G609-46 Matrix: Soil
Report Basis: Dry Weight Solids 93.92

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	5.70		mg/Kg	1	12/18/08 20:49
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits
BFB		100	100	99.5	1 149	70-130

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Prep Method: 5035
Analytical Method: 8015 Initial Wt/Vol: 5.6 g
Instrument ID: GC4 Final Volume: 5 mL

ument ID: GC4 Final Volume: 5
Analyst: DVG

Analyst: \_\_ŊVζ

Reviewed By: GRC Page 9 of 31

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Analyzed By: DVG

Client Sample ID: 169-8 (2-4)

Client Project ID: Row-203 Date Collected: 12/10/2008 14:30

Lab Sample ID: G609-46-8A Date Received: 12/12/2008

Lab Project ID: G609-46 Matrix: Soil
Report Basis: Dry Weight Solids 92.76

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	5.89		mg/Kg	1	12/18/08 21:16
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits
BFB		100	105	105	riag	70-130

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Prep Method: 5035
Analytical Method: 8015 Initial Wt/Vol: 5.49 g
Instrument ID: GC4 Final Volume: 5 mL

Iment ID: GC4 Final Volume: Analyst: DVG

Analyst: V4\_\_\_

Reviewed By: M

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-9 (2-4)

Client Project ID: Row-203

Lab Sample ID: G609-46-9A

Lab Project ID: G609-46

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected: 12/10/2008 15:00

Date Received: 12/12/2008

Matrix: Soil

Solids 93.49

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	5.83		mg/Kg	1	12/18/08 21:42
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits
BFB		100	97	97.3	3	70-130

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015

Instrument ID: GC4

Analyst: DVG

Prep Method: 5035

Initial Wt/Vol: 5.5 g Final Volume: 5 mL

Analyst: DVa\_\_\_

Reviewed By:

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169- 10 (4-6)

Client Project ID: Row-203

Lab Sample ID: G609-46-10A

Lab Project ID: G609-46

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected: 12/10/2008 15:30

Date Received: 12/12/2008

Matrix: Soil

Solids 94.85

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed	
Gasoline Range Organics	BQL	5.96		mg/Kg	1	12/18/08 22:09	
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits	
BFB		100	93	93.4		70-130	

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015

Instrument ID: GC4

Analyst: DVG

Prep Method: 5035 Initial Wt/Vol: 5.31 g

Final Volume: 5 mL

Analyst: 0V4

Reviewed By: GRO
Page 12 of 31

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: Method Blank

Client Project ID:

Lab Sample ID: VBLK4121808A

Lab Project ID:

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected:

Date Received:

Matrix: Soil

Solids 100.00

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed	
Gasoline Range Organics	BQL	6.00		mg/kg	1	12/18/08 06:12	
Surrogate Spike Results		Added	Result	Recovery	Flag	Limits	
BFB		100	95	94.9		70-130	

# Comments:

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015 Instrument ID: GC4

Analyst: DVG

Prep Method: 5035 Initial Wt/Vol: 5 g Final Volume: 5 mL

Analyst: 014

Reviewed By: MGRO

# QC Results for Total Petroleum Hydrocarbons by GC/FID

Client Sample ID: Batch QC

Analyzed By: DVG

Lab Sample ID: g609-44-1a

Matrix: Soil

LCS ID: LCS4121808A / VP121808

Solids 98.47

#### MS/MSD

Analyte	Sample	Spiked	MS	REC	Spiked	MSD	REC		RPD	
	MG/KG	MG/KG	MG/KG	% #	MG/KG	MG/KG	%	#	%	#
		L.		(70-130%)			(70-130%	)	(30%)	
				Lana	1 40	110	1 02 4	7	5.04	$\rightarrow$
GRO	BQL	16	15.8	98.8 🗸	16	14.9	93.1	$\leq$	5.94	

#### LCS

Analyte	Spiked	Result	REC	LIMITS		
•	MG/KG	MG/KG MG/KG		Lower	Upper	
GRO	16	18	109 🗸	70	130	

Comments:

Reviewed By:

Page 14 of 31

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: Method Blank

Client Project ID:

Lab Sample ID: VBLK4121808B

Lab Project ID:

Report Basis: Dry Weight

Analyzed By: DVG

Date Collected:

Date Received:

Matrix: Soil

Solids 100.00

Analyte	Result	RL		Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	6.00		mg/kg	1	12/18/08 16:50
Surrogate Spike Results		Added 100	Result 113	Recovery 113	Flag	<b>Limits</b> 70-130
51 5						

#### Comments:

#### **Batch Information**

Analytical Batch: VP121808 Analytical Method: 8015

Instrument ID: GC4

Analyst: DVG

Prep Method: 5035 Initial Wt/Vol: 5 g

Final Volume: 5 mL

Analyst: DVG

Reviewed By: GRO
Page 15 of 31

# QC Results for Total Petroleum Hydrocarbons by GC/FID

Client Sample ID: Batch QC

Analyzed By: DVG

Lab Sample ID: g609-46-2a

Matrix: Soil

LCS ID: LCS4121808B / VP121808

Solids 92.88

#### MS/MSD

Analyte	Sample MG/KG	Spiked MG/KG	MS MG/KG	REC #	Spiked MG/KG	MSD MG/KG	REC % #	RPD % #
				(70-130%)			(70-130%)	(30%)
GRO	BQL	16	16.4	103 🗸	16	16.3	102 🗸	0.976 ~

LCS

Analyte	Spiked	Result	REC		LIMITS	
Andry to	MG/KG	MG/KG	%	#	Lower	Upper
				/ 1		100
GRO	16	18	113 🗸		70	130

Comments:

Reviewed By: The

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-1 (2-4) Date Collected: 12/10/2008 11:45

Client Project ID: Row-203 Date Received: 12/12/2008

Lab Sample ID: G609-46-1D

Lab Project ID: G609-46

Solids 93.63

Description: Description of the state of th

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.17	mg/Kg	1	12/17/08 18:34
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	39.3	98.2

#### Comments:

#### **Batch Information**

Analytical Batch: EP121708 Prep batch: 13228

Analytical Method: 8015 Prep Method: 3541

Instrument: GC6 Prep Date: 12/15/08

Analyst: FAW Initial Prep Wt/Vol: 34.62 G

Analyst: EAW Initial Prep Wt/Vol: 34.62 G
Prep Final Vol: 10 mL

Analyst:

Reviewed By: DRO.XLS

NC Certification #481

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-2 (0-2) Client Project ID: Row-203

Lab Sample ID: G609-46-2D Lab Project ID: G609-46 Date Collected: 12/10/2008 12:00

Date Received: 12/12/2008

Matrix: Soil Solids 92.88

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	13.4	6.59	mg/Kg	1	12/17/08 19:02
Surrogate Spike Results OTP		Spike Added 40	Control Limits 40-140	Spike Result 36	Percent Recovery 90

#### Comments:

#### **Batch Information**

Analytical Batch: EP121708
Analytical Method: 8015
Instrument: GC6
Analyst: EAW

Prep batch: 13228
Prep Method: 3541
Prep Date: 12/15/08
Initial Prep Wt/Vol: 32.69 G
Prep Final Vol: 10 mL

Analyst: \_ &

Reviewed By:

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-3 (2-4)

Client Project ID: Row-203

Date Collected: 12/10/2008 12:20

Date Received: 12/12/2008

Lab Sample ID: G609-46-3D Matrix: Soil
Lab Project ID: G609-46 Solids 91.71

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.59	mg/Kg	1	12/17/08 19:30
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	34.5	86.3

#### Comments:

#### **Batch Information**

Analytical Batch: EP121708 Prep batch: 13228

Analytical Method: 8015 Prep Method: 3541

Instrument: GC6 Prep Date: 12/15/08

Analyst: EAW Initial Prep Wt/Vol: 33.08 G

Prep Final Vol: 10 mL

Analyst: \_ \_ \_

Reviewed By: ORO,XLS

# **Results for Total Petroleum Hydrocarbons** by GC/FID 8015

Date Collected: 12/10/2008 12:35 Client Sample ID: 169-4 (2-4)

Date Received: 12/12/2008 Client Project ID: Row-203

Matrix: Soil Lab Sample ID: G609-46-4D Solids 91.98 Lab Project ID: G609-46 Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.67	mg/Kg	1	12/17/08 19:58
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	35.2	88

#### Comments:

#### **Batch Information**

Prep batch: 13228 Analytical Batch: EP121708 Prep Method: 3541 Analytical Method: 8015 Prep Date: 12/15/08 Instrument: GC6 Initial Prep Wt/Vol: 32.62 G Analyst: EAW

Prep Final Vol: 10 mL

Analyst: \_ C

Reviewed By

NC Certification #481

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-5 (2-4)
Client Project ID: Row-203

Lab Sample ID: G609-46-5D Lab Project ID: G609-46 Date Collected: 12/10/2008 12:50

Date Received: 12/12/2008

Matrix: Soil Solids 92.85

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	32.9	6.51	mg/Kg	1	12/17/08 21:24
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	35.9	89.7

#### Comments:

#### **Batch Information**

Analytical Batch: EP121708
Analytical Method: 8015
Instrument: GC6

Analyst: EAW

Prep batch: 13228 Prep Method: 3541 Prep Date: 12/15/08 Initial Prep Wt/Vol: 33.08 G

Prep Final Vol: 10 mL

Analyst: \_\_\_\_

Reviewed By

y: DROXIS

N.C. Certification #481

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-6 (4-6)

Date Collected: 12/10/2008 13:10

Client Project ID: Row-203 Date Received: 12/12/2008

Lab Sample ID: G609-46-6D Matrix: Soil
Lab Project ID: G609-46 Solids 95.42

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.09	mg/Kg	1	12/17/08 21:53
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	34.8	87.1

#### Comments:

#### **Batch Information**

Analytical Batch: EP121708 Prep batch: 13228

Analytical Method: 8015 Prep Method: 3541

Instrument: GC6 Prep Date: 12/15/08

Analyst: EAW Initial Prep Wt/Vol: 34.41 G

Prep Final Vol: 10 mL

Analyst: \_ C

Reviewed By:

NC Certification #481

N.C. Certification #481

Page 22 of 31

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-7 (2-4)

Client Project ID: Row-203

Lab Sample ID: G609-46-7D Lab Project ID: G609-46 Date Collected: 12/10/2008 13:45

Date Received: 12/12/2008

Matrix: Soil Solids 93.92

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.47	mg/Kg	1	12/17/08 22:21
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	36	90

#### Comments:

#### **Batch Information**

Analytical Batch: EP121708 Analytical Method: 8015

Instrument: GC6
Analyst: EAW

Prep batch: 13228 Prep Method: 3541 Prep Date: 12/15/08

Initial Prep Wt/Vol: 32.9 G Prep Final Vol: 10 mL

Analyst: \_\_\_

Reviewed By: DRO.XLS
Page 23 of 31

NC Certification #481

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-8 (2-4)

Client Project ID: Row-203

Lab Sample ID: G609-46-8D

Lab Project ID: G609-46

Date Collected: 12/10/2008 14:30

Date Received: 12/12/2008

Matrix: Soil

Solids 92.76

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.18	mg/Kg	1	12/17/08 22:49
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery 85.3
OTP		40	40-140	34.1	65.3

#### Comments:

#### **Batch Information**

Analytical Batch: EP121708 Analytical Method: 8015

Instrument: GC6

Analyst: EAW

Prep batch: 13228 Prep Method: 3541

Prep Date: 12/15/08 Initial Prep Wt/Vol: 34.91 G

Prep Final Vol: 10 mL

NC Certification #481

Reviewed By:

Page 24 of 31

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: 169-9 (2-4)

Client Project ID: Row-203

Lab Sample ID: G609-46-9D

Lab Project ID: G609-46

Date Collected: 12/10/2008 15:00

Date Received: 12/12/2008

Matrix: Soil

Solids 93.49

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.62	mg/Kg	1	12/17/08 23:18
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	34.3	85.8

#### Comments:

#### **Batch Information**

Analytical Batch: EP121708 Analytical Method: 8015

Instrument: GC6
Analyst: EAW

Prep batch: 13228 Prep Method: 3541 Prep Date: 12/15/08

Initial Prep Wt/Vol: 32.32 G Prep Final Vol: 10 mL

Analyst: W

Reviewed By: PROXIS

NC Certification #481

# Results for Total Petroleum Hydrocarbons by **GC/FID 8015**

Client Sample ID: 169-10 (4-6)

Client Project ID: Row-203

Lab Sample ID: G609-46-10D

Lab Project ID: G609-46

Date Collected: 12/10/2008 15:30

Date Received: 12/12/2008

Matrix: Soil

Solids 94.85

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.54	mg/Kg	1	12/18/08 01:40
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	33.7	84.3
Comments:					

#### **Batch Information**

Analytical Batch: EP121708 Analytical Method: 8015

> Instrument: GC6 Analyst: EAW

Prep batch: 13229 Prep Method: 3541 Prep Date: 12/15/08

Initial Prep Wt/Vol: 32.25 G Prep Final Vol: 10 mL

Analyst: \_ C

NC Certification #481

N.C. Certification #481 Page 26 of 31

# Results for Total Petroleum Hydrocarbons by **GC/FID 8015**

Client Sample ID: Method Blank

Client Project ID:

Lab Sample ID: PB13228

Lab Project ID:

Date Collected:

Date Received:

Matrix: SOIL

Solids 100.00

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.25	mg/Kg	1	12/17/08 12:28
Surrogate Spike Results		Spike Added	Control Limits	Spike Result	Percent Recovery
OTP		40	40-140	38.4	96
Comments:					

#### **Batch Information**

Analytical Batch: EP121708 Analytical Method: 8015

Instrument: GC6

Analyst: EAW

Prep batch: 13228 Prep Method: 3541 Prep Date: 12/15/08

Initial Prep Wt/Vol: 32 G Prep Final Vol: 10 mL



Reviewed By: Page 27 of 31

# Results for Total Petroleum Hydrocarbons by GC/FID 8015

Client Sample ID: Method Blank

Client Project ID:

Lab Sample ID: PB13229

Lab Project ID:

Date Collected: Date Received:

Matrix: SOIL

Solids 100.00

Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.25	mg/Kg	1	12/18/08 00:43
Surrogate Spike Results OTP		Spike Added 40	Control Limits 40-140	Spike Result 34.2	Percent Recovery 85.5

#### Comments:

#### Batch Information

Analytical Batch: EP121708 Analytical Method: 8015

Instrument: GC6 Analyst: EAW Prep batch: 13229 Prep Method: 3541 Prep Date: 12/15/08

Initial Prep Wt/Vol: 32 G Prep Final Vol: 10 mL

Analyst:

Reviewed By: \_\_\_\_\_\_

# QC Results for Total Petroleum Hydrocarbons by GC/FID

Client Sample ID: Batch QC

Lab Sample ID: G609-46-9D

Batch ID: 13228

Analyzed By: EAW

Matrix: Soil

Solids 93.49

#### MS/MSD

Analyte	Sample	Spiked	MS	REC		Spiked	MSD	REC		RPD
	MG/KG	MG/KG	MG/KG	%	#	MG/KG	MG/KG	%	#	%

#### LCS

Analyte	Spiked	Spiked Result REC L		LIN	IMITS	
	MG/KG	MG/KG	% #	Lower	Upper	
DRO	62.5	61	97.6	55.3	137	

Reviewed By:

# QC Results for Total Petroleum Hydrocarbons by GC/FID

Client Sample ID: Batch QC

Lab Sample ID: G609-45-11D

Batch ID: 13229

Analyzed By: EAW

Matrix: Soil

Solids 82.48

#### MS/MSD

Analyte	Sample	Spiked	MS	REC		Spiked	MSD	REC	$\neg$	RPD
	MG/KG	MG/KG	MG/KG	%	#	MG/KG	MG/KG	%	#	%
					-					

#### LCS

Analyte	Spiked	Result	REC	LIN	IITS
	MG/KG	MG/KG	% #	Lower	Upper
DRO	62.5	56.1	89.8	55.3	137



# SGS Environmental Services Inc. **CHAIN OF CUSTODY RECORD**

SITE/PWSID#

David Graham

CONTACT

CLIENT:

PROJECT: ROW 205

REPORTS T

David Grange

P.O. NUMBER

That Hickory

INVOICE TO:

SAMPLE IDENTIFICATION

LAB NO

6-0

(4-6)

169-

FAX NO.:( QUOTE #

Locations Nationwide

• Ohio • New Jersey

www.us.sgs.com West Virginia

090815

· North Carolina Maryland Hawaii

(BSENT REMARKS Samples Received Cold? (Circle/YES OF Chain of Custody Seal. (Circle) 1. W BROKEN PAGE Temperature C: INTACT Special Deliverable Requirements; 91-603.5 Shipping Ticket No. Special Instructions Shipping Carrier; CHO 25 103 VAD reserver es Sed X × HOY × SGS Reference SAMPLE 13/13/px 10.115 Date Time 9 9 9 989 Time Time 5 U 5 6 0 °Z иши о Date N Date W M 10 M E-MAIL dychen @ harth, Lungn.c 212 MATRIX 2/2 28/2 2016 200 5.16 50/4 50/5 50L 1157 Of 21 PHONE NO: (74) 576-900 Received By: Received By: Received By: 1345 000 190 450 1500 1235 430 TIME (3/0 145 20/01/79 01/0/02 13/10/08 B/10/03 80/0/10 64/0/08 20/0/10 B1/0/03 20/0/17 80/0//01 DATE 1500 Time Time Time

SGS Environmental Services,

Fay. A	Ear (010) 350,1557
Tel: (907) 562-2343	Wilmington, NC 28405 Tel: (910) 350-1903
AK 99518	1, NC 28405
Anchorage,	Wilmingtor
☐ 200 W. Potter Drive	3 5500 Business Drive Wilmingto

2 1270 Greenbrier Street Charleston, WV 25311 Tel: (304) 346-0725 Fax: (304) 346-0761

White - Retained by Lab Yellow - Returned with Report Pink - Retained by Sampler

STD

Date Needed

Requested Turnaround Time:

Time

Date

Received By:

Time

Date

Relinquished By: (4)

□ RUSH

£0/1/kg

Date

Date

Collected/Relinquished By:(1)

Bane

Signif

Relinquished By: (2)

(h-c)

(h-1) (4-4)

> 5-691 01-631

-691

(4-1-)

2-4)

(9-4)

9-591 169-7

(h-0)

7

69

N.C. Certification #481

(2-4)

Relinquished By: (3)

Date