

CONTRACT: C203291 **ID: U-2810C**

CONTENTS:

LINE	STATION	PLAN	PROFILE	XSECTS
-L-	15+00 to 15+50	4	23	
	15+50 to 17+00	4	23	
	17+00 to 93+00	4-10	23-25	
	93+00 to 98+00	10	25,26	40-42
	98+00 to 244+84	10-21	26-31	
-Y1-	11+22 to 12+67	5	32	
-Y4-	10+37 to 12+35	10	33	
-Y6-	10+00 to 16+62	11	34	
-Y7-	10+55 to 19+20	12,22	35	
-Y9-	10+79 to 12+31	14	36	
-Y14-	8+00 to 18+32	19	37	
-RET.WALL-	15+00 to 17+10	4	38	39

NOTE: SEE SHEET 2A FOR PLAN SHEET LAYOUT AT TIME OF INVESTIGATION

STATE OF NORTH CAROLINA

**DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL UNIT**

**ROADWAY
SUBSURFACE INVESTIGATION**

STATE PROJ. 34866.1.1 I.D. U-2810 F.A. PROJ. STP-1003(22)
 COUNTY CUMBERLAND
 PROJECT DESCRIPTION FAYETTEVILLE - SR 1003 (CAMDEN RD.)
 FROM NC 59 (HOPE MILLS RD.) TO NORTH OF
 SR 1007 (OWEN DRIVE.)
INVENTORY

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	U-2810C	1	42
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
34866.1.1	STP-1003(22)	P.E.	
34866.2.2	STP-1003(22)	RW & UTIL	
34866.3.FD3	STP-1003(70)	CONSTR.	


CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WAS MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL UNIT @ 1951-250-4088. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA IS PART OF THE CONTRACT.


GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BORING. THE LABORATORY SAMPLE DATA AND THE IN SITU UNPLACED TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

This inventory is for U-2810, which includes U-2810A, U-2810B, U-2810C. Please refer to the respective portions for your needs.



INVESTIGATED BY T.P. MOOREFIELD PERSONNEL J.L. PEDRO
 CHECKED BY N.T. ROBERSON N.D. MOHS
 SUBMITTED BY N.T. ROBERSON M.L. REEDER
 DATE SEPTEMBER 2005 CONSULTANT: S&ME
J. WHITE
G. PAYNTER



DRAWN BY: T.T. WALKER, J.L. PEDRO

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IS IT CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.































NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL UNIT

ID	STATE PROJECT NO.	SHEET NO.
U-2810	34866.1J	2


SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION		GRADATION		ROCK DESCRIPTION		TERMS AND DEFINITIONS																																																										
<p>SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED OR WEATHERED EARTH MATERIALS WHICH CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND WHICH YIELDS LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (ASTM T208, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM AND BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE:</p> <p align="center"><i>VERY STIFF, GRAY SILTY CLAY, MOST WITH INTERBEDDED FINE SAND LAYERS, HIGH PLASTIC, A-7-6</i></p>		<p>WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE UNIFORMITY. INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED)</p> <p>POORLY GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.</p> <p align="center">ANGULARITY OF GRAINS</p> <p>THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS ARE DESIGNATED BY THE TERMS: <u>ANGULAR</u>, <u>SUBANGULAR</u>, <u>SUBROUNDED</u>, OR <u>ROUNDED</u>.</p>		<p>HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WHEN TESTED, WOULD YIELD SPT REFUSAL, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p> <p>WEATHERED ROCK (WR)  NON-COASTAL PLAIN MATERIAL THAT YIELDS SPT N VALUES > 100 BLOWS PER FOOT.</p> <p>CRYSTALLINE ROCK (CR)  FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.</p> <p>NON-CRYSTALLINE ROCK (NCR)  FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.</p> <p>COASTAL PLAIN SEDIMENTARY ROCK (CP)  COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.</p>		<p>ALLUVIUM (ALLUV.) - SOILS WHICH HAVE BEEN TRANSPORTED BY WATER.</p> <p>ADUJFER - A WATER BEARING FORMATION OR STRATA.</p> <p>ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND.</p> <p>ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC.</p> <p>ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE.</p> <p>CALCAREOUS (CALC.) - SOILS WHICH CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE.</p> <p>COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE.</p> <p>CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.</p> <p>DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK.</p> <p>DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL.</p> <p>DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH.</p> <p>FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE.</p> <p>FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES.</p> <p>FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL.</p> <p>FLOOD PLAIN (F.P.) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM.</p> <p>FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD.</p> <p>JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED.</p> <p>LEDGE - A SHALE-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT.</p> <p>LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS.</p> <p>MOTTLED (MOTJ) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE.</p> <p>PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM.</p> <p>RESIDUAL SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK.</p> <p>ROCK QUALITY DESIGNATION (R.Q.D.) - A MEASURE OF ROCK QUALITY DESCRIBED BY: TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.</p> <p>SAPROLITE (SAP.) - RESIDUAL SOIL WHICH RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK.</p> <p>SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, WHICH HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS.</p> <p>SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE.</p> <p>STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR B.P.F.) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS LESS THAN 0.1 FOOT PENETRATION WITH 60 BLOWS.</p> <p>STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE.</p> <p>STRATA ROCK QUALITY DESIGNATION (S.R.Q.D.) - A MEASURE OF ROCK QUALITY DESCRIBED BY: TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 10 CENTIMETERS DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE.</p> <p>TOPSOIL (T.S.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>																																																										
<p align="center">SOIL LEGEND AND AASHTO CLASSIFICATION</p> <table border="1"> <tr> <th>GENERAL CLASS.</th> <th>GRANULAR MATERIALS (>5% PASSING #200)</th> <th>SILT-CLAY MATERIALS (>25% PASSING #200)</th> <th>ORGANIC MATERIALS</th> </tr> <tr> <td>GROUP CLASS.</td> <td>A-1, A-3, A-2, A-2-4, A-2-5, A-2-6, A-2-7</td> <td>A-4, A-5, A-6, A-7, A-7-5, A-7-6, A-7-7</td> <td>A-8, A-9, A-10, A-11, A-12</td> </tr> <tr> <td>SYMBOL</td> <td></td> <td></td> <td></td> </tr> <tr> <td>% PASSING</td> <td>50 MX, 30 MX, 15 MX, 10 MX, 5 MX</td> <td>40 MX, 30 MX, 20 MX, 10 MX, 5 MX</td> <td>10 MX, 5 MX, 2 MX, 1 MX</td> </tr> <tr> <td>LIQUID LIMIT</td> <td>6 MX</td> <td>10 MX, 15 MX, 20 MX, 25 MX, 30 MX</td> <td>40 MX, 30 MX, 20 MX, 10 MX, 5 MX</td> </tr> <tr> <td>PLASTIC INDEX</td> <td>0</td> <td>0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30</td> <td>0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30</td> </tr> <tr> <td>GROUP INDEX</td> <td>0</td> <td>0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30</td> <td>0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30</td> </tr> <tr> <td>USUAL TYPES OF MAJOR MATERIALS</td> <td>STONE FRAGS. GRAVEL AND SAND, FINE SAND</td> <td>SILT OR CLAYEY GRAVEL AND SAND, SILTY SOILS, CLAYEY SOILS</td> <td>SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER, HIGHLY ORGANIC SOILS</td> </tr> <tr> <td>GEN. RATINGS AS A SUBGRADE</td> <td>EXCELLENT TO GOOD</td> <td>FAIR TO POOR</td> <td>FAIR TO POOR, POOR, UNSUITABLE</td> </tr> </table> <p align="center">P.I. OF A-7-5 ≤ L.L. - 30 + P.I. OF A-7-6 > L.L. - 30</p>		GENERAL CLASS.	GRANULAR MATERIALS (>5% PASSING #200)	SILT-CLAY MATERIALS (>25% PASSING #200)	ORGANIC MATERIALS	GROUP CLASS.	A-1, A-3, A-2, A-2-4, A-2-5, A-2-6, A-2-7	A-4, A-5, A-6, A-7, A-7-5, A-7-6, A-7-7	A-8, A-9, A-10, A-11, A-12	SYMBOL				% PASSING	50 MX, 30 MX, 15 MX, 10 MX, 5 MX	40 MX, 30 MX, 20 MX, 10 MX, 5 MX	10 MX, 5 MX, 2 MX, 1 MX	LIQUID LIMIT	6 MX	10 MX, 15 MX, 20 MX, 25 MX, 30 MX	40 MX, 30 MX, 20 MX, 10 MX, 5 MX	PLASTIC INDEX	0	0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30	0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30	GROUP INDEX	0	0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30	0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30	USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL AND SAND, FINE SAND	SILT OR CLAYEY GRAVEL AND SAND, SILTY SOILS, CLAYEY SOILS	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER, HIGHLY ORGANIC SOILS	GEN. RATINGS AS A SUBGRADE	EXCELLENT TO GOOD	FAIR TO POOR	FAIR TO POOR, POOR, UNSUITABLE	<p align="center">MINERALOGICAL COMPOSITION</p> <p>MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.</p> <p align="center">COMPRESSIBILITY</p> <p>SLIGHTLY COMPRESSIBLE LIQUID LIMIT LESS THAN 30 MODERATELY COMPRESSIBLE LIQUID LIMIT 31-50 HIGHLY COMPRESSIBLE LIQUID LIMIT GREATER THAN 50</p> <p align="center">PERCENTAGE OF MATERIAL</p> <table border="1"> <tr> <th>ORGANIC MATERIAL</th> <th>GRANULAR SOILS</th> <th>SILT-CLAY SOILS</th> <th>OTHER MATERIAL</th> </tr> <tr> <td>TRACE OF ORGANIC MATTER</td> <td>2 - 3%</td> <td>3 - 5%</td> <td>TRACE</td> </tr> <tr> <td>LITTLE ORGANIC MATTER</td> <td>3 - 5%</td> <td>5 - 12%</td> <td>LITTLE</td> </tr> <tr> <td>MODERATELY ORGANIC</td> <td>5 - 10%</td> <td>12 - 20%</td> <td>SOME</td> </tr> <tr> <td>HIGHLY ORGANIC</td> <td>>10%</td> <td>>20%</td> <td>HIGHLY</td> </tr> </table> <p align="center">GROUND WATER</p> <p> WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING.</p> <p> STATIC WATER LEVEL AFTER 24 HOURS.</p> <p> PERCHED WATER, SATURATED ZONE OR WATER BEARING STRATA</p> <p> SPRING OR SEEPAGE</p>		ORGANIC MATERIAL	GRANULAR SOILS	SILT-CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME	HIGHLY ORGANIC	>10%	>20%	HIGHLY	<p align="center">WEATHERING</p> <p>FRESH - ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING, ROCK RINGS UNDER HAMMER IF CRYSTALLINE.</p> <p>VERY SLIGHT (V. SL.) - ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN, CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.</p> <p>SLIGHT (SL.) - ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.</p> <p>MODERATE (MOD.) - SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.</p> <p>MODERATELY SEVERE (MOD. SEV.) - ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <i>IF TESTED, WOULD YIELD SPT REFUSAL.</i></p> <p>SEVERE (SEV.) - ALL ROCKS EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <i>IF TESTED, YIELDS SPT N VALUES > 100 BPF.</i></p> <p>VERY SEVERE (V. SEV.) - ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <i>IF TESTED, YIELDS SPT N VALUES < 100 BPF.</i></p> <p>COMPLETE - ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.</p>				
GENERAL CLASS.	GRANULAR MATERIALS (>5% PASSING #200)	SILT-CLAY MATERIALS (>25% PASSING #200)	ORGANIC MATERIALS																																																													
GROUP CLASS.	A-1, A-3, A-2, A-2-4, A-2-5, A-2-6, A-2-7	A-4, A-5, A-6, A-7, A-7-5, A-7-6, A-7-7	A-8, A-9, A-10, A-11, A-12																																																													
SYMBOL																																																																
% PASSING	50 MX, 30 MX, 15 MX, 10 MX, 5 MX	40 MX, 30 MX, 20 MX, 10 MX, 5 MX	10 MX, 5 MX, 2 MX, 1 MX																																																													
LIQUID LIMIT	6 MX	10 MX, 15 MX, 20 MX, 25 MX, 30 MX	40 MX, 30 MX, 20 MX, 10 MX, 5 MX																																																													
PLASTIC INDEX	0	0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30	0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30																																																													
GROUP INDEX	0	0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30	0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30																																																													
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL AND SAND, FINE SAND	SILT OR CLAYEY GRAVEL AND SAND, SILTY SOILS, CLAYEY SOILS	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER, HIGHLY ORGANIC SOILS																																																													
GEN. RATINGS AS A SUBGRADE	EXCELLENT TO GOOD	FAIR TO POOR	FAIR TO POOR, POOR, UNSUITABLE																																																													
ORGANIC MATERIAL	GRANULAR SOILS	SILT-CLAY SOILS	OTHER MATERIAL																																																													
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE																																																													
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE																																																													
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME																																																													
HIGHLY ORGANIC	>10%	>20%	HIGHLY																																																													
<p align="center">CONSISTENCY OR DENSENESS</p> <table border="1"> <tr> <th>PRIMARY SOIL TYPE</th> <th>COMPACTNESS OR CONSISTENCY</th> <th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th> <th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT²)</th> </tr> <tr> <td>GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td> <td>VERY LOOSE, LOOSE, MEDIUM DENSE, DENSE, VERY DENSE</td> <td><4, 4 TO 10, 10 TO 30, 30 TO 50, >50</td> <td>N/A</td> </tr> <tr> <td>GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>VERY SOFT, SOFT, MEDIUM STIFF, STIFF, VERY STIFF, HARD</td> <td>2 TO 4, 4 TO 8, 8 TO 15, 15 TO 30, >30</td> <td><0.25, 0.25 TO 1, 1 TO 2, 2 TO 4, >4</td> </tr> </table>		PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE, LOOSE, MEDIUM DENSE, DENSE, VERY DENSE	<4, 4 TO 10, 10 TO 30, 30 TO 50, >50	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT, SOFT, MEDIUM STIFF, STIFF, VERY STIFF, HARD	2 TO 4, 4 TO 8, 8 TO 15, 15 TO 30, >30	<0.25, 0.25 TO 1, 1 TO 2, 2 TO 4, >4	<p align="center">MISCELLANEOUS SYMBOLS</p> <p> ROADWAY EMBANKMENT WITH SOIL DESCRIPTION</p> <p> SOIL SYMBOL</p> <p> ARTIFICIAL FILL OTHER THAN ROADWAY EMBANKMENTS</p> <p> INFERRED SOIL BOUNDARIES</p> <p> INFERRED ROCK LINE</p> <p> ALLUVIAL SOIL BOUNDARY</p> <p> DIP/DIP DIRECTION OF ROCK STRUCTURES</p> <p> SOUNDING ROD</p> <p> TEST BORING</p> <p> AUGER BORING</p> <p> CORE BORING</p> <p> MONITORING WELL</p> <p> PIEZOMETER INSTALLATION</p> <p> SLOPE INDICATOR INSTALLATION</p> <p> SPT N-VALUE</p> <p> SPT REFUSAL</p> <p> S - BULK SAMPLE</p> <p> SS - SPLIT SPOON SAMPLE</p> <p> ST - SHELBY TUBE SAMPLE</p> <p> RS - ROCK SAMPLE</p> <p> RT - RECOMPACT TRIAXIAL SAMPLE</p> <p> CBR - CBR SAMPLE</p>																																																		
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)																																																													
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE, LOOSE, MEDIUM DENSE, DENSE, VERY DENSE	<4, 4 TO 10, 10 TO 30, 30 TO 50, >50	N/A																																																													
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT, SOFT, MEDIUM STIFF, STIFF, VERY STIFF, HARD	2 TO 4, 4 TO 8, 8 TO 15, 15 TO 30, >30	<0.25, 0.25 TO 1, 1 TO 2, 2 TO 4, >4																																																													
<p align="center">TEXTURE OR GRAIN SIZE</p> <table border="1"> <tr> <th>U.S. STD. SIEVE SIZE OPENING (MM)</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> <tr> <td></td> <td>4.76</td> <td>2.0</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> </table> <table border="1"> <tr> <th>BOULDER (BLDR.)</th> <th>COBBLE (COB.)</th> <th>GRAVEL (GR.)</th> <th>COARSE SAND (CSE. SD.)</th> <th>FINE SAND (F. SD.)</th> <th>SILT (SL.)</th> <th>CLAY (CL.)</th> </tr> <tr> <td>GRAIN SIZE</td> <td>MM 305</td> <td>75</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> </tr> <tr> <td></td> <td>IN. 12"</td> <td>3"</td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.76	2.0	0.42	0.25	0.075	0.053	BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)	GRAIN SIZE	MM 305	75	2.0	0.25	0.05	0.005		IN. 12"	3"					<p align="center">ABBREVIATIONS</p> <p>AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - CONE PENETRATION TEST CSE. - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F. - FINE FOSS. - FOSSILIFEROUS FRAC. - FRACTURED FRAGS. - FRAGMENTS MED. - MEDIUM</p> <p>PMT - PRESSUREMETER TEST SD. - SAND, SANDY SL. - SILT, SILTY SLI. - SLIGHTLY TCR - TRICONE REFUSAL γ - UNIT WEIGHT γ_d - DRY UNIT WEIGHT w - MOISTURE CONTENT V. - VERY VST - VANE SHEAR TEST</p>																											
U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																										
	4.76	2.0	0.42	0.25	0.075	0.053																																																										
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)																																																										
GRAIN SIZE	MM 305	75	2.0	0.25	0.05	0.005																																																										
	IN. 12"	3"																																																														
<p align="center">SOIL MOISTURE - CORRELATION OF TERMS</p> <table border="1"> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> <tr> <td rowspan="2">LL - LIQUID LIMIT PL - PLASTIC LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>- WET - (W)</td> <td>SEMI-SOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td rowspan="2">OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </table>		SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT PL - PLASTIC LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	- WET - (W)	SEMI-SOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	<p align="center">EQUIPMENT USED ON SUBJECT PROJECT</p> <table border="1"> <tr> <th>DRILL UNITS:</th> <th>ADVANCING TOOLS:</th> <th>HAMMER TYPE:</th> </tr> <tr> <td><input type="checkbox"/> MOBILE B-</td> <td><input type="checkbox"/> CLAY BITS</td> <td><input type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</td> </tr> <tr> <td><input type="checkbox"/> BK-51</td> <td><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</td> <td rowspan="2">CORE SIZE: <input type="checkbox"/> B <input type="checkbox"/> N <input type="checkbox"/> H</td> </tr> <tr> <td><input type="checkbox"/> CME-45C</td> <td><input type="checkbox"/> 8" HOLLOW AUGERS</td> </tr> <tr> <td><input type="checkbox"/> CME-550</td> <td><input type="checkbox"/> HARD FACED FINGER BITS</td> <td rowspan="2">HAND TOOLS: <input type="checkbox"/> POST HOLE DIGGER <input type="checkbox"/> HAND AUGER <input type="checkbox"/> SOUNDING ROD <input type="checkbox"/> VANE SHEAR TEST <input type="checkbox"/> OTHER</td> </tr> <tr> <td><input type="checkbox"/> PORTABLE HOIST</td> <td><input type="checkbox"/> TUNG-CARBIDE INSERTS</td> </tr> <tr> <td><input type="checkbox"/> OTHER CME-750</td> <td><input type="checkbox"/> CASING w/ ADVANCER</td> <td></td> </tr> <tr> <td><input type="checkbox"/> TRUCK MOUNTED</td> <td><input type="checkbox"/> TRICONE _____ STEEL TEETH</td> <td></td> </tr> <tr> <td><input type="checkbox"/> OTHER</td> <td><input type="checkbox"/> TRICONE _____ TUNG-CARB.</td> <td></td> </tr> <tr> <td></td> <td><input type="checkbox"/> CORE BIT</td> <td></td> </tr> <tr> <td></td> <td><input type="checkbox"/> OTHER _____</td> <td></td> </tr> </table>		DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:	<input type="checkbox"/> MOBILE B-	<input type="checkbox"/> CLAY BITS	<input type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL	<input type="checkbox"/> BK-51	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE: <input type="checkbox"/> B <input type="checkbox"/> N <input type="checkbox"/> H	<input type="checkbox"/> CME-45C	<input type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> CME-550	<input type="checkbox"/> HARD FACED FINGER BITS	HAND TOOLS: <input type="checkbox"/> POST HOLE DIGGER <input type="checkbox"/> HAND AUGER <input type="checkbox"/> SOUNDING ROD <input type="checkbox"/> VANE SHEAR TEST <input type="checkbox"/> OTHER	<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS	<input type="checkbox"/> OTHER CME-750	<input type="checkbox"/> CASING w/ ADVANCER		<input type="checkbox"/> TRUCK MOUNTED	<input type="checkbox"/> TRICONE _____ STEEL TEETH		<input type="checkbox"/> OTHER	<input type="checkbox"/> TRICONE _____ TUNG-CARB.			<input type="checkbox"/> CORE BIT			<input type="checkbox"/> OTHER _____																		
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																														
LL - LIQUID LIMIT PL - PLASTIC LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																														
	- WET - (W)	SEMI-SOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																														
OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																														
	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																														
DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:																																																														
<input type="checkbox"/> MOBILE B-	<input type="checkbox"/> CLAY BITS	<input type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL																																																														
<input type="checkbox"/> BK-51	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE: <input type="checkbox"/> B <input type="checkbox"/> N <input type="checkbox"/> H																																																														
<input type="checkbox"/> CME-45C	<input type="checkbox"/> 8" HOLLOW AUGERS																																																															
<input type="checkbox"/> CME-550	<input type="checkbox"/> HARD FACED FINGER BITS	HAND TOOLS: <input type="checkbox"/> POST HOLE DIGGER <input type="checkbox"/> HAND AUGER <input type="checkbox"/> SOUNDING ROD <input type="checkbox"/> VANE SHEAR TEST <input type="checkbox"/> OTHER																																																														
<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS																																																															
<input type="checkbox"/> OTHER CME-750	<input type="checkbox"/> CASING w/ ADVANCER																																																															
<input type="checkbox"/> TRUCK MOUNTED	<input type="checkbox"/> TRICONE _____ STEEL TEETH																																																															
<input type="checkbox"/> OTHER	<input type="checkbox"/> TRICONE _____ TUNG-CARB.																																																															
	<input type="checkbox"/> CORE BIT																																																															
	<input type="checkbox"/> OTHER _____																																																															
<p align="center">PLASTICITY</p> <table border="1"> <tr> <th>NONPLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td>LOW PLASTICITY</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MED. PLASTICITY</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGH PLASTICITY</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </table> <p align="center">COLOR</p> <p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YEL-BRN, BLUE-GRAY) MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>		NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	LOW PLASTICITY	0-5	VERY LOW	MED. PLASTICITY	6-15	SLIGHT	HIGH PLASTICITY	16-25	MEDIUM		26 OR MORE	HIGH	<p align="center">ROCK HARDNESS</p> <p>VERY HARD - CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.</p> <p>HARD - CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.</p> <p>MODERATELY HARD - CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.</p> <p>MEDIUM HARD - CAN BE GROVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.</p> <p>SOFT - CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.</p> <p>VERY SOFT - CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.</p>																																															
NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																														
LOW PLASTICITY	0-5	VERY LOW																																																														
MED. PLASTICITY	6-15	SLIGHT																																																														
HIGH PLASTICITY	16-25	MEDIUM																																																														
	26 OR MORE	HIGH																																																														
<p align="center">TEXTURE OR GRAIN SIZE</p> <table border="1"> <tr> <th>U.S. STD. SIEVE SIZE OPENING (MM)</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> <tr> <td></td> <td>4.76</td> <td>2.0</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> </table> <table border="1"> <tr> <th>BOULDER (BLDR.)</th> <th>COBBLE (COB.)</th> <th>GRAVEL (GR.)</th> <th>COARSE SAND (CSE. SD.)</th> <th>FINE SAND (F. SD.)</th> <th>SILT (SL.)</th> <th>CLAY (CL.)</th> </tr> <tr> <td>GRAIN SIZE</td> <td>MM 305</td> <td>75</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> </tr> <tr> <td></td> <td>IN. 12"</td> <td>3"</td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.76	2.0	0.42	0.25	0.075	0.053	BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)	GRAIN SIZE	MM 305	75	2.0	0.25	0.05	0.005		IN. 12"	3"					<p align="center">FRACTURE SPACING</p> <table border="1"> <tr> <th>TERM</th> <th>SPACING</th> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> </tr> </table> <p align="center">BEDDING</p> <table border="1"> <tr> <th>TERM</th> <th>THICKNESS</th> </tr> <tr> <td>VERY THICKLY BEDDED</td> <td>> 4 FEET</td> </tr> <tr> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </table> <p align="center">INDURATION</p> <p>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</p> <p>FRIABLE - RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</p> <p>MODERATELY INDURATED - GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</p> <p>INDURATED - GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</p> <p>EXTREMELY INDURATED - SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</p>		TERM	SPACING	VERY WIDE	MORE THAN 10 FEET	WIDE	3 TO 10 FEET	MODERATELY CLOSE	1 TO 3 FEET	CLOSE	0.16 TO 1 FEET	VERY CLOSE	LESS THAN 0.16 FEET	TERM	THICKNESS	VERY THICKLY BEDDED	> 4 FEET	THICKLY BEDDED	1.5 - 4 FEET	THINLY BEDDED	0.16 - 1.5 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET	THINLY LAMINATED	< 0.008 FEET
U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																										
	4.76	2.0	0.42	0.25	0.075	0.053																																																										
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)																																																										
GRAIN SIZE	MM 305	75	2.0	0.25	0.05	0.005																																																										
	IN. 12"	3"																																																														
TERM	SPACING																																																															
VERY WIDE	MORE THAN 10 FEET																																																															
WIDE	3 TO 10 FEET																																																															
MODERATELY CLOSE	1 TO 3 FEET																																																															
CLOSE	0.16 TO 1 FEET																																																															
VERY CLOSE	LESS THAN 0.16 FEET																																																															
TERM	THICKNESS																																																															
VERY THICKLY BEDDED	> 4 FEET																																																															
THICKLY BEDDED	1.5 - 4 FEET																																																															
THINLY BEDDED	0.16 - 1.5 FEET																																																															
VERY THINLY BEDDED	0.03 - 0.16 FEET																																																															
THICKLY LAMINATED	0.008 - 0.03 FEET																																																															
THINLY LAMINATED	< 0.008 FEET																																																															
<p align="center">PLASTICITY</p> <table border="1"> <tr> <th>NONPLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td>LOW PLASTICITY</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MED. PLASTICITY</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGH PLASTICITY</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </table> <p align="center">COLOR</p> <p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YEL-BRN, BLUE-GRAY) MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>		NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	LOW PLASTICITY	0-5	VERY LOW	MED. PLASTICITY	6-15	SLIGHT	HIGH PLASTICITY	16-25	MEDIUM		26 OR MORE	HIGH	<p align="center">ROCK HARDNESS</p> <p>VERY HARD - CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.</p> <p>HARD - CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.</p> <p>MODERATELY HARD - CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.</p> <p>MEDIUM HARD - CAN BE GROVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.</p> <p>SOFT - CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.</p> <p>VERY SOFT - CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.</p>																																															
NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																														
LOW PLASTICITY	0-5	VERY LOW																																																														
MED. PLASTICITY	6-15	SLIGHT																																																														
HIGH PLASTICITY	16-25	MEDIUM																																																														
	26 OR MORE	HIGH																																																														
<p align="center">PLASTICITY</p> <table border="1"> <tr> <th>NONPLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td>LOW PLASTICITY</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MED. PLASTICITY</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGH PLASTICITY</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </table> <p align="center">COLOR</p> <p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YEL-BRN, BLUE-GRAY) MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>		NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	LOW PLASTICITY	0-5	VERY LOW	MED. PLASTICITY	6-15	SLIGHT	HIGH PLASTICITY	16-25	MEDIUM		26 OR MORE	HIGH	<p align="center">FRACTURE SPACING</p> <table border="1"> <tr> <th>TERM</th> <th>SPACING</th> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> </tr> </table> <p align="center">BEDDING</p> <table border="1"> <tr> <th>TERM</th> <th>THICKNESS</th> </tr> <tr> <td>VERY THICKLY BEDDED</td> <td>> 4 FEET</td> </tr> <tr> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </table> <p align="center">INDURATION</p> <p>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</p> <p>FRIABLE - RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</p> <p>MODERATELY INDURATED - GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</p> <p>INDURATED - GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</p> <p>EXTREMELY INDURATED - SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</p>		TERM	SPACING	VERY WIDE	MORE THAN 10 FEET	WIDE	3 TO 10 FEET	MODERATELY CLOSE	1 TO 3 FEET	CLOSE	0.16 TO 1 FEET	VERY CLOSE	LESS THAN 0.16 FEET	TERM	THICKNESS	VERY THICKLY BEDDED	> 4 FEET	THICKLY BEDDED	1.5 - 4 FEET	THINLY BEDDED	0.16 - 1.5 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET	THINLY LAMINATED	< 0.008 FEET																				
NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																														
LOW PLASTICITY	0-5	VERY LOW																																																														
MED. PLASTICITY	6-15	SLIGHT																																																														
HIGH PLASTICITY	16-25	MEDIUM																																																														
	26 OR MORE	HIGH																																																														
TERM	SPACING																																																															
VERY WIDE	MORE THAN 10 FEET																																																															
WIDE	3 TO 10 FEET																																																															
MODERATELY CLOSE	1 TO 3 FEET																																																															
CLOSE	0.16 TO 1 FEET																																																															
VERY CLOSE	LESS THAN 0.16 FEET																																																															
TERM	THICKNESS																																																															
VERY THICKLY BEDDED	> 4 FEET																																																															
THICKLY BEDDED	1.5 - 4 FEET																																																															
THINLY BEDDED	0.16 - 1.5 FEET																																																															
VERY THINLY BEDDED	0.03 - 0.16 FEET																																																															
THICKLY LAMINATED	0.008 - 0.03 FEET																																																															
THINLY LAMINATED	< 0.008 FEET																																																															
<p align="center">PLASTICITY</p> <table border="1"> <tr> <th>NONPLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td>LOW PLASTICITY</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MED. PLASTICITY</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGH PLASTICITY</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </table> <p align="center">COLOR</p> <p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YEL-BRN, BLUE-GRAY) MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>		NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	LOW PLASTICITY	0-5	VERY LOW	MED. PLASTICITY	6-15	SLIGHT	HIGH PLASTICITY	16-25	MEDIUM		26 OR MORE	HIGH	<p align="center">FRACTURE SPACING</p> <table border="1"> <tr> <th>TERM</th> <th>SPACING</th> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> </tr> </table> <p align="center">BEDDING</p> <table border="1"> <tr> <th>TERM</th> <th>THICKNESS</th> </tr> <tr> <td>VERY THICKLY BEDDED</td> </tr></table>		TERM	SPACING	VERY WIDE	MORE THAN 10 FEET	WIDE	3 TO 10 FEET	MODERATELY CLOSE	1 TO 3 FEET	CLOSE	0.16 TO 1 FEET	VERY CLOSE	LESS THAN 0.16 FEET	TERM	THICKNESS	VERY THICKLY BEDDED																															
NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																														
LOW PLASTICITY	0-5	VERY LOW																																																														
MED. PLASTICITY	6-15	SLIGHT																																																														
HIGH PLASTICITY	16-25	MEDIUM																																																														
	26 OR MORE	HIGH																																																														
TERM	SPACING																																																															
VERY WIDE	MORE THAN 10 FEET																																																															
WIDE	3 TO 10 FEET																																																															
MODERATELY CLOSE	1 TO 3 FEET																																																															
CLOSE	0.16 TO 1 FEET																																																															
VERY CLOSE	LESS THAN 0.16 FEET																																																															
TERM	THICKNESS																																																															
VERY THICKLY BEDDED																																																																

TIP PROJECT: U-2810

See Sheet 1-A For Index of Sheets



VICINITY MAP

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS


CUMBERLAND COUNTY

**LOCATION: FAYETTEVILLE - SR 1003 (CAMDEN RD.) FROM
NC 59 (HOPE MILLS RD.) TO NORTH OF SR 1007 (OWEN DR.)**

**TYPE OF WORK: GRADING, DRAINAGE, WIDENING, RESURFACING
CURB & GUTTER, SIGNALS, GUARDRAIL,
CULVERT, STRUCTURES & RETAINING WALL**


STATE	STATE PROJECT REFERENCE NO.	SHEET NO.
N.C.	U-2810	2A
STATE PROJ. NO.	P.A. PROJ. NO.	DESCRIPTION
34866.1.1	STP-1003(22)	

INCOMPLETE PLANS
DO NOT USE FOR R/W ACQUISITION
PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION



NOTES: CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD.

CONTRACT:



DESIGN DATA

ADT 2004 = 15,400
ADT 2030 = 26,800
DHV = 10 %
D = 60 %
T = 5 % *
V = 50 MPH
* TTST 1 %
DUAL 4 %

PROJECT LENGTH

LENGTH ROADWAY TIP PROJ. U-2810 = 3.787 MILES
LENGTH STRUCTURES TIP PROJ. U-2810 = 0.098 MILES
TOTAL LENGTH OF TIP PROJ. U-2810 = 3.885 MILES

Prepared In the Office of:

DIVISION OF HIGHWAYS
1000 Birch Ridge Dr., Raleigh NC, 27610

2002 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:	ROGER D. THOMAS, P.E. PROJECT ENGINEER
LETTING DATE:	SAMUEL L. ST. CLAIR PROJECT DESIGN ENGINEER
	October 2007

HYDRAULICS ENGINEER

SIGNATURE: _____ P.E.

ROADWAY DESIGN ENGINEER

SIGNATURE: _____ P.E.

**DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA**

STATE DESIGN ENGINEER _____ P.E.

DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION

APPROVED _____ P.E.
DIVISION ADMINISTRATOR

DATE _____



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

Michael F. Easley
GOVERNOR

P.O. BOX 25201, RALEIGH, N.C. 27611-5201

Lyndo Tippet
SECRETARY

September 7, 2005

STATE PROJECT: 34866.1.1 (U-2810)
FEDERAL PROJECT: STP-1003(22)
COUNTY: Cumberland
DESCRIPTION: Fayetteville – SR 1003 (Camden Rd.) from NC 59 (Hope Mills Rd.) to north of SR 1007 (Owen Dr.)
SUBJECT: Geotechnical Report – Inventory

Project Description

This project consists of widening the existing Camden Road (-L-, SR 1003) from two lanes to four lanes with medians and turn lanes. The project begins just north of the intersection of Camden Road and Hope Mills Road (NC 59), and ends just east of the Owen Drive (SR 1007) intersection. The interval -L- Sta. 56+69 to Sta. 74+66 is currently being constructed as part of U-620 (Hope Mills Bypass). Another interval, -L- Sta. 176+51 to 181+50, was recently constructed during the widening of SR 1344 (Mid Pine Rd.). A 3,000-foot section of the roadway is being shifted eastward approximately 600 feet from -L- Sta. 100+00 to Sta. 130+00. The widening generally occurs to the left of the existing roadway. Bridges are to be constructed over Little Rockfish Creek (see Plan Sheet No. 5) and the CSX railroad (see Plan Sheet Nos. 11 and 12). A culvert is to be constructed along Buckhead Creek at -L- Sta. 40+00. A retaining wall will be constructed left of -L- Sta. 15+00 to 17+10.

The geotechnical field investigation was conducted during the period of February and March, 2005. A truck-mounted D-50 drill with a manual hammer, and an ATV-mounted CME-750 drill machine with an automatic hammer, were used during the investigation. Standard Penetration Tests were performed in selected borings and additional borings were advanced using continuous flight augers. Representative soil samples were collected for visual classification in the field and for laboratory analysis by the Materials and Tests Unit.

The following alignments, totaling 4.4 miles, were investigated. Subsurface soil profiles, or cross-sections, of these alignments are included in this report.

<u>Line</u>	<u>Station</u>
-L-	15+00 to 56+69

-L-	74+66 to 176+51
-L-	181+50 to 244+84
-Y1-	11+22 to 12+67
-Y4-	10+37 to 12+35
-Y6-	10+00 to 16+62
-Y7-	10+12 to 19+20
-Y9-	10+79 to 12+31
-Y14-	8+00 to 18+32

Areas of Special Geotechnical Interest

- 1) Highly Plastic Clay Soils: Areas containing highly plastic clay soils are noted below:

<u>Alignment</u>	<u>Station</u>	<u>Offset</u>
-L-	17+00	55 LT
-L-	19+00	CL
-L-	40+25	45 RT
-L-	51+50	25 RT
-L-	88+00	3 RT
-L-	90+50	50 LT
-L-	95+50	5 RT
-L-	96+00	45 RT
-L-	97+00	45 RT
-L-	114+42	CL
-Y4-	11+00	20 RT

A discussion of these highly plastic clay soils is located below in the section titled: "Soil Properties".

- 2) Organic Soils: The following area contains soils with organic contents ranging from 23.1 to 40.8%:

<u>Alignment</u>	<u>Station</u>	<u>Offset</u>
-L-	95+95 to 97+95	LT

- 3) Groundwater: The following areas exhibit a high water table, seasonal high groundwater, or the potential for groundwater related construction problems:

<u>Alignment</u>	<u>Station</u>
-L-	24+50 to 33+00
-L-	46+50 to 55+00
-L-	96+00 to 97+95

4) Water Wells: Water wells were noted within the construction limits at the following locations:

<u>Alignment</u>	<u>Station</u>	<u>Offset</u>
-L-	80+09	20 LT
-L-	83+05	24 LT
-L-	92+20	21 LT
-L-	92+50	21 LT
-L-	94+90	47 LT
-L-	103+20	31 RT
-L-	105+37	17 LT
-L-	117+98	16 LT
-L-	131+51	21 LT
-L-	133+33	31 LT
-L-	147+01	32 LT
-L-	159+28	46 LT

Physiography and Geology

The project is located between the city of Fayetteville and the town of Hope Mills, within the Coastal Plain Province. The area is underlain by Cretaceous-age sands and clays of the Black Creek Formation. Undifferentiated Quaternary-age sands occur at the ground surface. Recent alluvial sand is present in the Little Rockfish Creek floodplain. Numerous homes, churches, and businesses occur along Camden Road. The Little Rockfish Creek floodplain is wooded, as well as the areas left and right of -L- Sta. 43+00 to 60+00.

Soil Properties

Roadway Embankment Soils: Roadway embankment soil occurs in several locations on the project. Three to five feet of embankment soil, consisting of loose to medium dense sand (AASHTO classification of A-2-4), overlies alluvial sand within the Little Rockfish Creek floodplain. Roadway embankment soil is also present from -L- Sta. 43+50 to 55+50 and -L- Sta. 74+66 to 103+00. The embankment soil in these areas primarily consists of loose sand (A-2-4 and A-3).

Artificial Fill Soils: An area of artificial fill soil occurs at the beginning of the project, left of -L- Sta. 15+00 to 18+40 (see Plan Sheet No. 4 and Cross-section Sheet No. 38). A parking lot and the adjacent building have been constructed on the fill. The fill soils consists of loose to medium dense, sand (A-2-4 and A-3).

Alluvial Soils: Alluvial soils are present in the floodplain of Little Rockfish Creek and in the channels of several other streams which cross the project corridor. Alluvial soils in the Little Rockfish Creek floodplain are generally 5 to 8 feet thick, consisting of loose to medium dense, silty sand (A-2-4 and A-1-b) with gravel (see Plan Sheet Nos. 4 and 5, and Profile Sheet No. 23).

Another area of alluvial soil occurs left of -L- Sta. 96+00 to 97+95 (see Plan Sheet No. 10, Profile Sheet No. 26, and Cross-section Sheet Nos. 40 to 42). Approximately 2 to 5 feet of very soft, saturated muck occurs in this area. Organic content of the muck ranges from 23.1 to 40.8%, with a moisture content as high as 305%. The muck overlies 3 to 5 feet of gray, dense, saturated alluvial sand (A-2-4).

embankment fill soil. The existing roadway embankment has been placed over a portion of this area of highly organic soil (-L- Sta. 97+10 to 98+10). The boring at -L- Sta. 98+00/3RT suggests that the very soft muck was undercut and backfilled with sand. The remaining underlying alluvial soil consists of five feet of loose sand with traces of organic material (A-2-4 with 3.3% organic content).

Coastal Plain Soils: These soils are derived from the Tertiary-age sedimentary deposits which occur at the ground surface. These soils are multicolored, with hues of tan, orange, and gray being most common. Sandy soil is the most common Coastal Plain soil in the project area. These sandy soils are generally loose to medium dense sands and silty sands (A-1-b, A-3, and A-2-4). Loose to medium dense, clayey sand (A-2-6) is also present in minor amounts. Areas containing highly plastic (plasticity indices of greater than 25) soils are listed above in Section 1 of "Areas of Special Geotechnical Interest".

Culverts

-L- Sta. 40+00: This proposed culvert consists of a 137-foot long triple box culvert on Buckhead Creek (see Plan Sheet No. 6). Approximately 4 to 5 feet of fill will overlie the culvert. The culvert will be underlain by 5 feet of loose, coarse, alluvial sand (A-1-a). The alluvial sand is underlain by medium dense, Coastal Plain sand (A-3).

Retaining Wall

A retaining wall is to be constructed left of -L- Sta. 15+00 to 17+13 (see Plan Sheet No. 4, Profile Sheet No. 38, and Cross-section Sheet No. 39). Eleven to thirteen feet of artificial fill was encountered at the location of the wall. The fill was constructed for the adjacent buildings and parking lot. The fill consists of red-brown to tan, loose to medium dense, dry to moist sand (A-3 and A-2-4). The fill soil is underlain by Coastal Plain soils, consisting of either medium dense sand (A-3), stiff, sandy silt (A-4), or stiff to hard, silty clay (A-6) and highly plastic clay (A-7-6). Groundwater was not encountered in the retaining wall borings.

Groundwater

Groundwater generally occurs within one to three feet of the ground surface in the alluvial soils of the Little Rockfish Creek floodplain. Groundwater occurs at, or very near, the ground surface in the alluvial area left of -L- Sta. 96+00 to 98+10. Groundwater, where present, occurs at depths of 10 to 15 feet on the remainder of the project.

Prepared by,

Thomas P. Moorefield

Thomas P. Moorefield, LG
Project Geologist

Bulk Samples

The following bulk sample was taken for tests to determine the engineering properties of the soil.

<u>Sample No.</u>	<u>Location</u>	<u>Depth (feet)</u>	<u>Test</u>
CBR-1	-L- Sta. 203+50/35RT	0.0 - 5.0	California Bearing Ratio

3C

EARTHWORK BALANCE SHEET

Volumes in Cubic Yards

PROJECT: U-2810C

COUNTY: Cumberland

DATE: 10/10/2013

COMPILED BY: Brian Kanaan

SHEET 1 OF 2 SHEETS

STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE			
		TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. +25%		ROCK	SUITABLE	UNSUIT.	TOTAL
-L- 129+50.00 LT	-L- 155+00.00 LT	1,005				1,005	5,081		5,081	6,351	5,346				
-Y9- 11+00.00	-Y9- 12+28.12	264				264	37		37	46			218		218
	SUBTOTAL	1,269				1,269	5,118		5,118	6,397	5,346		218		218
-L- 155+00.00 LT	-L- 178+50.00 LT	221				221	4,515		4,515	5,644	5,423				
-Y12- 11+25.00	-Y12- 12+82.97	205				205	32		32	40			165		165
	SUBTOTAL	426				426	4,547		4,547	5,684	5,423		165		165
-L- 181+54.00 LT	-L- 205+00.00 LT	432				432	2,317		2,317	2,896	2,464				
	SUBTOTAL	432				432	2,317		2,317	2,896	2,464				
-L- 205+00.00 LT	-L- 229+00.00 LT	870				870	2,420		2,420	3,025	2,155				
-Y13- 11+00.00	-Y13- 12+53.73	112				112	42		42	53			59		59
-Y14- 8+00.00	-Y14- 12+87.34	965				965	169		169	211			754		754
	SUBTOTAL	1,947				1,947	2,631		2,631	3,289	2,155		813		813
-L- 231+32.51 LT	-L- 245+00.00 LT	305				305	5,099		5,099	6,374	6,069				
-Y16- 11+90.80	-Y16- 13+65.00	27				27	27		27	34	7				
	SUBTOTAL	332				332	5,126		5,126	6,408	6,076				
-L- 129+50.00 RT	-L- 155+00.00 RT	494				494	1,151		1,151	1,439	945				
	SUBTOTAL	494				494	1,151		1,151	1,439	945				
-L- 155+00.00 RT	-L- 176+66.00 RT	419				419	1,427		1,427	1,784	1,365				
-Y10- 10+34.75	-Y10- 11+06.00	33				33	8		8	10			23		23
-Y11- 10+34.75	-Y11- 11+75.00	227				227	9		9	11			216		216
	SUBTOTAL	679				679	1,444		1,444	1,805	1,365		239		239
	SHEET TOTAL	5,579				5,579	22,334		22,334	27,918	23,774		1,435		1,435

NOTE: EARTHWORK QUANTITIES ARE CALCULATED BY THE ROADWAY DESIGN UNIT. THESE EARTHWORK QUANTITIES ARE BASED IN PART ON SUBSURFACE DATA PROVIDED BY THE GEOTECHNICAL ENGINEERING UNIT. Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing asphalt pavement will be paid for at the lump sum price for "Grading".

3D

PROJECT U-2810 C

COUNTY: Cumberland

DATE: 10/10/2013

Volumes in Cubic Yards


COMPILED BY: Brian Kanaan

SHEET 2 OF 2 SHEETS


STATION	STATION	EXCAVATION				EMBANKMENT				BORROW	WASTE							
		TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH		EMBANK. +25%	ROCK	SUITABLE	UNSUIT.	TOTAL			
-L- 182+00.00 RT	-L- 205+00.00 RT	1,196				1,196				1,788		1,788	2,235	1,039				
SUBTOTAL		1,196				1,196				1,788		1,788	2,235	1,039				
-L- 205+00.00 RT	-L- 230+42.76 RT	795				795				1,086		1,086	1,358	563				
-Y14- 13+90.64	-Y14- 18+30.00	2,315				2,315				64		64	80			2,235		2,235
-Y15- 10+39.37	-Y15- 11+00.00	14				14				7		7	9			5		5
SUBTOTAL		3,124				3,124				1,157		1,157	1,447	563		2,240		2,240
-L- 232+50.00 RT	-L- 245+00.00 RT	685				685				292		292	365			320		320
-Y16- 16+00.00	-Y16- 16+65.00	13				13									13			13
SUBTOTAL		698				698				292		292	365			333		333
-DETL- 196+75.00	-DETL- 204+46.94	82				82				259		259	324	242				
SUBTOTAL		82				82				259		259	324	242				
SHEET TOTAL		5,100				5,100				3,496		3,496	4,371	1,843		2,573		2,573
TOTAL FROM SHEET 1		5,579				5,579				22,334		22,334	27,918	23,774		1,435		1,435
TOTAL		10,679				10,679				25,830		25,830	32,289	25,617		4,008		4,008
MATERIAL FOR SHOULDER CONSTRUCTION										718		718	898	898				
LOSS DUE TO CLEARING & GRUBBING		-35				-35								35				
WASTE TO REPLACE BORROW														-4,008		-4,008		-4,008
PROJECT TOTAL		10,644				10,644				26,548		26,548	33,186	22,542		0		0
EST. 5% TO REPLACE TOP SOIL ON BORROW PIT														1,127				
GRAND TOTAL		10,644												23,669				
SAY		10,675												23,700				

NOTE: EARTHWORK QUANTITIES ARE CALCULATED BY THE ROADWAY DESIGN UNIT. THESE EARTHWORK QUANTITIES ARE BASED IN PART ON SUBSURFACE DATA PROVIDED BY THE GEOTECHNICAL ENGINEERING UNIT. Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing asphalt pavement will be paid for at the lump sum price for "Grading".

EST. DDE = 1,110 CUBIC YARDS
 CLASS IV SUBGRADE STABILIZATION (CONTENGENCY) = 1,100 TONS
 SELECT GRANULAR MATERIAL (CONTENGENCY) = 1,000 CUBIC YARDS
 PER GEOTECH RECOMMENDATION, ESTIMATED 1,000 CUBIC YARDS OF UNDERCUT TO BE USED IN THE DISCRETION OF THE RESIDENT ENGINEER.



BEGIN TIP PROJECT U-2810 -L- STA 15+00.00



DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY MOSS FOR MONUMENT "TASTEE"


WITH NAD 83 STATE PLANE GRID COORDINATES OF
 NORTHING: 470412294(1) EASTING: 201708950(1)

THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.99988238


THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "TASTEE" TO "L" STATION (supplied by roadway) IS

ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES
 VERTICAL DATUM USED IS MVD 29

MATCH LINE 24+00 -L- SEE SHEET 5



PROJECT REFERENCE NO.	SHEET NO.
U-2810	5



MATCH LINE 24+00 -L- SEE SHEET 4

MATCH LINE 37+00 -L- SEE SHEET 6

25

30

35

-Y1- POT Sta. 10+00.00

-L- POT Sta. 36+37.33 =
 -Y1- POT Sta. 13+16.27
 -Y2- POT Sta. 10+00.00

BEG. CONSTRUCTION
 -Y1- POT Sta. 11+21.84

-Y2- PT Sta. 10+13.70

-Y2- PT Sta. 10+81.22

S 65° 31' 08.0" E

-Y2- PT Sta. 10+88.92

-Y2- PT Sta. 11+77.62

END CONSTRUCTION

-Y2- PT Sta. 11+99.00

-Y2- POT Sta. 11+92.38

S 30° 25' 25.0" E

30' CONC

30' CONC

30' CONC

30' CONC

30' CONC


30' CONC

30' CONC

30' CONC


8/17/99

PROJECT REFERENCE NO.	SHEET NO.
U-2810	6




MATCH LINE 37+00 SEE SHEET 5


MATCH LINE 50+00 SEE SHEET 7



SEE SHT 24 FOR -L- PROFILE
 SEE SHT C- FOR CULVERT PLANS



PROJECT REFERENCE NO.	SHEET NO.
U-2810	7



50

55

60



MATCH LINE 50+00 -L- SEE SHEET 6

MATCH LINE 63+00 -L- SEE SHEET 8

-L- PT Sta. 56+44.98



END CONSTRUCTION
-L- STA. 56+68.97








MATCH LINE 89+00 -L- SEE SHEET 9



MATCH LINE 102+00 -L- SEE SHEET 11







PROJECT REFERENCE NO.	SHEET NO.
U-2810	13




MATCH LINE 128+00 -L- SEE SHEET 12

MATCH LINE 141+00 -L- SEE SHEET 14

-L- PT Sta. 131+71J2


REMOVAL OF EXIST PAVEMENT



SEE SHEET 27 FOR -L- PROFILE




PROJECT REFERENCE NO.	SHEET NO.
U-2810	14

MATCH LINE 141+00 -L- SEE SHEET 13

MATCH LINE 154+00 -L- SEE SHEET 15




PROPOSED




PROJECT REFERENCE NO.	SHEET NO.
U-2810	15

MATCH LINE 154+00 -L- SEE SHEET 14


MATCH LINE 167+00 -L- SEE SHEET 16






MATCH LINE 167+00 -L- SEE SHEET 15

MATCH LINE 180+00 -L- SEE SHEET 17




CONSTRUCTION



PROJECT REFERENCE NO.	SHEET NO.
U-2810	17

MATCH LINE 180+00 -L- SEE SHEET 16


MATCH LINE 193+00 -L- SEE SHEET 18



BEGIN CONSTRUCTION
-L- STA. 181+50 +/-

-L- PTS. 186+56.55



8/17/99



PROJECT REFERENCE NO.	SHEET NO.
U-2810	18

MATCH LINE 193+00 -L- SEE SHEET 17

MATCH LINE 206+00 -L- SEE SHEET 19



3

195

200

205

COASTAL FLAVN

-L- PT Sta. 205+47.67

-L- PC Sta. 195+96.48

ISMTL BUS

ISMTL BUS

ISMTL BUS

ISBK CHURCH

ISFD (ABAND)

HTR ABAND

ISFD ABAND

ISFD

WATER VAULT

18'-25'-42.2" E

24" DR

24" DR

20" DR

24" DR

24" DR

24" DR

36" DR

36" DR

36" DR

36" DR

36" DR

36" DR

36" DR

36" DR

36" DR

72" CHL & 35BW

72" CHL & 35BW

72" CHL & 35BW

72" CHL & 35BW

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL

48" CHL


48" CHL

48" CHL

48" CHL

48" CHL



48" CH



PROJECT REFERENCE NO.	SHEET NO.
U-2810	19

MATCH LINE 206+00 SEE SHEET 18

MATCH LINE 219+00 SEE SHEET 20



-Y14- POT Sta. 8+00.00

-Y13- POT Sta. 10+00.00

BEG CONSTRUCTION
Sta. 11+00.00

COASTAL PLAIN

-L- POT Sta. 216+08.68 =
-Y14- POT Sta. 13+38.99


POT Sta. 211+10.00 =
-Y13- POT Sta. 12+86.48

-Y13- PT Sta. 12+57.12


COASTAL PLAIN

COASTAL PLAIN

-Y14- POT Sta. 18+67.81






END TIP PROJECT U-2810 -L- STA 244+83.86




MATCH LINE 232+00 SEE SHEET 20

-Y16- Sta. 11+95.13
END CONSTRUCTION





SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-10	0	19+00	4.4-5.9	A-2-4(0)	24	8	30.6	38.2	13.1	18.1	100	85	35
SS-11	0	19+00	9.4-10.9	A-2-4(0)	23	10	27.9	40.7	12.3	19.1	100	87	34
SS-12	0	19+00	14.4-15.9	A-7-6(7)	46	27	35.4	19.9	6.4	38.2	96	75	44
SS-13	0	22+00	4.0-5.5	A-2-4(0)	22	NP	47.7	44.3	5.0	3.0	100	76	11




SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
S-14	8	25+00	8.0-9.0	A-2-4(0)	28	NP	25.7	48.0	15.3	10.1	100	89	28
SS-117	50	26+20	3.2-4.7	A-3(0)	22	NP	45.9	48.6	1.5	4.0	92	73	8
SS-118	50	26+20	9.2-9.7	A-1-b(0)	40	NP	65.9	18.2	10.5	6.1	96	60	18
SS-119	50	26+20	18.2-19.7	A-2-7(1)	44	21	59.9	17.0	11.0	12.1	98	80	24
SS-120	50	26+20	33.2-34.7	A-2-7(0)	46	20	70.0	12.7	8.2	9.1	95	45	19
SS-88	-19	28+18	4.3-5.8	A-1-b(0)	25	NP	84.8	14.7	0.7	0.0	91	35	1
SS-90	-19	28+18	9.3-10.8	A-2-5(0)	43	NP	65.9	16.8	12.3	5.0	97	67	18
SS-91	-19	28+18	14.0-15.5	A-5(7)	35	18	26.1	21.1	24.6	28.1	100	85	57
SS-92	-19	28+18	24.0-25.5	A-2-6(0)	38	18	64.6	16.1	10.2	9.1	96	53	20
SS-93	-19	28+18	30.0-30.5	A-6(5)	38	17	24.7	30.1	31.0	14.2	97	82	49
SS-94	-19	28+18	34.0-35.5	A-4(0)	19	6	33.8	34.1	22.1	10.1	100	81	38
SS-95	-19	28+18	39.0-40.5	A-5(10)	39	17	16.6	20.0	37.1	26.3	100	90	69
SS-96	-19	28+18	44.0-45.5	A-6(1)	35	13	34.4	33.8	26.0	6.0	100	82	36
HS-121	-30	35+50	0.0-4.5	A-6(7)	30	13	8.7	26.9	22.0	42.4	100	95	69
HS-122	-30	35+50	4.6-8.0	A-2-4(0)	21	NP	12.4	70.3	10.2	7.1	100	93	28
SS-17	-30	37+00	18.9-20.4	A-1-b(0)	18	NP	74.8	18.4	4.7	2.0	98	21	4

SOIL TEST RESULTS


SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE
							C. SAND	F. SAND	SILT	CLAY	10	40	200	
SS-18	-78	39+70	4.0-6.6	A-2-4(0)	14	NP	34.3	66.3	6.3	4.0	89	71	13	
SS-19	-78	39+70	14.0-16.6	A-2-6(1)	37	21	64.6	18.0	7.4	16.1	93	47	22	
SS-20	46	40+86	3.7-5.3	A-1-5(0)	16	NP	69.2	22.1	3.6	6.0	88	40	8	
SS-21	46	40+86	8.7-10.3	A-1-5(0)	31	NP	81.1	16.3	1.6	3.0	96	41	4	
SS-22	46	40+86	13.7-16.3	A-3(0)	33	NP	44.4	61.9	3.7	1.0	100	74	6	
SS-23	46	40+86	18.7-25.3	A-7-6(11)	46	30	38.0	36.3	16.7	32.3	99	83	61	
S-24	6	41+86	7.0-8.0	A-1-5(0)	18	NP	70.1	21.3	5.6	5.0	83	36	8	
S-25	9	43+80	2.0-3.0	A-6(3)	28	14	24.3	36.4	16.1	24.1	100	87	42	
S-26	9	43+80	10.0-12.0	A-2-4(0)	19	NP	32.6	67.6	5.0	6.0	97	88	13	
S-27	6	46+50	2.0-3.0	A-2-4(0)	17	NP	46.8	38.3	7.8	7.0	98	68	16	
SS-28	6	46+50	3.9-5.4	A-2-4(0)	23	8	33.0	56.6	10.3	23.1	100	81	36	
SS-29	6	46+50	8.9-9.9	A-2-6(2)	40	23	32.1	16.1	3.6	28.3	96	68	31	
S-30	0	48+00	11.0-12.0	A-2-4(0)	33	8	48.2	35.5	14.3	15.1	100	66	27	
S-31	35	51+50	2.0-3.0	A-2-4(0)	17	NP	68.9	23.2	8.8	8.0	98	63	13	
SS-32	35	51+50	3.8-5.3	A-2-4(0)	19	NP	37.3	59.6	14.0	11.1	97	74	24	
SS-33	35	51+50	8.8-9.8	A-7-6(39)	61	34	0.8	1.4	37.4	60.4	100	100	98	37.6
SS-34	35	51+50	13.8-15.3	A-3(0)	18	NP	71.6	20.5	4.8	3.0	97	63	10	


- (A) ROADWAY EMBANKMENT, BROWN, MEDIUM DENSE, MOIST COARSE SAND
- (B) COASTAL PLAIN, DARK BROWN, VERY LOOSE, WET, SAND WITH TRACE OF ORGANIC MATERIALS
- (C) COASTAL PLAIN, GRAY, MEDIUM STIFF, WET SILTY CLAY, HIGHLY PLASTIC



SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-35	45	54+00	3.8-5.3	A-2-6(0)	27	11	64.9	14.1	3.9	17.1	98	59	22
SS-36	45	54+00	8.8-10.3	A-2-4(0)	22	10	81.1	6.5	3.3	9.1	96	29	13
SS-37	-8	56+00	3.9-5.4	A-2-6(1)	39	16	64.7	9.8	5.3	20.1	97	59	25
SS-38	-8	56+00	13.9-15.4	A-2-4(0)	27	8	51.6	26.1	3.2	19.1	100	69	23






SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
HS-124	5	94+60	3.0-4.5	A-2-4(0)	23	3	62.0	32.1	1.7	14.1	96	68	16
SS-59	5	95+50	3.9-4.9	A-7-6(48)	68	42	1.0	0.8	21.8	76.4	100	99	98
SS-60	5	95+60	8.9-10.4	A-2-4(0)	24	NP	63.1	24.1	4.7	8.0	100	70	13

SOIL TEST RESULTS


SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200	
SS-61	3	98+00	4.0-6.5	A-3(0)	19	NP	56.9	35.4	5.7	2.0	98	57	8	
SS-62	3	98+00	9.0-10.5	A-3(0)	20	NP	45.8	46.8	5.5	2.0	100	73	8	
SS-63	3	98+00	14.0-15.5	A-2-4(0)	26	NP	42.4	43.6	9.9	4.0	99	74	14	3.3
SS-64	3	98+00	19.0-20.5	A-1-5(0)	20	NP	86.0	5.0	2.9	6.0	98	25	9	
S-65	-15	100+00	6.0-7.0	A-2-4(0)	20	NP	32.8	56.7	4.5	6.0	100	84	12	
S-66	-15	100+00	12.0-13.0	A-2-4(0)	28	10	64.8	17.7	3.4	14.1	98	64	18	
SS-67	-10	101+50	3.9-5.4	A-2-6(0)	36	19	43.0	36.8	1.1	20.1	93	69	20	
SS-68	-10	101+60	18.9-15.4	A-2-4(0)	23	NP	77.4	9.8	4.7	8.0	100	60	13	
SS-69	-10	101+60	33.9-35.4	A-1-5(0)	20	NP	88.6	6.6	1.7	3.0	98	20	5	
S-70	0	104+00	5.0-6.0	A-3(0)	24	NP	16.4	77.8	2.8	3.0	100	93	6	




SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-71	0	108+50	3.5-5.0	A-3(0)	23	NP	32.6	63.4	3.0	1.0	100	86	5
S-72	0	113+30	7.0-8.0	A-3(0)	24	NP	25.7	70.8	2.7	1.0	100	98	4
S-73	0	113+30	17.0-18.0	A-1-5(0)	21	NP	79.4	17.2	2.4	1.0	94	29	3
SS-74	0	114+2	3.5-5.0	A-2-4(0)	18	NP	29.5	61.4	7.0	2.0	100	88	11
SS-75	0	114+2	13.5-15.0	A-3(0)	24	NP	69.0	28.7	2.2	0.0	100	63	3
SS-76	0	114+2	18.5-20.0	A-2-4(0)	25	NP	4.5	73.2	6.2	17.1	100	97	25
SS-77	0	114+2	23.5-25.0	A-2-4(0)	23	NP	76.3	11.2	3.6	9.0	95	65	13
SS-78	0	114+2	28.5-30.0	A-2-4(0)	21	NP	57.1	33.1	3.8	6.0	100	65	11
SS-79	0	114+2	33.5-35.0	A-7-6(28)	64	25	6.2	6.0	28.4	60.3	100	96	89
SS-80	0	114+2	43.5-45.0	A-7-6(17)	45	24	12.3	14.3	19.2	64.3	100	97	74
SS-81	0	114+2	53.5-55.0	A-2-4(0)	20	NP	60.4	24.4	7.1	8.0	100	74	17
SS-82	0	114+2	58.5-60.0	A-7-5(46)	69	39	0.8	3.8	28.0	72.4	100	100	96
SS-83	0	119+60	3.0-5.1	A-3(0)	18	NP	34.7	57.5	3.8	4.0	100	88	9
SS-84	0	119+60	13.8-15.1	A-3(0)	22	NP	15.6	74.8	2.8	7.0	100	97	10

SOIL TEST RESULTS													
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-86	0	124+50	3.5-5.0	A-3(0)	20	NP	25.4	66.4	2.1	6.0	100	93	9




SOIL TEST RESULTS													
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
S-97	0	136+50	1.0-2.0	A-2-4(0)	20	NP	26.6	58.0	3.3	12.1	100	90	16
S-98	0	136+50	6.0-7.0	A-3(0)	24	NP	15.5	78.2	2.2	4.0	100	95	7
S-99	-40	146+50	5.0-6.0	A-2-4(0)	20	NP	21.4	64.7	2.8	11.1	98	91	15
S-100	-40	146+50	8.0-9.0	A-2-4(0)	22	NP	16.3	69.7	2.9	11.1	100	96	14
SS-105	-10	149+00	3.4-4.9	A-3(0)	20	NP	24.6	70.2	3.2	2.0	100	94	8
SS-106	-10	149+00	13.4-14.9	A-2-4(0)	32	9	18.3	58.0	4.4	24.2	100	95	29




SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-105	-10	149+00	3.4-4.9	A-3(0)	20	NP	24.6	70.2	3.2	2.0	100	94	6
SS-106	-10	149+00	13.4-14.9	A-2-4(0)	32	9	18.3	53.0	4.4	24.2	100	95	29
S-104	0	154+00	13.0-14.0	A-2-6(1)	31	14	16.8	56.4	4.6	22.2	100	96	28
S-102	-15	159+00	1.0-2.0	A-3(0)	22	NP	18.6	75.8	2.5	3.0	100	96	6
S-103	-15	159+00	12.0-13.0	A-2-4(0)	19	NP	17.9	60.7	6.3	15.1	100	95	22




SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-101	0	164+00	8.3-9.8	A-6(2)	31	15	12.7	49.9	12.2	25.2	100	96	39
S-107	-10	169+00	1.0-2.0	A-2-4(0)	18	NP	18.3	67.6	4.9	9.1	100	94	15
S-108	-10	169+00	4.0-5.0	A-2-6(0)	32	12	15.8	54.6	4.3	25.2	100	96	30
SS-109	0	171+50	9.4-10.9	A-2-4(0)	18	NP	22.4	64.5	9.1	4.0	100	93	15




SOIL TEST RESULTS



SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
S-110	10	190+50	3.0-4.0	A-3(0)	22	NP	23.4	71.8	1.8	3.0	100	92	6



SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-111	45	201+00	3.9-5.4	A-3(0)	24	NP	22.3	73.6	0.0	4.0	100	92	5
CBR-1	35	203+50	0.0-5.0	A-3	20	NP	19.9	72.4	2.6	5.0	100	94	9







SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-115	-50	233+00	3.4-4.9	A-3(0)	24	NP	15.8	80.4	0.8	3.0	100	95	4
SS-116	-50	233+00	8.4-9.9	A-3(0)	24	NP	31.0	66.5	1.5	1.0	100	89	3

END PROJECT U-2810
 END OVERLAY
 -L- STA 244+83.86

END GRADE
 BEGIN OVERLAY
 -L- STA 243+10 EL. 188.70



OVERLAY
 INCLUDE 1/2



SOIL TEST RESULTS



SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS- 15	20	11+50	4.0-5.5	A-3(0)	25	NP	44.9	51.1	4.0	0.0	94	75	5
SS- 16	20	11+50	14.0-15.5	A-3(0)	25	NP	28.4	68.0	5.6	0.0	100	95	8

-Y1-
(GEORGE OWEN RD., SR 1133)



SOIL TEST RESULTS													
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-56	20	11+00	4.0-5.5	A-2-6(0)	30	13	53.7	25.5	4.7	16.1	98	58	21
SS-57	20	11+00	19.0-20.5	A-1-6(0)	29	NP	79.0	10.1	2.9	8.0	98	37	11
SS-58	20	11+00	29.0-30.5	A-7-6(27)	53	27	6.2	5.6	23.8	64.3	100	95	90

-Y4-
(SR 3366, ASHEBORO ST.)





SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS- 87	0	14+60	3.5-5.0	A-3(0)	24	NP	44.3	53.3	1.4	1.0	100	77	3
SS- 88	0	14+60	13.5-15.0	A-3(0)	20	NP	41.6	51.2	3.2	4.0	97	71	7



-Y6-

(SR 1137, CRYSTAL SPRINGS RD.)





SOIL TEST RESULTS													
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
S-85	0	18+00	6.0-7.0	A-3(0)	22	NP	36.4	67.8	4.8	1.0	100	89	7

-Y7-
(OAKLAND AVE.)



-Y9-



(SR 2900 KING CHARLES DR.)



SOIL TEST RESULTS





SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-112	-40	12+00	3.6-5.1	A-3(0)	24	NP	22.3	72.3	0.4	5.0	100	93	6
SS-113	30	15+00	3.6-5.1	A-3(0)	24	NP	21.7	74.7	0.6	3.0	100	94	4
SS-114	30	15+00	18.6-20.1	A-3(0)	22	NP	17.8	77.0	2.2	3.0	100	95	7


-Y14-



15

RETAINING WALL ENVELOPE





SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
SS-5	57	16+50	13.8-16.4	A-7-6(8)	42	22	32.8	18.9	20.1	28.2	97	75	52
SS-6	57	16+50	18.9-20.4	A-7-6(22)	44	26	3.4	14.7	29.6	52.3	100	99	87
SS-7	55	17+00	4.1-5.6	A-8(0)	20	NP	49.9	46.6	6.5	3.0	100	79	10
SS-8	55	17+00	14.1-16.6	A-6(8)	36	19	26.4	19.7	17.7	36.2	100	86	57
SS-9	55	17+00	19.1-20.6	A-7-6(42)	63	37	1.0	2.6	28.0	68.4	100	100	97


SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
S-1	62	15+50	1.0-2.0	A-2-4(0)	24	7	48.7	32.1	6.1	13.1	99	71	20
SS-2	62	15+50	4.1-5.6	A-3(0)	22	NP	41.1	53.2	2.6	3.0	99	86	6
SS-3	62	16+50	14.1-16.6	A-3(0)	23	NP	67.3	39.7	1.9	1.0	100	79	3
SS-4	61	16+00	13.8-16.3	A-4(5)	29	9	14.9	19.1	43.9	22.1	96	86	73

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

SOIL TEST RESULTS


SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
S-123	45	93+00	2.5-5.0	A-2-6(0)	37	17	60.6	20.2	0.0	19.2	95	56	19
S-124	47	94+50	2.0-5.5	A-2-4(0)	31	7	45.4	37.0	1.5	16.2	97	69	17
S-125	5	94+50	3.0-4.5	A-2-4(0)	23	3	52.0	32.1	1.7	14.1	96	68	16



150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANICS
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-59	5	95+50	8.9-4.9	A-7-6(48)	68	42	1.0	0.8	21.8	78.4	100	99	98		
SS-60	5	96+60	8.9-10.4	A-2-4(0)	24	NP	63.1	24.1	4.7	8.0	100	70	18		
S-128	45	96+00	1.0-4.5	A-7-6(43)	66	38	1.9	1.4	62.3	34.3	99	98	96	29.0	
S-128	-50	96+50	1.0-2.0	A-5(22)	123	NP	9.7	8.7	60.3	20.3	99	94	81	305.0	40.8



150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANICS
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-127	43	97+00	4.0-6.0	A-7-6(21)	61	28	11.6	9.4	56.8	22.2	98	92	79	28.9	
S-129	-69	97+00	1.0-2.0	A-5(2)	86	NP	28.8	24.3	38.8	8.1	98	84	47		23.1
S-130	-69	97+00	8.0-4.0	A-2-4(0)	17	NP	66.9	26.6	6.3	11.1	96	66	16		
SS-61	3	98+00	4.0-6.6	A-3(0)	19	NP	66.9	26.4	6.7	2.0	96	67	8		
SS-62	3	98+00	9.0-10.6	A-3(0)	20	NP	46.8	46.6	6.6	2.0	100	78	8		
SS-63	3	98+00	14.0-16.5	A-2-4(0)	26	NP	42.4	43.6	9.9	4.0	99	74	14		3.3
SS-64	3	98+00	19.0-20.5	A-1-b(0)	20	NP	86.0	6.0	2.9	6.0	99	25	9		

