



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

March 5, 2014

Addendum No. 1

RE: Contract ID C203369

WBS # 42324.3.FD1

F. A. # BRSTP-2806(1)

Buncombe County (B-5167)

Bridge #108 over Upper Flat Creek on SR-2806

March 18, 2014 Letting

To Whom It May Concern:

Reference is made to the proposal form furnished to you on this project.

The following revision has been made to the proposal:

On Page No. 2 the project special provision entitled "Delay In Right Of Entry" has been revised. Please void Page No. 2 in your proposal and staple the revised Page No. 2 thereto.

Sincerely,

R. A. Garris, PE
Contract Officer

RAG/jag
Attachment

cc: Mr. Ron Hancock, PE
Mr. Jay Swain, PE
Ms. D. M. Barbour, PE
Mr. Rodger Rochelle, PE
Mr. R.E. Davenport, PE
Project File (2)

Mr. Ray Arnold, PE
Ms. Natalie Roskam, PE
Mr. Ronnie Higgins
Ms. Marsha Sample
Ms. Lori Strickland

PERMANENT VEGETATION ESTABLISHMENT:

(2-16-12) (Rev. 10-15-13)

104

SP1 G16

Establish a permanent stand of the vegetation mixture shown in the contract. During the period between initial vegetation planting and final project acceptance, perform all work necessary to establish permanent vegetation on all erodible areas within the project limits, as well as, in borrow and waste pits. This work shall include erosion control device maintenance and installation, repair seeding and mulching, supplemental seeding and mulching, mowing, and fertilizer topdressing, as directed. All work shall be performed in accordance with the applicable section of the *2012 Standard Specifications*. All work required for initial vegetation planting shall be performed as a part of the work necessary for the completion and acceptance of the Intermediate Contract Time (ICT). Between the time of ICT and Final Project acceptance, or otherwise referred to as the vegetation establishment period, the Department will be responsible for preparing the required National Pollutant Discharge Elimination System (NPDES) inspection records.

Once the Engineer has determined that the permanent vegetation establishment requirement has been achieved at an 80% vegetation density (the amount of established vegetation per given area to stabilize the soil) and no erodible areas exist within the project limits, the Contractor will be notified to remove the remaining erosion control devices that are no longer needed. The Contractor will be responsible for, and shall correct any areas disturbed by operations performed in permanent vegetation establishment and the removal of temporary erosion control measures, whether occurring prior to or after placing traffic on the project.

Payment for *Response for Erosion Control, Seeding and Mulching, Repair Seeding, Supplemental Seeding, Mowing, Fertilizer Topdressing, Silt Excavation, and Stone for Erosion Control* will be made at contract unit prices for the affected items. Work required that is not represented by contract line items will be paid in accordance with Articles 104-7 or 104-3 of the *2012 Standard Specifications*. No additional compensation will be made for maintenance and removal of temporary erosion control items.

CONSTRUCTION MORATORIUM

(01-06-12)

SP1 I-15

No in-water work or land disturbance within the 25 ft wide buffer zone will be allowed from **January 1** through **April 15** of any year.

DELAY IN RIGHT OF ENTRY:

(7-1-95)

108

SP1 G22 A

The Contractor will not be allowed right of entry to the parcels listed below **until April 30, 2014** unless otherwise permitted by the Engineer.

<u>Parcel No.</u>	<u>Property Owner</u>
007	Garren Creek VFD
008	Federal National Mortgage Association