J:\B-5164\\Roadway\XSC\Earthwork

| PROJ. REFERENCE NO. | SHEET NO. |
|---|---|
| B-5164 | X-1A |

# STATE OF NORTH CAROLINA
# DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

## *CROSS-SECTION SUMMARY*

| Station L | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) | Station | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) | Station | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) | Station | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) | Station | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) | Station | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 13+70.00 | 0 | 0 | | | | | | | | | | | | | | | |
| 14+00.00 | 1 | 3 | | | | | | | | | | | | | | | |
| 14+50.00 | 2 | 7 | | | | | | | | | | | | | | | |
| 15+00.00 | 3 | 17 | | | | | | | | | | | | | | | |
| 15+05.81 | 1 | 4 | | | | | | | | | | | | | | | |
| 16+23.19 | 0 | 0 | | | | | | | | | | | | | | | |
| 16+50.00 | 9 | 6 | | | | | | | | | | | | | | | |
| 17+00.00 | 22 | 1 | | | | | | | | | | | | | | | |
| 17+50.00 | 15 | 2 | | | | | | | | | | | | | | | |
| 17+60.00 | 0 | 0 | | | | | | | | | | | | | | | |

**Earthwork quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.**

**Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing and removal of existing pavement will be paid for at the contract lump sum price for "Grading".**