DocuSign Envelope ID: E65A348D-36F5-463B-B776-EC933A8E9BB1 Earthwork Volumes.xls

PROJ. REFERENCE NO.	SHEET NO.
B-4591	X-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Undercut Exc. (cu. yd.)	Embt (cu. yd.)
13+50.00	0	0	0
14+00.00	122	0	12
14+50.00	127	0	44
15+00.00	73	0	103
15+50.00	11	0	162
16+00.00	1	0	198
16+50.00	0	0	209
17+00.00	0	0	210
17+50.00	0	0	209
18+00.00	0	0	216
18+50.00	0	0	231
19+00.00	0	28.0	250
19+50.00	0	75.0	228
20+00.00	0	128.0	203
20+50.00	0	87.0	198
21+00.00	0	30.0	168
21+50.00	0	12.0	133
22+00.00	0	0	84
22+50.00	0	0	75
22+70.00	0	0	59

Station L	Uncl. Exc. (cu. yd.)	Undercut Exc. (cu. yd.)	Embt (cu. yd.)
23+70.00	0	0	0
24+00.00	0	52	122
24+50.00	0	102	226
25+00.00	0	57	266
25+50.00	0	29	304
26+00.00	0	0	344
26+50.00	0	0	385
27+00.00	0	0	402
27+50.00	0	0	384
28+00.00	0	0	364
28+50.00	0	0	377
29+00.00	0	0	391
29+50.00	0	0	385
30+00.00	0	0	378
30+50.00	0	0	373
31+00.00	0	0	371
31+50.00	0	0	330
32+00.00	0	0	260
32+50.00	0	0	197
33+00.00	0	0	138
33+50.00	7	0	87
34+00.00	27	0	46
34+50.00	66	0	24
34+70.00	18	0	4