TIP NO.	SHEET NO.
B-4983	SIGN-2

APPROVED: DocuSigned by: Ronald W. King 0695D7A8677C40C...

DATE: 5/6/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 022959 ENGINEER RONALD W. KING

(401) QUANTITY REQ'D 1

36 X 36
S4-5

YELLOW/GREEN REFLECTIVE SHEETING

ONE "U" POST PER SIGN

(402) QUANTITY REQ'D 1

36 X 36
S1-1

YELLOW/GREEN REFLECTIVE SHEETING

ONE "U" POSTS PER SIGN

(403) QUANTITY REQ'D 2

30 X 30
R1-1

ONE "U" POST PER SIGN

(404) QUANTITY REQ'D 1

SCHOOL

24 X 8
S4-3P

MOUNT ABOVE SIGN 405
IN 1 INSTALLATIONS

(405) QUANTITY REQ'D 1

SPEED
LIMIT
25

24 X 30
R2-1

ONE "U" POST PER SIGN

(406) QUANTITY REQ'D 1

7 30 8 30 AM
2 00 3 00 PM

24 X 10
S4-1P

MOUNT BELOW SIGN 405
IN 1 INSTALLATIONS

(407) QUANTITY REQ'D 1

SPEED
LIMIT
35

24 X 30
R2-1

ONE "U" POST PER SIGN

(408) QUANTITY REQ'D 1

END SCHOOL ZONE

24 X 30
S5-2

MOUNT BELOW SIGN 407
IN 1 INSTALLATIONS

TYPE "E" or "F" SIGNS

06-MAY-2014 11:23
P:\TIPProjects-B\B4983\Traffic\Signing\CADD\Quantities & GM Signs\B-4983 Qties.dgn
meaton A1 TE274922