



March 5, 2013

North Carolina Department of Transportation
Geotechnical Engineering Unit
GeoEnvironmental Section
1589 Mail Service Center
Raleigh, North Carolina 27699-1589

Attention: Mr. Terry Fox, L.G. **email:** twfox@ncdot.gov

Reference: **Preliminary Site Assessment Report**
NCDOT Project U-2525B. WBS Element 34821.1.1
Greensboro Eastern Loop from North of US 70 Relocation to US 29 North
of Greensboro
Parcel No. 110, James H. Scales (Cutterz Barber Shop)
4207 Corbin Road
Greensboro, Guilford County, North Carolina
S&ME Project No. 1054-13-008

Dear Mr. Fox,

S&ME, Inc. (S&ME) is submitting this Preliminary Site Assessment (PSA) Report to the North Carolina Department of Transportation (NCDOT). This report presents the background information, field activities, findings, conclusions, and recommendations. These services were performed in general accordance with S&ME Proposal No. P218-12V, Revision 1, dated January 10, 2013, and Contract Number 7000012210 dated June 2, 2012, between NCDOT and S&ME, authorized by NCDOT in its January 11, 2013 Notice to Proceed Letter.

1.0 INTRODUCTION

1.1 Background Information

Based on the NCDOT's December 17, 2012, *Request for Technical and Cost Proposal*, and additional information from the NCDOT's file transfer site, the PSA was conducted within the NCDOT right-of-way (ROW) and/or up to the permanent utility easement at the following property:

Parcel #110 James H. Scales (Cutterz Barber Shop)
4207 Corbin Road, Greensboro, Guilford County, North Carolina

Additional information provided from the NCDOT's file transfer site included:

- CADD and PDF files which were used as a base map for preparation of this PSA.

The PSA included a preliminary geophysical site assessment, and subsequent limited soil

sampling (five borings up to 10 feet below ground surface (ft. bgs.)), within the designated ROW/Easement assessment area. **Figure 1** shows the vicinity and site location, and **Figure 2** shows the site and boring locations. Soil sampling results are shown on **Figure 3**.

Project Information

A site specific Health and Safety Plan was prepared prior to field activities. Underground utilities were located and marked by the North Carolina One-Call Service. A private utility locator, Superior Locate of Greensboro, North Carolina, was also used to mark on site buried utilities and the potential locations of underground storage tanks (USTs) and associated utilities.

S&ME was requested to investigate the existing NCDOT right-of-way (ROW) and/or up to the permanent utility easement in preparation for construction.

2.0 GEOPHYSICAL SITE ASSESSMENT

2.1 Methods and Field Testing

On January 17, 2013, S&ME personnel performed time domain electromagnetic (TDEM) and ground penetrating radar (GPR) surveys within the proposed right-of-way and/or easement of the accessible areas of Parcel #110. These technologies were used in conjunction with each other in order to detect the presence of potential USTs at the site. A brief description of each technology is presented in Section 2.2 and 2.3.

2.2 Time Domain Electromagnetic Methodology

TDEM methods measure the electrical conductivity of shallow subsurface materials. The conductivity is determined by transmitting a time-varying magnetic pulse into the ground and measuring the amplitude and phase shift of the secondary magnetic field. The secondary magnetic field is created when the conductive materials become an inductor as the primary magnetic field is passed through them.

The TDEM surveys were performed with a Geonics EM-61 MKII system, which has a 1.0-meter by 0.5-meter coil system. The EM-61 TDEM system allows discrimination between moderately conductive subsurface materials and very conductive metallic targets as the secondary electromagnetic response from metallic targets are of longer duration than those created by moderately conductive subsurface materials. Accordingly, only the later EM arrivals are recorded so that only the very conductive metallic features are targeted. The surveys were designed to locate metallic tanks within depths of about 5 feet; the assumed maximum depth at which we anticipated the top of a UST to be present. These data were acquired with GPS support and the results were used in Surfer Version 10.0 to geostatistically grid and plot the data. **Figure 4** shows the TDEM location plan.

TDEM data were collected along a grid spaced at approximate 5-foot intervals. **Figures 5 and 6** provide the TDEM dataset collected on Parcel 110.

2.3 Ground Penetrating Radar

GPR is an electromagnetic method that detects interfaces between subsurface materials with differing dielectric constants. The transmitter radiates electromagnetic waves into the earth from an antenna moving across the ground surface. Electromagnetic waves are reflected back to the receiver by interfaces between materials with differing dielectric constants. The intensity of the reflected signal is a function of the contrast in the dielectric constant at the interface, the conductivity of the material that the wave is traveling through, and the frequency of the signal.

The GPR surveys were performed with a GSSI SIRS-3000 unit equipped with a 400 MHz shielded antenna. The depth of GPR wave penetration at a site is a function of the conductivity of the subsurface materials and signal frequency. The average maximum depth of penetration for the GPR survey was approximately six feet below ground surface. **Figure 7** shows the GPR test locations and **Figure 8** presents the GPR profiles of the anomalies.

3.0 SOIL ASSESSMENT

3.1 Soil Sampling

On January 28, 2013, S&ME advanced five soil borings on the subject property within the specified NCDOT ROW/Easement. The soil boring locations were placed along the proposed ROW (**Figures 2 and 3**). S&ME utilized a track mounted Geoprobe® rig to perform the borings and to collect soil samples. S&ME's drill crew advanced the Geoprobe® borings up to approximately 10 ft.-bgs. A photographic log is included in **Appendix I**. Soil samples were continuously collected in five foot long disposable acetate-plastic sleeves that line the hollow stainless-steel sample probes. Soil recovered from the sleeves was classified on-site by S&ME personnel and screened with a Photoionization Detector (PID) at approximately two foot intervals to measure relative headspace concentrations of volatile organic compounds (VOCs).

VOC headspace readings were obtained from an aliquot of each soil sample that was placed in a re-sealable bag. Another portion of the sample was placed in a separate re-sealable bag and stored in an insulated container with ice for possible laboratory analyses. After waiting approximately 15 minutes to allow the sample to reach ambient temperature and headspace equilibrium, the PID probe was inserted into the bag to obtain a headspace reading. A summary of the PID readings and logs of the soil borings are included in **Appendix II**.

Based upon the field screening results and visual observations, a total of 13 soil aliquots were provided to QROS, LLC (QROS) for on-site analysis of gasoline range organics (TPH-GRO) and diesel range organics (TPH-DRO) by ultra-violet fluorescence spectroscopy. Samples exhibiting elevated results based upon the data provided by QROS were then placed directly into laboratory supplies containers and shipped to Pace Analytical

Services (Pace) a North Carolina certified laboratory, under standard chain-of-custody procedure. Soil samples were analyzed for TPH-GRO by EPA Method 8015B/5030B and for TPH-DRO by EPA Method 8015B/3546.

Borings were backfilled with bentonite pellets and soil. Used gloves were bagged and disposed off-site.

3.2 Soil Sample Analytical Results

The approximate soil boring locations are shown in **Figure 2**. The soil sampling laboratory results are summarized in **Table 1** and shown on **Figure 3**, and a copy of the laboratory analytical report is included as an **Appendix III**.

A concentration of TPH-DRO was detected in one of the 13 soil samples provided to QROS. Soil sample 110-3-10 (collected from a depth of 10 ft.-bgs) exhibited a concentration of TPH-DRO of 12.9 milligrams per kilogram (mg/Kg). No additional samples exhibited a concentration of TPH-DRO above the QROS reporting limits. No concentrations of TPH-GRO were detected in any of the samples provided to QROS above the QROS reporting limits. Based upon the QROS results, one soil sample (110-3-10) was submitted to Pace for further analysis.

The Pace laboratory analytical results indicated that neither concentrations of TPH-GRO or TPH-DRO were detected above the laboratory method reporting limits in soil sample 110-3-10.

4.0 CONCLUSIONS AND RECOMMENDATIONS

4.1 Geophysical Assessment

Two TDEM anomalies (Anomalies 1 and 2) not corresponding to site surface features were identified in the TDEM dataset (**Figures 4 through 6**); the anomalies were marked in the field. A total of two GPR profiles were also collected at the site (**Figure 7**). GPR reflections associated with TDEM Anomaly 1 are characterized by relatively small high amplitude responses at about 2 feet bgs. These GPR reflectors are most likely related to a buried reinforced concrete slab. TDEM Anomaly 2 is characterized by a relatively small high amplitude response less than 1 foot bgs. Example GPR profiles are located in **Figure 8**. Anomalies 1 and 2 do not exhibit TDEM response and/or GPR reflections indicative of UST's.

4.2 Soil Assessment

On January 28, 2013, S&ME advanced five soil borings (110-1 through 110-5) each to approximately 10 ft. bgs, on the subject property at the designated locations illustrated on **Figure 2** on January 28, 2013. The on-site analysis of soil sample 110-3-10 by QROS indicated that TPH-DRO was detected at 12.9 mg/Kg. The off-site (Pace) laboratory analytical results of soil samples indicated that neither TPH-GRO or TPH-DRO was detected in a concentration exceeding the laboratory method reporting limits. The off-site laboratory (Pace) is the confirming laboratory, therefore, the final results for the sample

from 110-3-10 are non-detect for TPH-DRO and GRO.

4.3 Recommendations

No indications of petroleum were noted in the field soil screenings or from the off-site laboratory (Pace) analysis. However, the on-site (QROS) analysis reported a detection of 12.9 mg/Kg of TPH-DRO in soil sample 110-3-10. Therefore, it is possible that during construction, NCDOT may encounter soil impacted with petroleum in the vicinity of sample location 110-3 at a depth of approximately 10 feet below ground surface. Assuming that a section of impacted soil approximately five feet thick, and approximately 10 feet in diameter at a depth of approximately 10 feet below ground surface may be impacted; up to approximately 15 cubic yards of soil near location 110-3 may be impacted, S&ME recommends maintaining an awareness level for the possible presence of petroleum in the soil in the project area.

5.0 LIMITATIONS

The estimated volumes of petroleum impacted soil stated in Section 4.3 above are based on the limited data points and soil samples collected by S&ME for this preliminary investigation. The actual amount of petroleum impacted soil encountered during roadway expansion activities may vary depending on the actual grading plan for the project within the affected ROW/Easement.

The results of this preliminary investigation are limited to the boring locations presented herein. The results of this Preliminary Site Assessment are not all inclusive and may not represent existing conditions across the entire property. These results only reflect the current conditions at the locations sampled on the date this Preliminary Site Assessment was performed. This report has been prepared in accordance with generally accepted environmental engineering and geophysical practice for specific application to this project. The conclusions and recommendations contained in this report are based upon applicable standards of our practice in this geographic area at the time this report was prepared. No other warranty, expressed or implied, is made.

The conclusions for the geophysical assessment submitted herein are based upon the data obtained from the non-invasive testing. As such, even within the surveyed area, the survey cannot be considered 100 percent accurate due to inherent method limitations, survey limitations, site features, and/or unforeseen site-specific conditions. Accordingly, the possibility exists that not all subsurface, man-made features have been located.

TDEM and GPR are commonly used to locate USTs, however certain limitations exist. Nearby, metallic objects such as vehicles, metal buildings/storage units, heating/air conditioning units, utilities, etc. will interfere with the TDEM survey. Properties of the subsurface materials (e.g., clay content, moisture, etc.) can have a significant impact on the effective depth of penetration of the GPR survey. Accordingly, non-metallic tanks, tanks at depths below about 5 feet, and tanks outside of the survey area may not have been detected using the geophysical techniques. In addition, due to interference, there may be areas within the proposed survey area where an interpretation of subsurface

features was not feasible.

Regardless of the thoroughness of a geophysical study, there is always a possibility that actual conditions may not match the interpretations. The results should be considered accurate only to the degree implied by the methods used and the method's limitations and data coverage. Accordingly, the possibility exists that not all geologic features at a project site will be located due to either subsurface soil conditions or the occurrence of features outside the lateral limits and below the depth of penetration of the methods used. The location and/or determination (or the lack thereof) of potential USTs is based on our review of provided information and of the geophysical survey. Under no circumstances does S&ME assume any responsibility for damages resulting from the presence of subsurface features that may exist but were not identified by our survey.

This Preliminary Site Assessment was performed solely for NCDOT regarding the above-referenced site and assessment area. This report is provided for the sole use of NCDOT. Use of this report by any other parties will be at such party's sole risk. S&ME disclaims liability for any such use or reliance by third parties. The observations presented in this report are indicative of conditions during the time of the assessment and of the specific areas referenced.

CLOSING

S&ME welcomes the opportunity to assist you with your environmental needs. Should you have any questions regarding this report, please call Tom Raymond at (919) 954-6229.

Sincerely,

S&ME, Inc.



Michael W. Pfeifer
Project Manager



Kevin D. Hon
Project Geophysicist



Thomas P. Raymond, P.E.
Senior Consultant

Attachments: Table 1 – Soil Laboratory Analytical Results
Figure 1 – Vicinity Map
Figure 2 – Site Map with Boring Locations
Figure 3 – Soil Sample Results Map
Figure 4 – TDEM Test Location Plan
Figure 5 – TDEM Data Plot
Figure 6 – TDEM Data Plot with CADD Overlay

Attachments: Table 1 – Soil Laboratory Analytical Results
Figure 1 –Vicinity Map
Figure 2 – Site Map with Boring Locations
Figure 3 – Soil Sample Results Map
Figure 4 – TDEM Test Location Plan
Figure 5 – TDEM Data Plot
Figure 6 – TDEM Data Plot with CADD Overlay
Figure 7 – GPR Test Location Plan
Figure 8 – GPR Profile Lines 084 and 085
Appendix I – Photographic Log
Appendix II – Boring Logs
Appendix III – Laboratory Analytical Report and Chain of Custody

TABLES

TABLE 1
Summary of Soil Analytical Results
NCDOT Project U2525-B
Parcel 110 - Cutterz Barbershop
4207 Corbin Road
Greensboro, Guilford County, North Carolina
S&ME Project No. 1054-13-008


Sample ID	Sample Depth (Ft.-bgs)	Contaminant of Concern	Total Petroleum Hydrocarbons (TPH) Gasoline Range Organics (GRO) and Diesel Range Organics (DRO)			
			GRO by Ultraviolet Fluorescence (UVF) Spectrometry Field Screening	DRO by Ultraviolet Fluorescence (UVF) Spectrometry Field Screening	GRO by EPA Method 8015/3550	DRO by EPA Method 8015/5030
		Date				
110-1-2	2.0	1/28/2013	<1.6	<1.6	Sample Not Submitted for Additional Analysis	
110-1-4	4.0	1/28/2013	<1.3	<1.3		
110-1-6	6.0	1/28/2013	<1.3	<1.3		
110-1-8	8.0	1/28/2013	<1.2	<1.2		
110-1-10	10.0	1/28/2013	<1.3	<1.3		
110-2-2	2.0	1/28/2013	<1.3	<1.3		
110-2-4	4.0	1/28/2013	<1.3	<1.3		
110-2-6	6.0	1/28/2013	<1.3	<1.3		
110-2-8	8.0	1/28/2013	<1.3	<1.3		
110-2-10	10.0	1/28/2013	<1.2	<1.2		
110-3-10	10.0	1/28/2013	<1.3	12.9	<6.7	<7.0
110-4-10	10.0	1/28/2013	<1.3	<1.3	Sample Not Submitted for Additional Analysis	
110-5-10	10.0	1/28/2013	<1.3	<1.3		
North Carolina UST Action Levels			10	10	10	10

Notes:

- Ultraviolet Fluorescence Spectrometry (UVF) analysis performed with QED HC-1 Analyzer
- 1. Concentrations are reported in milligrams per kilogram (mg/Kg).
- 2. Ft.-bgs - feet below ground surface.
- 3. Sample concentrations that exceed the North Carolina Action Levels are shown in Shaded and **BOLD** fields.
- 4. UST: Underground Storage Tank

FIGURES

S:\PROJECTS\2013\13-008 NCDOT 5 Env PSAs\CAD\FIG1_PARCEL110.dwg, FIG1, 2/25/2013 8:44:12 AM, 1:1



TOPO SOURCE: NCGS DRG
LAKE BRANDT, DATED 1951, REV 1994
BROWNS SUMMIT, DATED 1951, REV 1994
CONTOUR INTERVAL 10 FEET


SCALE:	1" = 2000'
DATE:	FEB. 2013
DRAWN BY:	BTR
PROJECT NO:	1054-13-008



S&ME
WWW.SMEINC.COM
NC ENGINEER LICENSE #F-0176
3201 SPRING FOREST RD, RALEIGH, NC 27616



VICINITY MAP
PARCEL 110
CUTTERZ BARBERSHOP - 4207 CORBIN RD
GREENSBORO, NORTH CAROLINA

A-10xx
FIGURE NO.
1



LEGEND

Geoenvironmental Boring
 Potential Soil Contamination:
 Area or Site



SCALE: 1" = 100'
 DATE: FEB. 2013
 DRAWN BY: BTR
 PROJECT NO: 1054-13-008

S&ME
 WWW.SMEINC.COM
 NC ENGINEER LICENSE #F-0176
 3201 SPRING FOREST RD, RALEIGH, NC 27616

SITE MAP
 PARCEL 110 - CUTTERZ BARBERSHOP
 4207 CORBIN RD
 GREENSBORO, NORTH CAROLINA

A-3560
 SHEET NO.
 2



LEGEND

- APPROXIMATE SAMPLE LOCATION
- SOIL SAMPLES COLLECTED JANUARY 28, 2013
- mg/Kg - MILLIGRAMS PER KILOGRAM
- GRO - TOTAL PETROLEUM HYDROCARBONS GASOLINE RANGE ORGANICS
- DRO - TOTAL PETROLEUM HYDROCARBONS DIESEL RANGE ORGANICS
- UVF - ULTRAVIOLET FLUORESCENCE FIELD SCREENING
- EPA - METHODS 8015/3550 & 8015/5030
- * INDICATES EXCEEDENCE OF STATE ACTION LEVEL OF 10 mg/Kg




IMAGE SOURCE: NC ONEMAP, DATED 2010


A-3561

SCALE:	1" = 40'
DATE:	FEB. 2013
DRAWN BY:	BTR
PROJECT NO:	1054-13-008

SOIL CONSTITUENT MAP
 PARCEL 110 - CUTTERZ BARBERSHOP
 4207 CORBIN RD
 GREENSBORO, NORTH CAROLINA

FIGURE NO.


3



REFERENCE:

- Google Earth Aerial Photograph
- Dated February 2, 2012

LEGEND

 TDEM Path

SCALE: NTS

DRAWN BY: KDH

CHECKED BY: DDB

DATE: 1-23-13



TDEM TEST LOCATION PLAN
NCDOT No. U-2525B – Parcel 110 Cutterz Barberhsop
4207 Corbin Road Greensboro, Guilford County, North Carolina


PROJECT NO.: 1054-13-008

FIGURE NO.

4



Conductivity (mV)



REFERENCE:

- Google Earth Aerial Photograph
- Dated February 2, 2012


SCALE:	NTS
DRAWN BY:	KDH
CHECKED BY:	DDB
DATE:	1-23-13



<p>TDEM DATA PLOT</p> <p>NCDOT No. U-2525B – Parcel 110 Cutterz Barbershop</p> <p>4207 Corbin Road Greensboro, Guilford County, North Carolina</p>	<p>FIGURE NO.</p> <p>5</p>
<p>PROJECT NO.: 1054-13-008</p>	



Conductivity (mV)



SCALE: NTS
DRAWN BY: KDH
CHECKED BY: DDB
DATE: 1-23-13



TDEM DATA PLOT WITH CADD OVERLAY
NCDOT No. U-2525B – Parcel 110 Cutterz Barbershop
4207 Corbin Road Greensboro, Guilford County, North Carolina
PROJECT NO.: 1054-13-008

FIGURE NO.
6



REFERENCE:

- Google Earth Aerial Photograph
- Dated February 2, 2012

LEGEND

-  GPR Line
-  TDEM Anomaly

SCALE: NTS

DRAWN BY: KDH

CHECKED BY: DDB

DATE: 1-23-13



GPR TEST LOCATION PLAN


NCDOT No. U-2525B – Parcel 110 Cutterz Barbershop
4207 Corbin Road Greensboro, Guilford County, North Carolina

PROJECT NO.: 1054-13-008


FIGURE NO.

7

Line 066



Line 067



SCALE: AS SHOWN

DRAWN BY: KDH

CHECKED BY: DDB

DATE: 1-23-13



GPR PROFILE EXAMPLES – LINES 066 AND 067
NCDOT No. U-2525B – Parcel 110 Cutterz Barbershop
4207 Corbin Road Greensboro, Guilford County, North Carolina

PROJECT NO.: 1054-13-008

FIGURE NO.

8

APPENDIX I

Photographic Log



1 View of front of Cutterz Barbershop facing the northeast.



2 View of the southwestern corner of Cutterz Barbershop facing northeast.



NCDOT Project U2525B
 Parcel 110 Cutterz Barbershop
 4207 Corbin Road, Greensboro, Guilford County, North Carolina

S&ME Project No. 1054-13-008

Taken by: ALB

Date Taken: 2/11/2013

APPENDIX II

Boring Logs

BORING LOG



Project Name: NCDOT Project U2525-B
Parcel 110
S&ME Project No. 1054-13-008

Boring Number: 110-1
Sampling Personnel: Lyndal Butler
Date Drilled: 1/28/2013
Depth to Groundwater: Not Encountered
Total Depth: 10 ft. bgs.

Drilling method: Geoprobe® Direct Push

STRATIFICATION

Depth (Feet)		Soil Description	PID Reading (ppm)	Sample No. and Depth	
From	To			Sample No. analyzed on-site by QROS	Depth (Ft-BGS)
0	0.4	Topsoil			
0.4	2.0	ML: Clayey Silt, yellow tan and orange brown, dry ML: Silt, yellow tan, dry, relict texture	<1	110-1-2	2.0
2.0	3.0				
3.0	4.0		<1	110-1-4	4.0
4.0	5.0				
5.0	6.0		<1	110-1-6	6.0
6.0	7.0				
7.0	8.0		<1	110-1-8	8.0
8.0	9.0				
9.0	10.0		<1	110-1-10	10.0
			<i>Boring terminated at 10.0 ft. bgs.</i>		

Notes:

- 1. Ft-BGS: Feet Below Ground Surface
- 2. PID: Photo-Ionization Detector
- 3. PPM: parts per million (volume/volume)
- 4.*Indicates sample was sent to off-site laboratory for additional analysis.

Boring Number: 110-2
Sampling Personnel: Lyndal Butler
Date Drilled: 1/28/2013
Depth to Groundwater: Not Encountered
Total Depth: 10 ft. bgs.

Drilling method: Geoprobe® Direct Push

STRATIFICATION

Depth (Feet)		Soil Description	PID Reading (ppm)	Sample No. and Depth	
From	To			Sample No. analyzed on-site by QROS	Depth (Ft-BGS)
0	0.4	Topsoil			
0.4	2.0	ML: Clayey Silt, yellow tan and orange brown, dry ML: Silt, yellow tan, dry, relict texture	<1	110-2-2	2.0
2.0	3.0				
3.0	4.0		<1	110-2-4	4.0
4.0	5.0				
5.0	6.0		<1	110-2-6	6.0
6.0	7.0				
7.0	8.0		<1	110-2-8	8.0
8.0	9.0				
9.0	10.0		<1	110-2-10	10.0
			<i>Boring terminated at 10 ft. bgs.</i>		

Notes:

- 1. Ft-BGS: Feet Below Ground Surface
- 2. PID: Photo-Ionization Detector
- 3. PPM: parts per million (volume/volume)
- 4.*Indicates sample was sent to off-site laboratory for additional analysis.

BORING LOG



Project Name: NCDOT Project U2525-B

Parcel 110

S&ME Project No. 1054-13-008

Boring Number: 110-3
Sampling Personnel: Lyndal Butler
Date Drilled: 1/28/2013
Depth to Groundwater: Not Encountered
Total Depth: 10 ft. bgs.

Drilling method: Geoprobe® Direct Push

STRATIFICATION

Depth (Feet)		Soil Description	PID Reading (ppm)	Sample No. and Depth	
From	To			Sample No. analyzed on-site by QROS	Depth (Ft-BGS)
0	0.4	Asphalt and base course			
0.4	2.0	ML: Clayey Silt, yellow tan and orange brown, dry ML: Silt, yellow tan, relict texture, dry, moist 9.5 feet	<1		
2.0	3.0				
3.0	4.0		<1		
4.0	5.0		<1		
5.0	6.0		<1		
6.0	7.0		<1		
7.0	8.0		<1		
8.0	9.0		<1		
9.0	10.0		<1	110-3-10*	10.0
		<i>Boring terminated at 10 ft. bgs.</i>			

Notes:

- 1. Ft-BGS: Feet Below Ground Surface
- 2. PID: Photo-Ionization Detector
- 3. PPM: parts per million (volume/volume)
- 4.*Indicates sample was sent to off-site laboratory for additional analysis.

Boring Number: 110-4
Sampling Personnel: Lyndal Butler
Date Drilled: 1/28/2013
Depth to Groundwater: Not Encountered
Total Depth: 10 ft. bgs.

Drilling method: Geoprobe® Direct Push

STRATIFICATION

Depth (Feet)		Soil Description	PID Reading (ppm)	Sample No. and Depth	
From	To			Sample No. analyzed on-site by QROS	Depth (Ft-BGS)
0	0.5	Topsoil			
0.5	2.0	ML: Clayey Silt, yellow tan and orange brown, dry ML: Silt, yellow tan, dry, relict texture ML: Fine sandy Silt, orange brown, dry	<1		
2.0	3.0				
3.0	4.0		<1		
4.0	5.5		<1		
5.5	6.0		<1		
6.0	7.0		<1		
7.0	8.0		<1		
8.0	9.0		<1		
9.0	10.0		<1	110-4-10	10.0
		<i>Boring terminated at 10 ft. bgs.</i>			

Notes:

- 1. Ft-BGS: Feet Below Ground Surface
- 2. PID: Photo-Ionization Detector
- 3. PPM: parts per million (volume/volume)
- 4.*Indicates sample was sent to off-site laboratory for additional analysis.

BORING LOG



Project Name: NCDOT Project U2525-B

Parcel 110

S&ME Project No. 1054-13-008

Boring Number: 110-5
Sampling Personnel: Lyndal Butler
Date Drilled: 1/28/2013
Depth to Groundwater: Not Encountered
Total Depth: 10 ft. bgs.

Drilling method: Geoprobe® Direct Push

STRATIFICATION

Depth (Feet)		Soil Description	PID Reading (ppm)	Sample No. and Depth	
From	To			Sample No. analyzed on-site by QROS	Depth (Ft-BGS)
0	0.4	Asphalt and base course			
0.4	2.0	ML: Clayey Silt, yellow tan and orange brown, dry	<1		
2.0	3.0				
3.0	4.0		<1		
4.0	5.0				
5.0	6.0	ML: Silt, yellow tan, dry, relict texture	<1		
6.0	7.0				
7.0	8.0		<1		
8.0	9.0				
9.0	10.0	ML: Silt, yellow tan, moist	<1	110-5-10	10.0
<i>Boring terminated at 10 ft. bgs.</i>					

Notes:

1. Ft-BGS: Feet Below Ground Surface
2. PID: Photo-Ionization Detector
3. PPM: parts per million (volume/volume)
- 4.*Indicates sample was sent to off-site laboratory for additional analysis.

APPENDIX III

Laboratory Analytical Report and Chain of Custody Form



KB LABS, INC.
6821 SW Archer Road
Gainesville, Florida 32608
Telephone (352) 367-0073
Fax (352) 378-6491
Email: info@kbmobilelabs.com

February 14, 2013

Michael Pfeifer
S&ME
3201 Spring Forest Road
Raleigh, NC 27616

**RE: NCDOT
KB Labs Project # 13-7**

Dear Mr. Pfeifer:

Enclosed is the final report of the on-site analysis performed by KB Labs, Inc. at the above referenced site. Samples were collected and analyzed onsite during January 29-Feb 1. Included are a brief project narrative, data report narrative, final analytical results, and sample chain-of-custody form.

If you have any questions, please do not hesitate to call me or Kelly Bergdoll, President of KB Labs, at (352) 367-0073.

Sincerely,

KB Labs, Inc.

Todd Romero
Director of Operations

PROJECT NARRATIVE

Project Scope

Between January 29 and February 1, 2013, a total of 89 soil samples were analyzed for S&ME in Greensboro. The samples were analyzed for field TPH.

Analytical Procedure

All samples were analyzed using Ultra -violet Fluorescence Spectrometry. For soils, ten grams of soil was extracted in 20 mL of methanol. Extracts were then analyzed on a UV fluorometer. Fluorescence was compared against a series of prepared calibration standards to produce the results. For this project a QED analyzer was used that provides a fluorescence fingerprint image for each sample and uses a spectral library to help identify the dominant hydrocarbon type where possible.

Analytical Results

Laboratory results were provided to the client on an as-completed basis. Final results of the on-site analyses are provided in this report. The data produced and reported in the field has been reviewed and approved for this final report by the Director of Operations for KB Labs and was reviewed by QROS.

Method Blanks: Daily analysis of methanol reagent samples was performed in order to monitor the cleanliness of the analytical system before and during each analytical run.
Continuing Calibration: Following initial standardization with a five point PAH curve, standards were analyzed periodically to determine the stability of the calibration before, during, and after each analytical run.

Data were reported on an as received (wet weight) basis.



Hydrocarbon Analysis Results

Client: S&ME
Address: US-29 Greensboro, NC

Samples taken 1/28/13, 1/29/13
Samples extracted 1/29/13
Samples analysed 1/29/13

Contact: Lyndal Butler

Operator Chris Horrell

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	110-1-2	31.4	<1.6	<1.6	<1.6	<1.6	< 1.57	< 0.16	< 0.078	9.9	24.7	65.4	PAH
s	110-1-4	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	11.2	24.7	64.2	PAH
s	110-1-6	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	11.9	22.8	65.3	PAH
s	110-1-8	24.8	<1.2	<1.2	<1.2	<1.2	< 1.24	< 0.12	< 0.062	11.6	26.4	62	V.Deg Fuel (est) 18.5%
s	110-1-10	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	ID not possible
s	110-2-2	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	0	5.2	94.8	ID not possible
s	110-2-4	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	0	10.3	89.7	ID not possible
s	110-2-6	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	11.6	19.1	69.3	V.Deg Fuel (est) 12.3%
s	110-2-8	24.5	<1.2	<1.2	<1.2	<1.2	< 1.23	< 0.12	< 0.061	12	21.3	66.6	ID not possible
s	116-14-10	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	6.1	55	38.9	V.Deg.PHC 33.2%

Initial Calibrator QC check

Low Range Calibrator Final check

High Range Calibrator Final check

Results generated by a QED HC-1 analyser

Fingerprints are tentative identifications based on operator selected library matches

Concentration values in mg/kg for soil samples and mg/L for water samples.

Fingerprint match abbreviations

Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match

Soil values are not corrected for moisture or stone content

(SBS)= site specific background subtracted (LBS)= Library background subtracted

%=Overall Fingerprint match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: US-29 Greensboro, NC

Samples taken 1/28/13, 1/29/13
Samples extracted 1/29/13
Samples analysed 1/29/13

Contact: Lyndal Butler

Operator Chris Horrell

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	110-2-10	24.5	<1.2	<1.2	<1.2	<1.2	< 1.23	< 0.12	< 0.061	0	0	100	ID not possible
s	116-16-10	24.5	<1.2	25.4	21.5	46.9	9.79	< 0.12	< 0.061	98.9	1	0.1	Deg Kerosene (est) + Deg.Petrol (est) 47.4%
s	116-16-10 dup	24.5	10.8	30	28.3	58.3	11.83	0.19	< 0.061	99	0.7	0.3	Deg Kerosene (est) + Deg.Petrol 67.7%
s	110-3-10	26.0	<1.3	<1.3	12.9	12.9	8.02	< 0.13	< 0.065	57.9	34.5	7.5	Degraded Fuel (est) 87.3%
s	116-17-10	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	0	0	100	ID not possible
s	110-4-10	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	ID not possible
s	110-5-10	25.2	<1.3	<1.3	<1.3	<1.3	< 1.26	< 0.13	< 0.063	0	0	100	ID not possible
s	116-18-4	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	ID not possible
s	155-1-6	24.5	<1.2	<1.2	<1.2	<1.2	< 1.23	< 0.12	< 0.061	0	0	100	ID not possible
s	155-3-8	24.5	<1.2	<1.2	2.4	2.4	< 1.23	< 0.12	< 0.061	5.8	72.4	21.8	V.Deg Diesel + Deg.Fuel (est) 48.8%
Initial Calibrator QC check						Low Range Calibrator Final check High Range Calibrator Final check							

Results generated by a QED HC-1 analyser

Fingerprints are tentative identifications based on operator selected library matches

Concentration values in mg/kg for soil samples and mg/L for water samples.

Fingerprint match abbreviations

Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match

Soil values are not corrected for moisture or stone content

(SBS)= site specific background subtracted (LBS)= Library background subtracted

%=Overall Fingerprint match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro, NC

Samples taken 1/28, 1/29, 1/30 2013
Samples extracted 1/30/13
Samples analysed 1/30/13

Contact: Lyndal Butler

Operator CAH

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	116-16-8	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	ID not possible
s	116-16-12	25.5	<1.3	8.8	13.7	22.5	5.99	< 0.13	< 0.064	96.6	2.3	1.1	Deg Kerosene (est) + Deg.Petrol (est) 52%
s	116-16-14	25.0	<1.3	<1.3	<1.3	<1.3	< 1.25	< 0.13	< 0.063	0	3.8	96.2	Background Organics
s	116-18-14	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	76.8	4.4	18.8	Deg Petrol (est) 1.3%
s	155-4-10	25.7	<1.3	4.2	30.6	34.8	14.29	0.23	< 0.064	91.5	7.3	1.2	Deg Kerosene (est) 58.6%
s	155-4-12	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	86.9	2.3	10.8	Deg Kerosene (est) 21.4%
s	155-5-10	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	Background Organics
s	155-6-4	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	9.9	2.4	87.6	Deg Diesel 44.6%
s	155-7-6	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	Background Organics
s	155-8-4	25.0	<1.3	<1.3	<1.3	<1.3	< 1.25	< 0.13	< 0.063	83.8	0	16.2	Background Organics

Initial Calibrator QC check

Low Range Calibrator Final check
 High Range Calibrator Final check

Results generated by a QED HC-1 analyser

Fingerprints are tentative identifications based on operator selected library matches

Concentration values in mg/kg for soil samples and mg/L for water samples.

Fingerprint match abbreviations

Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match

Soil values are not corrected for moisture or stone content

(SBS)= site specific background subtracted (LBS)= Library background subtracted

%=Overall Fingerprint match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro, NC

Samples taken 1/28, 1/29, 1/30 2013
Samples extracted 1/30/13
Samples analysed 1/30/13

Contact: Lyndal Butler

Operator CAH

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	116-2-2	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	0	0	100	ID not possible
s	116-1-6	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	ID not possible
s	116-3-2	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	ID not possible
s	116-4-2	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	ID not possible
s	116-5-2	24.8	<1.2	<1.2	<1.2	<1.2	< 1.24	< 0.12	< 0.062	0	0	100	ID not possible
s	116-6-2	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	0	0	100	ID not possible
s	116-7-2	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	ID not possible
s	116-8-9	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	41.2	5.7	53.1	Deg Petrol (est) 1.3%
s	116-9-10	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	80.9	17.3	1.8	Deg Diesel 34.3%
s	116-10-8	25.7	<1.3	<1.3	12.4	12.4	8.22	0.21	< 0.064	55.3	40.8	3.9	+ Deg.Fuel 19.1%

Initial Calibrator QC check

Low Range Calibrator Final check

High Range Calibrator Final check

Results generated by a QED HC-1 analyser

Fingerprints are tentative identifications based on operator selected library matches

Concentration values in mg/kg for soil samples and mg/L for water samples.

Fingerprint match abbreviations

Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match

Soil values are not corrected for moisture or stone content

(SBS)= site specific background subtracted (LBS)= Library background subtracted

%=Overall Fingerprint match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro, NC

Samples taken 1/28, 1/29, 1/30 2013
Samples extracted 1/30/13
Samples analysed 1/30/13

Contact: Lyndal Butler

Operator CAH

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	116-11-4	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	ID not possible
s	116-12-4	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	ID not possible
s	66-2-15	25.7	<1.3	<1.3	17	17	9.76	0.19	< 0.064	82.1	12.8	5.1	Deg Diesel 64.9%
s	66-2-20	26.0	<1.3	<1.3	10.6	10.6	6.57	< 0.13	< 0.065	90.3	7.9	1.9	Deg Diesel 47.3%
s	116-13-4	25.2	<1.3	<1.3	<1.3	<1.3	< 1.26	< 0.13	< 0.063	0	0	100	ID not possible
s	137-1-10	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	ID not possible
s	137-2-10	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	ID not possible
s	137-3-10	25.2	<1.3	<1.3	<1.3	<1.3	< 1.26	< 0.13	< 0.063	0	0	100	ID not possible
s	137-4-10	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	0	0	100	Background Organics
s	137-5-6	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	0	0	100	ID not possible

Initial Calibrator QC check

Low Range Calibrator Final check

High Range Calibrator Final check

Results generated by a QED HC-1 analyser

Fingerprints are tentative identifications based on operator selected library matches

Concentration values in mg/kg for soil samples and mg/L for water samples.

Fingerprint match abbreviations

Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match

Soil values are not corrected for moisture or stone content

(SBS)= site specific background subtracted (LBS)= Library background subtracted

%=Overall Fingerprint match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro NC

Samples taken 1.30, 1.31
Samples extracted 1.31.13
Samples analysed 1/31/13

Contact: Lyndal Butler

Operator Chris Horrell

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	137-9-15	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	95.5	0	4.5	Deg.Fuel 69.1%
s	137-10-15	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	94.5	1.6	3.9	Deg.Fuel 62.6%
s	137-8-15	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	81.8	4.9	13.3	Background Organics
s	137-6-10	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	Deg.Fuel Residue 18.9%
s	137-7-2	25.5	<1.3	<1.3	2.1	2.1	< 1.27	< 0.13	< 0.064	84.4	14.3	1.3	Deg Petrol (est) 48.2%
s	137-11-15	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	Deg.Fuel Residue 19.7%
s	66-6-10	1570.3	<39	2432	31283	33715	16658	198	<2	87.8	10.5	1.7	Deg.Fuel
s	66-6-20	1586.0	<40	<40	<40	<40	< 79	<8	<2	0	0	100	Deg.Fuel Residue 9.7%

Initial Calibrator QC check OK

Low Range Calibrator Final check
 High Range Calibrator Final check

Results generated by a QED HC-1 analyser

Fingerprints provide a tentative hydrocarbon identification based on operator selected library matches

Concentration values in mg/kg for soil samples and mg/L for water samples.

Fingerprint match abbreviations

Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match

Soil values are not corrected for moisture or stone content

(SBS)= site specific background subtracted (LBS)= Library background subtracted

% = match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro, NC

Samples taken
Samples extracted
Samples analysed

Contact: Lyndal Butler

Operator CAH

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	137-12-15	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	Match not possible
s	137-13-2	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	97.4	1.1	1.6	Deg Diesel

Initial Calibrator QC check	OK	Low Range Calibrator Final check	OK	0.07
		High Range Calibrator Final check	OK	1.61

Results generated by a QED HC-1 analyser
 Concentration values in mg/kg for soil samples and mg/L for water samples.
 Soil values are not corrected for moisture or stone content

Fingerprints provide a tentative hydrocarbon identification based on operator selected library matches
 Fingerprint match abbreviations Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match
 (SBS)= site specific background subtracted (LBS)= Library background subtracted % = match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro, NC

Samples taken Thursday, January 31, 2013
Samples extracted Thursday, January 31, 2013
Samples analysed Thursday, January 31, 2013

Contact: Lyndal Butler

Operator CAH

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	66-5-14	25.7	<1.3	<1.3	2.5	2.5	< 1.29	< 0.13	< 0.064	57.6	41.6	0.8	Deg.Fuel Residue 9.9%
s	66-7-19	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	91.7	6.1	2.2	Match not possible
s	137-14-2	25.7	<1.3	<1.3	2.1	2.1	1.89	< 0.13	< 0.064	47.5	36	16.5	V.Deg.PHC (LBS) 74%
s	137-15-2	25.0	<1.3	<1.3	<1.3	<1.3	< 1.25	< 0.13	< 0.063	0	0	100	Match not possible
s	66-1-15	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	96.6	3.4	Deg.Fuel Residue 57.5%
s	66-3-15	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	Match not possible
s	66-4-15	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	74.5	25.5	Match not possible
s	66-7-17	26.0	<1.3	<1.3	2.9	2.9	1.84	< 0.13	< 0.065	45.6	38	16.3	Degraded Fuel (est) 77.6%
s	66-8-15	25.0	<1.3	<1.3	<1.3	<1.3	< 1.25	< 0.13	< 0.063	0	0	100	Match not possible
s	66-9-15	25.7	<1.3	<1.3	4.2	4.2	1.69	< 0.13	< 0.064	42.4	33	24.6	Degraded Fuel (est) 62.8%
Initial Calibrator QC check			OK		Low Range Calibrator Final check				OK		0.08		
High Range Calibrator Final check			OK		1.57								

Results generated by a QED HC-1 analyser

Fingerprints provide a tentative hydrocarbon identification based on operator selected library matches

Concentration values in mg/kg for soil samples and mg/L for water samples.

Fingerprint match abbreviations

Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match

Soil values are not corrected for moisture or stone content

(SBS)= site specific background subtracted (LBS)= Library background subtracted

% = match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro, NC

Samples taken 1.31.13
Samples extracted 1.31.13
Samples analysed 1.31.13

Contact: Lyndal Butler

Operator CAH

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	66-10-9	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	Match not possible
s	66-11-15	25.7	<1.3	<1.3	<1.3	<1.3	< 1.29	< 0.13	< 0.064	0	0	100	Match not possible

Initial Calibrator QC check			OK			Low Range Calibrator Final check			Low			0.06
						High Range Calibrator Final check			OK			1.53

Results generated by a QED HC-1 analyser
 Concentration values in mg/kg for soil samples and mg/L for water samples.
 Soil values are not corrected for moisture or stone content

Fingerprints provide a tentative hydrocarbon identification based on operator selected library matches
 Fingerprint match abbreviations Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match
 (SBS)= site specific background subtracted (LBS)= Library background subtracted % = match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: US-29 Greensboro, NC

Samples taken 2.1.13
Samples extracted 2.1.13
Samples analysed 2.1.13

Contact: Lyndal Butler

Operator Chris Horrell

Project: NCDOT U2525B

Hydrocarbon Analysis Results													
Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	66-19-9	119.6	<6	83.1	915.3	998.4	788.4	9.6	<0.3	96.8	2.6	0.6	Deg Diesel 68.9%
s	66-19-11	119.6	<6	<6	47.1	47.1	25.7	<0.6	<0.3	92.9	6.1	1	V.Deg Diesel 69.9%
s	66-19-13	25.5	<1.3	2.6	43.3	45.9	29.25	0.43	< 0.064	93.2	4.6	2.2	V.Deg Diesel 57.9%
s	66-19-15	60.8	<3	5.8	299.3	305.1	257.31	3.39	< 0.152	90.7	7.6	1.7	V.Deg Diesel 55.4%
s	66-19-11 Duplicate	60.8	<3	<3	49.4	49.4	29.47	0.51	< 0.152	90.6	6.8	2.6	V.Deg Diesel 62.2%
s	66-23-5	25.2	<1.3	2.2	23.7	25.9	13.93	0.23	< 0.063	85.6	10.9	3.5	Deg Diesel + Deg.Fuel (est) 68.8%
s	66-23-15	25.2	<1.3	<1.3	2.8	2.8	2.1	< 0.13	< 0.063	71.5	19.1	9.4	Degraded Fuel (est) 71%
s	66-13-15	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	0	100	Match not possible
s	66-14-8	35.7	<1.8	7.6	190	197.5	145	1.92	< 0.090	90.9	7.8	1.3	Deg.Fuel 56.6%
s	66-14-15	24.8	<1.2	22.9	81.1	104	29.38	0.58	0.07	94.2	3.3	2.5	V.Deg Kerosene (est) (LBS) 60.7%
Initial Calibrator QC check			OK			Low Range Calibrator Final check			OK			0.08	
High Range Calibrator Final check			OK			High Range Calibrator Final check			OK			1.59	

Results generated by a QED HC-1 analyser
 Concentration values in mg/kg for soil samples and mg/L for water samples.
 Soil values are not corrected for moisture or stone content

Fingerprints provide a tentative hydrocarbon identification based on operator selected library matches
 Fingerprint match abbreviations
 (SBS)= site specific background subtracted (LBS)= Library background subtracted

Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match
 % = match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro NC

Samples taken 2.1.13
Samples extracted 2.1.13
Samples analysed 2.1.13

Contact: Lyndal Butler

Operator Chris Horrell

Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	66-17-15	24.8	<1.2	<1.2	2	2	< 1.24	< 0.12	< 0.062	78.9	17.4	3.7	Match not possible
s	66-20-11	40.8	<2	<2	67.2	67.2	51.31	0.77	< 0.102	44.6	50.8	4.6	Degraded Fuel (est) 75.9%
s	66-21-15	25.0	<1.3	<1.3	<1.3	<1.3	< 1.25	< 0.13	< 0.063	0	57.9	42.1	Match not possible
s	66-22-7	24.8	<1.2	<1.2	<1.2	<1.2	< 1.24	< 0.12	< 0.062	0	0	100	Match not possible
s	66-24-13	25.2	<1.3	<1.3	<1.3	<1.3	<1.26	<0.13	<0.063	0	0	100	Match not possible
s	66-25-12.5	806.0	<40.3	176.2	4515.8	4692	3242.7	41.5	<2.02	95.7	3.6	0.7	Deg Diesel 49.8%
s	66-26-11	1554.9	<39	54	7184	7238	4779	64	<2	94.7	4.5	0.8	Deg Diesel 54.2%
s	66-6-10 Duplicate	3114.9	<78	976	27695	28671	16407	207	<3	95.6	4.1	0.3	Deg Diesel 55.2%
s	66-27-15	25.7	<1.3	<1.3	7.2	7.2	4.26	< 0.13	< 0.064	72.5	21.9	5.6	Degraded Fuel (est) 90.3%
s	66-28-15	26.0	<1.3	<1.3	<1.3	<1.3	< 1.3	< 0.13	< 0.065	0	28.3	71.7	Match not possible
Initial Calibrator QC check										OK			
Low Range Calibrator Final check										Low			0.06
High Range Calibrator Final check										Low			1.43

Results generated by a QED HC-1 analyser
 Concentration values in mg/kg for soil samples and mg/L for water samples.
 Soil values are not corrected for moisture or stone content

Fingerprints provide a tentative hydrocarbon identification based on operator selected library matches
 Fingerprint match abbreviations Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match
 (SBS)= site specific background subtracted (LBS)= Library background subtracted % = match confidence



Hydrocarbon Analysis Results

Client: S&ME
Address: Greensboro NC

Samples taken 2.1.13
Samples extracted 2.1.13
Samples analysed 2.1.13

Contact: Lyndal Butler

Operator Chris Horrell











Project: NCDOT U2525B

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
										% light	% mid	% heavy	
s	66-29-15	25.5	<1.3	<1.3	<1.3	<1.3	< 1.27	< 0.13	< 0.064	0	0	100	Match not possible

Initial Calibrator QC check OK	Low Range Calibrator Final check OK	0.08
	High Range Calibrator Final check Low	1.40


Results generated by a QED HC-1 analyser
 Concentration values in mg/kg for soil samples and mg/L for water samples.
 Soil values are not corrected for moisture or stone content

Fingerprints provide a tentative hydrocarbon identification based on operator selected library matches
 Fingerprint match abbreviations Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match
 (SBS)= site specific background subtracted (LBS)= Library background subtracted % = match confidence




ID not possible


110-2-10



Deg Kerosene (est) + Deg.Petrol (est) 47.4% 116-16-10




Deg Kerosene (est) + Deg.Petrol 67.7% 116-16-10 dup




Degraded Fuel (est) 87.3%

110-3-10




ID not possible

116-17-10




ID not possible

110-4-10




ID not possible

110-5-10




ID not possible

116-18-4




ID not possible

155-1-6




V.Deg Diesel + Deg.Fuel (est) 48.8%

155-3-8




ID not possible

116-16-8




Deg Kerosene (est) + Deg.Petrol (est) 52%

116-16-12




Background Organics

116-16-14




Deg Petrol (est) 1.3%

116-18-14




Deg Kerosene (est) 58.6%

155-4-10




Deg Kerosene (est) 21.4%

155-4-12




Background Organics

155-5-10




Deg Diesel 44.6%

155-6-4




Background Organics











155-7-6





















Background Organics

155-8-4











0%

0

0%

0



0%

0

0%

0

0%

0

0%

0

0%


0

0%

0


Deg.Fuel Residue 9.9%

66-5-14




Match not possible

66-7-19




V.Deg.PHC (LBS) 74%

137-14-2




Match not possible

137-15-2




Deg.Fuel Residue 57.5%

66-1-15




Match not possible

66-3-15




Match not possible

66-4-15




Degraded Fuel (est) 77.6%

66-7-17




Match not possible



66-8-15



Degraded Fuel (est) 62.8%

66-9-15





0%

0

0%

0

0%

0

0%











0











0%

0

0%


0





Project NCDOT U2525B

Date Friday, February 01, 2013



0%

0

0%

0

0%

0

0%

0

0%


0

0%

0

0%

0



25132 SW 1st Avenue
 Newberry, FL 32669
 TEL (352) 472-5830
 FAX (352) 472-5832


200 Quade Drive
 Cary, NC 27513
 TEL (919) 678-0030

CHAIN-OF-CUSTODY RECORD

MOBILE UNIT #

CLIENT NAME		PROJECT NAME & ADDRESS						SAMPLE MATRIX	NUMBER OF CONTAINERS	IDENTIFY PARAMETERS DESIRED AND NO. OF CONTAINERS	VOLATILES	PRESERVATION
S+ME												
SAMPLERS		CONTACT PERSON				BATCH # (Lab Use Only)		COMMENT / SAMPLE PRE FIX				
Quantex		Lyndah Butler										
SAMPLE FIELD ID \ NUMBER	DATE SAMPLED	TIME SAMPLED	COMP.	GRAB	DATE REC'D	TIME REC'D	STATION LOCATION / No.					
110-1-2	1/28/13				1/29/13	12:00		5	1		10.29	
↓ 4	↓										10.0	
↓ 6											10.0	
↓ 8											10.5	
↓ 10											10.1	
110-2-2												10.2
↓ 4												10.2
↓ 6												10.2
↓ 8												10.6
↓ 10												10.6
110-3-2												10.4
↓ 4											} Not analyzed	
↓ 6												
↓ 8												
↓ 10											10.0	
Prelabeled Containers Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations				
			CLH					baggies				
Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time					
							1/29/13					

Matrix Types S Soil SW Surface Water GW Ground Water SG Soil Gas



25132 SW 1st Avenue
Newberry, FL 32669
TEL (352) 472-5830
FAX (352) 472-5832

200 Quade Drive
Cary, NC 27513
TEL (919) 678-0030


CHAIN-OF-CUSTODY RECORD

MOBILE UNIT #

CLIENT NAME		PROJECT NAME & ADDRESS						SAMPLE MATRIX	NUMBER OF CONTAINERS	IDENTIFY PARAMETERS DESIRED AND NO. OF CONTAINERS	PRESERVATION	
S+ME												
SAMPLERS		CONTACT PERSON				BATCH # (Lab Use Only)		VOLATILES				
Quantex		Lyndal Butler										
SAMPLE FIELD ID. \ NUMBER	DATE SAMPLED	TIME SAMPLED	COMP.	GRAB	DATE REC'D	TIME REC'D	STATION LOCATION / No.				COMMENT / SAMPLE PRE FIX	
110-4-2	1/28/13				1/29/13	12:00		S	1			} not analyzed as per client 10.0g
↓ 4	↓				↓	↓						
↓ 6	↓				↓	↓						
↓ 8	↓				↓	↓						
110-5-2											} not analyzed as per client 10.3g	
↓ 4	↓				↓	↓						
↓ 6	↓				↓	↓						
↓ 8	↓				↓	↓						
155-1-6	1/28/13										} 10.6g 10.6g	
3-8												
Prelined Containers Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations				
Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time					
			Q. Hel				1/29/13	baggies				

Matrix Types S Soil SW Surface Water GW Ground Water SG Soil Gas

2



25132 SW 1st Avenue
Newberry, FL 32669
TEL (352) 472-5830
FAX (352) 472-5832


200 Quade Drive
Cary, NC 27513
TEL (919) 678-0030

CHAIN-OF-CUSTODY RECORD

MOBILE UNIT #

CLIENT NAME		PROJECT NAME & ADDRESS						SAMPLE MATRIX	NUMBER OF CONTAINERS	IDENTIFY PARAMETERS DESIRED AND NO. OF CONTAINERS	VOLATILES	PRESERVATION
S+ME		NCDOT U2B25B Greensboro NC										
SAMPLERS		CONTACT PERSON				BATCH # (Lab Use Only)		COMMENT / SAMPLE PRE FIX				
Quantex		Lyndal Butler										
SAMPLE FIELD ID# NUMBER	DATE SAMPLED	TIME SAMPLED	COMP.	GRAB	DATE REC'D	TIME REC'D	STATION LOCATION / No.					
116-9-10	1/29/13				1/30/13			S	1		10.1	
116-10-8	↓										10.1	
116-11-4											10.1	
116-12-4											10.1	
116-13-4											10.3	
137-1-10	1/30/13										10.1	
66-2-15 ^{cont}					1/30/13	15:50					10.1	
66-2-18 ²⁰						↓					10.0	
137-2-10											10.0	
137-3-10											10.3	
137-4-10											10.2	
137-5-6											10.2	
Prelabeled Containers Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations				
Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time					

Matrix Types S Soil SW Surface Water GW Ground Water SG Soil Gas



25132 SW 1st Avenue
Newberry, FL 32669
TEL (352) 472-5830
FAX (352) 472-5832


200 Quade Drive
Cary, NC 27513
TEL (919) 678-0030

CHAIN-OF-CUSTODY RECORD

MOBILE UNIT #

CLIENT NAME		PROJECT NAME & ADDRESS						SAMPLE MATRIX	NUMBER OF CONTAINERS	IDENTIFY PARAMETERS DESIRED AND NO. OF CONTAINERS	PRESERVATION	
S+ME		NC DOT U2525B Greensboro										
SAMPLERS		CONTACT PERSON				BATCH # (Lab Use Only)		VOLATILES				
Quantex		Lyndal Butler										
SAMPLE FIELD ID \ NUMBER	DATE SAMPLED	TIME SAMPLED	COMP.	GRAB	DATE REC'D	TIME REC'D	STATION LOCATION / No.				COMMENT / SAMPLE PRE FIX	
116-18-14					1/29/13			5	1		10.0	
155-4-12											10.1	
155-5-10											10.0	
155-4-10											10.0	
155-6-4											10.1	
155-7-6											10.0	
155-8-4											10.4	
116-2-2					1/30/13						10.2	
116-1-6											10.0	
116-3-2											10.1	
116-4-2											10.0	
116-5-2											10.5	
116-6-2											10.2	
116-7-2					1/30/13						10.0	
116-8-9											10.1	
Prelined Containers Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations				
Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time					

Matrix Types S Soil SW Surface Water GW Ground Water SG Soil Gas



25132 SW 1st Avenue
 Newberry, FL 32669
 TEL (352) 472-5830
 FAX (352) 472-5832


200 Quade Drive
 Cary, NC 27513
 TEL (919) 678-0030

CHAIN-OF-CUSTODY RECORD

MOBILE UNIT #

CLIENT NAME		PROJECT NAME & ADDRESS						SAMPLE MATRIX	NUMBER OF CONTAINERS	IDENTIFY PARAMETERS DESIRED AND NO. OF CONTAINERS	VOLATILES	PRESERVATION C Chilled H HCL Ot Other (see Remarks)
SAMPLERS		CONTACT PERSON				BATCH # (Lab Use Only)						
SAMPLE FIELD ID \ NUMBER	DATE SAMPLED	TIME SAMPLED	COMP.	GRAB	DATE REC'D	TIME REC'D	STATION LOCATION / No.				COMMENT / SAMPLE PRE FIX	
Sd M 9												
Quantex												
116-14-10	1/29/13				1/29/13	14:00		S	1		10.0	
116-16-10	↓				↓			↓			10.6	
116-17-10											10.2	
116-18-14											10.0	
116-16-8											10.1	
↓ ↓ 12											10.2	
↓ ↓ 14											10.4	
Prcleaned Containers Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations				
Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	3				

Matrix Types S Soil SW Surface Water GW Ground Water SG Soil Gas




25132 SW 1st Avenue
 Newberry, FL 32669
 TEL (352) 472-5830
 FAX (352) 472-5832


200 Quade Drive
 Cary, NC 27513
 TEL (919) 678-0030

CHAIN-OF-CUSTODY RECORD

MOBILE UNIT #

CLIENT NAME		PROJECT NAME & ADDRESS						SAMPLE MATRIX	NUMBER OF CONTAINERS	IDENTIFY PARAMETERS DESIRED AND NO OF CONTAINERS	VOLATILES	PRESERVATION
S + ME		NCDOT U2525B US-29 Greensboro										
SAMPLERS		CONTACT PERSON				BATCH # (Lab Use Only)		COMMENT / SAMPLE PRE FIX				
Quantex		Lyndal Butler										
SAMPLE FIELD ID \ NUMBER	DATE SAMPLED	TIME SAMPLED	COMP.	GRAB	DATE REC'D	TIME REC'D	STATION LOCATION / No.					
137-6-10	1/30/13				1/30/13			S	1		10.0g	
↓ 7-2	↓				↓						10.2	
↓ 8-15	↓				↓						10.1	
↓ 9-15	↓				↓						10.3	
↓ 10-15	↓				↓						10.3	
↓ 11-15	↓				↓						10.0	
66-6-10	1/31/13				1/31/13						10.1	
66-6-20	↓				↓						10.0	
137-12-15	1/30/13				1/30/13						10.1	
↓ 13-2	↓				↓						10.0	
66-5-14	1/31/13				1/31/13						10.1	
66-7-19	↓				↓						10.0	
137-14-2	1/30/13				1/30/13						10.1	
137-15-2	1/30/13				1/30/13						10.4	
66-1-15	1/31/13				1/31/13						10.0	
Prelined Containers Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations				
							1/31/13	samples in baggies p. 1				

Matrix Types S Soil SW Surface Water GW Ground Water SG Soil Gas



25132 SW 1st Avenue
Newberry, FL 32669
TEL (352) 472-5830
FAX (352) 472-5832


200 Quade Drive
Cary, NC 27513
TEL (919) 678-0030

CHAIN-OF-CUSTODY RECORD

MOBILE UNIT #

CLIENT NAME		PROJECT NAME & ADDRESS						SAMPLE MATRIX	NUMBER OF CONTAINERS	IDENTIFY PARAMETERS DESIRED AND NO. OF CONTAINERS	PRESERVATION
S+ME		NCDOT U2825B US-29 Greensboro									
SAMPLERS		CONTACT PERSON				BATCH # (Lab Use Only)		VOLATILES			COMMENT / SAMPLE PRE FIX
Quantex		Lyndal Butle									
SAMPLE FIELD ID \ NUMBER	DATE SAMPLED	TIME SAMPLED	COMP.	GRAB	DATE REC'D	TIME REC'D	STATION LOCATION / No.				
66-3-15	1/31/13				1/31/13			S	1		10.1
66-4-15	↓				↓						10.1
66-7-17	↓				↓						10.0
66-8-15	↓				↓						10.4
66-9-15	↓				↓						10.1
66-10-9	↓				↓						10.0
66-11-15	↓				↓						10.1
Pretreated Containers Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations			
Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations			

Matrix Types S Soil SW Surface Water GW Ground Water SG Soil Gas



25132 SW 1st Avenue
Newberry, FL 32669
TEL (352) 472-5830
FAX (352) 472-5832

200 Quade Drive
Cary, NC 27513
TEL (919) 678-0030

CHAIN-OF-CUSTODY RECORD

MOBILE UNIT #

CLIENT NAME		PROJECT NAME & ADDRESS						SAMPLE MATRIX	NUMBER OF CONTAINERS	IDENTIFY PARAMETERS DESIRED AND NO. OF CONTAINERS	VOLATILES	PRESERVATION
S+ME		NC DOT U2525B US-29 Greensboro										
SAMPLERS		CONTACT PERSON				BATCH # (Lab Use Only)		COMMENT / SAMPLE PRE FIX				
Quantex		Lyndal Butler										
SAMPLE FIELD ID \ NUMBER	DATE SAMPLED	TIME SAMPLED	COMP.	GRAB	DATE REC'D	TIME REC'D	STATION LOCATION / No.					
66-13-15	2/1/13				2/1/13			S	1		10.0g	
14-8	↓				↓						10.2g	
14-15	↓				↓						10.5	
17-15	↓				↓						10.5	
19-9 *	↓				↓						10.2	
19-11 19-11 *	↓				↓						10.2	
19-13 *	↓				↓						10.2	
19-15 *	↓				↓						10.2	
20-11	↓				↓						10.3	
21-15	↓				↓						10.4	
22-7	↓				↓						10.5	
23-5 *	↓				↓						10.3	
23-15 *	↓				↓						10.3	
24-13	↓				↓						10.3	
25-12.5	↓				↓						10.0 PID: 300	
Pretreated Containers Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	Remarks and Observations				
Relinquished by: (Signature)		Date / Time	Received by: (Signature)				Date / Time	p1				

Matrix Types S Soil SW Surface Water GW Ground Water SG Soil Gas



Pace Analytical Services, Inc.
205 East Meadow Road - Suite A
Eden, NC 27288
(336)623-8921

Pace Analytical Services, Inc.
2225 Riverside Dr.
Asheville, NC 28804
(828)254-7176

Pace Analytical Services, Inc.
9800 Kinsey Ave. Suite 100
Huntersville, NC 28078
(704)875-9092

February 11, 2013

Chemical Testing Engineer
NCDOT
Materials & Tests Unit
1801 Blue Ridge Road
Raleigh, NC 27607

RE: Project: NCDOT U-2525B 34821.1.1
Pace Project No.: 92147015

Dear Chemical Engineer:

Enclosed are the analytical results for sample(s) received by the laboratory on February 06, 2013. The results relate only to the samples included in this report. Results reported herein conform to the most current TNI standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

Analyses were performed at the Pace Analytical Services location indicated on the sample analyte page for analysis unless otherwise footnoted.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Jon D Bradley for
Kevin Herring
kevin.herring@pacelabs.com
Project Manager

Enclosures



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..



Pace Analytical Services, Inc.
205 East Meadow Road - Suite A
Eden, NC 27288
(336)623-8921

Pace Analytical Services, Inc.
2225 Riverside Dr.
Asheville, NC 28804
(828)254-7176

Pace Analytical Services, Inc.
9800 Kinsey Ave. Suite 100
Huntersville, NC 28078
(704)875-9092

CERTIFICATIONS

Project: NCDOT U-2525B 34821.1.1
Pace Project No.: 92147015

Charlotte Certification IDs

9800 Kinsey Ave. Ste 100, Huntersville, NC 28078
North Carolina Drinking Water Certification #: 37706
North Carolina Field Services Certification #: 5342
North Carolina Wastewater Certification #: 12
South Carolina Certification #: 99006001

Florida/NELAP Certification #: E87627
Kentucky UST Certification #: 84
West Virginia Certification #: 357
Virginia/VELAP Certification #: 460221

REPORT OF LABORATORY ANALYSIS

SAMPLE ANALYTE COUNT

Project: NCDOT U-2525B 34821.1.1

Pace Project No.: 92147015

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92147015001	137-7-2	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C
92147015002	137-8-15	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C
92147015003	137-10-15	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C
92147015004	66-14-8	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C
92147015005	66-19-9	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C
92147015006	66-20-13	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C
92147015007	66-25-12.5	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C
92147015008	66-26-11	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C
92147015009	110-3-10	EPA 8015 Modified	MEJ	2	PASI-C
		EPA 8015 Modified	RGF	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C

REPORT OF LABORATORY ANALYSIS

HITS ONLY

Project: NCDOT U-2525B 34821.1.1
Pace Project No.: 92147015

Lab Sample ID Method	Client Sample ID Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92147015001	137-7-2					
EPA 8015 Modified	Diesel Components	22.9 mg/kg		6.6	02/07/13 18:02	
EPA 8015 Modified	Gasoline Range Organics	12.9 mg/kg		6.5	02/08/13 11:53	
ASTM D2974-87	Percent Moisture	24.8 %		0.10	02/06/13 15:28	
92147015002	137-8-15					
ASTM D2974-87	Percent Moisture	17.5 %		0.10	02/06/13 15:28	
92147015003	137-10-15					
ASTM D2974-87	Percent Moisture	16.6 %		0.10	02/06/13 15:28	
92147015004	66-14-8					
EPA 8015 Modified	Diesel Components	252 mg/kg		6.1	02/07/13 18:26	
EPA 8015 Modified	Gasoline Range Organics	7.9 mg/kg		5.8	02/08/13 13:48	
ASTM D2974-87	Percent Moisture	18.4 %		0.10	02/06/13 15:29	
92147015005	66-19-9					
EPA 8015 Modified	Diesel Components	5460 mg/kg		170	02/08/13 17:07	
ASTM D2974-87	Percent Moisture	26.5 %		0.10	02/06/13 15:29	
92147015006	66-20-13					
ASTM D2974-87	Percent Moisture	26.2 %		0.10	02/06/13 15:29	
92147015007	66-25-12.5					
EPA 8015 Modified	Diesel Components	4580 mg/kg		177	02/08/13 17:07	
EPA 8015 Modified	Gasoline Range Organics	40.1 mg/kg		7.1	02/08/13 14:57	
ASTM D2974-87	Percent Moisture	29.3 %		0.10	02/06/13 15:29	
92147015008	66-26-11					
ASTM D2974-87	Percent Moisture	15.0 %		0.10	02/06/13 15:29	
92147015009	110-3-10					
ASTM D2974-87	Percent Moisture	28.2 %		0.10	02/06/13 15:29	

See Page 15 for Results for Parcel 110 Sample.

REPORT OF LABORATORY ANALYSIS

PROJECT NARRATIVE

Project: NCDOT U-2525B 34821.1.1

Pace Project No.: 92147015

Method: EPA 8015 Modified
Description: 8015 GCS THC-Diesel
Client: NCDOT East Central
Date: February 11, 2013

General Information:

9 samples were analyzed for EPA 8015 Modified. All samples were received in acceptable condition with any exceptions noted below.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:

The samples were prepared in accordance with EPA 3546 with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

QC Batch: OEXT/20683

S4: Surrogate recovery not evaluated against control limits due to sample dilution.

- 66-19-9 (Lab ID: 92147015005)
 - n-Pentacosane (S)
- 66-25-12.5 (Lab ID: 92147015007)
 - n-Pentacosane (S)

Method Blank:

All analytes were below the report limit in the method blank with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

REPORT OF LABORATORY ANALYSIS

PROJECT NARRATIVE

Project: NCDOT U-2525B 34821.1.1
Pace Project No.: 92147015

Method: EPA 8015 Modified
Description: Gasoline Range Organics
Client: NCDOT East Central
Date: February 11, 2013

General Information:

9 samples were analyzed for EPA 8015 Modified. All samples were received in acceptable condition with any exceptions noted below.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:

The samples were prepared in accordance with EPA 5035A/5030B with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Internal Standards:

All internal standards were within QC limits with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

This data package has been reviewed for quality and completeness and is approved for release.

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1

Pace Project No.: 92147015

Sample: 137-7-2 **Lab ID: 92147015001** Collected: 01/30/13 09:10 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	22.9	mg/kg	6.6	1	02/06/13 13:35	02/07/13 18:02	68334-30-5	
Surrogates								
n-Pentacosane (S)	66	%	41-119	1	02/06/13 13:35	02/07/13 18:02	629-99-2	
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	12.9	mg/kg	6.5	1	02/08/13 08:46	02/08/13 11:53	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	116	%	70-167	1	02/08/13 08:46	02/08/13 11:53	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	24.8	%	0.10	1		02/06/13 15:28		



Pace Analytical Services, Inc.
 205 East Meadow Road - Suite A
 Eden, NC 27288
 (336)623-8921

Pace Analytical Services, Inc.
 2225 Riverside Dr.
 Asheville, NC 28804
 (828)254-7176

Pace Analytical Services, Inc.
 9800 Kincey Ave. Suite 100
 Huntersville, NC 28078
 (704)875-9092

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1
 Pace Project No.: 92147015

Sample: 137-8-15 **Lab ID: 92147015002** Collected: 01/30/13 09:45 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	ND	mg/kg	6.1	1	02/06/13 13:35	02/07/13 18:02	68334-30-5	
Surrogates								
n-Pentacosane (S)	47	%	41-119	1	02/06/13 13:35	02/07/13 18:02	629-99-2	
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	ND	mg/kg	7.2	1	02/08/13 08:46	02/08/13 13:02	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	109	%	70-167	1	02/08/13 08:46	02/08/13 13:02	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	17.5	%	0.10	1		02/06/13 15:28		



Pace Analytical Services, Inc.
 205 East Meadow Road - Suite A
 Eden, NC 27288
 (336)623-8921

Pace Analytical Services, Inc.
 2225 Riverside Dr.
 Asheville, NC 28804
 (828)254-7176

Pace Analytical Services, Inc.
 9800 Kinsey Ave. Suite 100
 Huntersville, NC 28078
 (704)875-9092

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1
 Pace Project No.: 92147015

Sample: 137-10-15 **Lab ID: 92147015003** Collected: 01/30/13 10:35 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	ND	mg/kg	6.0	1	02/06/13 13:35	02/07/13 18:26	68334-30-5	
Surrogates								
n-Pentacosane (S)	60	%	41-119	1	02/06/13 13:35	02/07/13 18:26	629-99-2	
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	ND	mg/kg	5.8	1	02/08/13 08:46	02/08/13 13:25	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	100	%	70-167	1	02/08/13 08:46	02/08/13 13:25	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	16.6	%	0.10	1		02/06/13 15:28		



Pace Analytical Services, Inc.
 205 East Meadow Road - Suite A
 Eden, NC 27288
 (336)623-8921

Pace Analytical Services, Inc.
 2225 Riverside Dr.
 Asheville, NC 28804
 (828)254-7176

Pace Analytical Services, Inc.
 9800 Kinsey Ave. Suite 100
 Huntersville, NC 28078
 (704)875-9092

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1
 Pace Project No.: 92147015

Sample: 66-14-8 **Lab ID: 92147015004** Collected: 02/01/13 09:32 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	252	mg/kg	6.1	1	02/06/13 13:35	02/07/13 18:26	68334-30-5	
Surrogates								
n-Pentacosane (S)	86	%	41-119	1	02/06/13 13:35	02/07/13 18:26	629-99-2	
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	7.9	mg/kg	5.8	1	02/08/13 08:46	02/08/13 13:48	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	132	%	70-167	1	02/08/13 08:46	02/08/13 13:48	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	18.4	%	0.10	1		02/06/13 15:29		



Pace Analytical Services, Inc.
 205 East Meadow Road - Suite A
 Eden, NC 27288
 (336)623-8921

Pace Analytical Services, Inc.
 2225 Riverside Dr.
 Asheville, NC 28804
 (828)254-7176

Pace Analytical Services, Inc.
 9800 Kinsey Ave. Suite 100
 Huntersville, NC 28078
 (704)875-9092

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1
 Pace Project No.: 92147015

Sample: 66-19-9 Lab ID: 92147015005 Collected: 02/01/13 11:55 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	5460	mg/kg	170	25	02/06/13 13:35	02/08/13 17:07	68334-30-5	
Surrogates								
n-Pentacosane (S)	0	%	41-119	25	02/06/13 13:35	02/08/13 17:07	629-99-2	S4
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	ND	mg/kg	6.7	1	02/08/13 08:46	02/08/13 14:11	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	104	%	70-167	1	02/08/13 08:46	02/08/13 14:11	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	26.5	%	0.10	1		02/06/13 15:29		

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1

Pace Project No.: 92147015

Sample: 66-20-13 **Lab ID: 92147015006** Collected: 02/01/13 12:34 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	ND	mg/kg	6.8	1	02/06/13 13:35	02/07/13 18:49	68334-30-5	
Surrogates								
n-Pentacosane (S)	62	%	41-119	1	02/06/13 13:35	02/07/13 18:49	629-99-2	
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	ND	mg/kg	8.3	1	02/08/13 08:46	02/08/13 14:34	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	100	%	70-167	1	02/08/13 08:46	02/08/13 14:34	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	26.2	%	0.10	1		02/06/13 15:29		



Pace Analytical Services, Inc.
 205 East Meadow Road - Suite A
 Eden, NC 27288
 (336)623-8921

Pace Analytical Services, Inc.
 2225 Riverside Dr.
 Asheville, NC 28804
 (828)254-7176

Pace Analytical Services, Inc.
 9800 Kinsey Ave. Suite 100
 Huntersville, NC 28078
 (704)875-9092

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1
 Pace Project No.: 92147015

Sample: 66-25-12.5 **Lab ID: 92147015007** Collected: 02/01/13 14:42 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	4580	mg/kg	177	25	02/06/13 13:35	02/08/13 17:07	68334-30-5	
Surrogates								
n-Pentacosane (S)	0 %		41-119	25	02/06/13 13:35	02/08/13 17:07	629-99-2	S4
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	40.1	mg/kg	7.1	1	02/08/13 08:46	02/08/13 14:57	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	146 %		70-167	1	02/08/13 08:46	02/08/13 14:57	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	29.3	%	0.10	1		02/06/13 15:29		

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1

Pace Project No.: 92147015

Sample: 66-26-11 **Lab ID: 92147015008** Collected: 02/01/13 15:13 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	ND	mg/kg	5.9	1	02/06/13 13:35	02/07/13 19:12	68334-30-5	
Surrogates								
n-Pentacosane (S)	80	%	41-119	1	02/06/13 13:35	02/07/13 19:12	629-99-2	
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	ND	mg/kg	5.3	1	02/08/13 08:46	02/08/13 15:20	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	100	%	70-167	1	02/08/13 08:46	02/08/13 15:20	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	15.0	%	0.10	1		02/06/13 15:29		



Pace Analytical Services, Inc.
 205 East Meadow Road - Suite A
 Eden, NC 27288
 (336)623-8921

Pace Analytical Services, Inc.
 2225 Riverside Dr.
 Asheville, NC 28804
 (828)254-7176

Pace Analytical Services, Inc.
 9800 Kinsey Ave. Suite 100
 Huntersville, NC 28078
 (704)875-9092

ANALYTICAL RESULTS

Project: NCDOT U-2525B 34821.1.1
 Pace Project No.: 92147015

Sample: 110-3-10 Lab ID: 92147015009 Collected: 02/01/13 16:48 Received: 02/06/13 09:45 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel								
Analytical Method: EPA 8015 Modified			Preparation Method: EPA 3546					
Diesel Components	ND	mg/kg	7.0	1	02/06/13 13:35	02/07/13 19:36	68334-30-5	
Surrogates								
n-Pentacosane (S)	69	%	41-119	1	02/06/13 13:35	02/07/13 19:36	629-99-2	
Gasoline Range Organics								
Analytical Method: EPA 8015 Modified			Preparation Method: EPA 5035A/5030B					
Gasoline Range Organics	ND	mg/kg	6.7	1	02/08/13 08:46	02/08/13 15:44	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	94	%	70-167	1	02/08/13 08:46	02/08/13 15:44	460-00-4	
Percent Moisture								
Analytical Method: ASTM D2974-87								
Percent Moisture	28.2	%	0.10	1		02/06/13 15:29		

QUALITY CONTROL DATA

Project: NCDOT U-2525B 34821.1.1
Pace Project No.: 92147015

QC Batch: GCV/6623 Analysis Method: EPA 8015 Modified
QC Batch Method: EPA 5035A/5030B Analysis Description: Gasoline Range Organics
Associated Lab Samples: 92147015001, 92147015002, 92147015003, 92147015004, 92147015005, 92147015006, 92147015007, 92147015008, 92147015009

METHOD BLANK: 918709 Matrix: Solid
Associated Lab Samples: 92147015001, 92147015002, 92147015003, 92147015004, 92147015005, 92147015006, 92147015007, 92147015008, 92147015009

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Gasoline Range Organics	mg/kg	ND	5.9	02/08/13 11:30	
4-Bromofluorobenzene (S)	%	102	70-167	02/08/13 11:30	

LABORATORY CONTROL SAMPLE: 918710

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Gasoline Range Organics	mg/kg	24.5	23.2	95	70-165	
4-Bromofluorobenzene (S)	%			97	70-167	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 918711 918712

Parameter	Units	92147015001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Qual
Gasoline Range Organics	mg/kg	12.9	27	27	46.0	45.8	122	121	47-187	1	
4-Bromofluorobenzene (S)	%						107	107	70-167		

QUALITY CONTROL DATA

Project: NCDOT U-2525B 34821.1.1
Pace Project No.: 92147015

QC Batch: OEXT/20683 Analysis Method: EPA 8015 Modified
QC Batch Method: EPA 3546 Analysis Description: 8015 Solid GCSV
Associated Lab Samples: 92147015001, 92147015002, 92147015003, 92147015004, 92147015005, 92147015006, 92147015007, 92147015008, 92147015009

METHOD BLANK: 916820 Matrix: Solid
Associated Lab Samples: 92147015001, 92147015002, 92147015003, 92147015004, 92147015005, 92147015006, 92147015007, 92147015008, 92147015009

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Diesel Components	mg/kg	ND	5.0	02/07/13 12:41	
n-Pentacosane (S)	%	70	41-119	02/07/13 12:41	

LABORATORY CONTROL SAMPLE: 916821

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Diesel Components	mg/kg	66.7	41.2	62	49-113	
n-Pentacosane (S)	%			66	41-119	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 916822 916823

Parameter	Units	92146950001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Qual
Diesel Components	mg/kg	ND	74.8	74.8	40.7	42.4	54	56	10-146	4	
n-Pentacosane (S)	%						52	60	41-119		



Pace Analytical Services, Inc.
205 East Meadow Road - Suite A
Eden, NC 27288
(336)623-8921

Pace Analytical Services, Inc.
2225 Riverside Dr.
Asheville, NC 28804
(828)254-7176

Pace Analytical Services, Inc.
9800 Kinsey Ave. Suite 100
Huntersville, NC 28078
(704)875-9092

QUALIFIERS

Project: NCDOT U-2525B 34821.1.1
Pace Project No.: 92147015

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to changes in sample preparation, dilution of the sample aliquot, or moisture content.

ND - Not Detected at or above adjusted reporting limit.

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PRL - Pace Reporting Limit.

RL - Reporting Limit.

S - Surrogate

1,2-Diphenylhydrazine (8270 listed analyte) decomposes to Azobenzene.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Acid preservation may not be appropriate for 2-Chloroethylvinyl ether, Styrene, and Vinyl chloride.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

LABORATORIES

PASI-C Pace Analytical Services - Charlotte

ANALYTE QUALIFIERS

S4 Surrogate recovery not evaluated against control limits due to sample dilution.



Pace Analytical Services, Inc.
 205 East Meadow Road - Suite A
 Eden, NC 27288
 (336)623-8921

Pace Analytical Services, Inc.
 2225 Riverside Dr.
 Asheville, NC 28804
 (828)254-7176

Pace Analytical Services, Inc.
 9800 Kinsey Ave. Suite 100
 Huntersville, NC 28078
 (704)875-9092

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: NCDOT U-2525B 34821.1.1
 Pace Project No.: 92147015

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92147015001	137-7-2	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015002	137-8-15	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015003	137-10-15	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015004	66-14-8	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015005	66-19-9	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015006	66-20-13	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015007	66-25-12.5	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015008	66-26-11	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015009	110-3-10	EPA 3546	OEXT/20683	EPA 8015 Modified	GCSV/13898
92147015001	137-7-2	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015002	137-8-15	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015003	137-10-15	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015004	66-14-8	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015005	66-19-9	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015006	66-20-13	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015007	66-25-12.5	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015008	66-26-11	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015009	110-3-10	EPA 5035A/5030B	GCV/6623	EPA 8015 Modified	GCV/6625
92147015001	137-7-2	ASTM D2974-87	PMST/5292		
92147015002	137-8-15	ASTM D2974-87	PMST/5292		
92147015003	137-10-15	ASTM D2974-87	PMST/5292		
92147015004	66-14-8	ASTM D2974-87	PMST/5292		
92147015005	66-19-9	ASTM D2974-87	PMST/5292		
92147015006	66-20-13	ASTM D2974-87	PMST/5292		
92147015007	66-25-12.5	ASTM D2974-87	PMST/5292		
92147015008	66-26-11	ASTM D2974-87	PMST/5292		
92147015009	110-3-10	ASTM D2974-87	PMST/5292		