PROJ. REFERENCE NO.	SHEET NO.
R-3620	X-1B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L (LT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
12+00.00	0	0	0
12+50.00	5	45	29
13+00.00	1	70	38
13+50.00	1	75	38
14+00.00	1	81	37
14+50.00	0	80	31

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
12+00.00	0	0	0
12+50.00	2	50	28
13+00.00	2	87	39
13+50.00	1	96	38
14+00.00	0	106	37
14+50.00	0	105	33

Station L (LT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
14+50.00	0	0	0
15+00.00	0	69	26
15+50.00	0	79	25
16+00.00	0	95	25
16+50.00	0	112	21
17+00.00	0	137	12
17+50.00	0	174	4
18+00.00	0	200	0

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
14+50.00	0	0	0
15+00.00	0	100	28
15+50.00	0	102	21
16+00.00	0	111	15
16+50.00	0	118	8
17+00.00	0	121	2
17+50.00	0	117	1
18+00.00	0	126	0

Station L (FULL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+00.00	0	0
18+50.00	0	380
19+00.00	0	471
19+50.00	0	622
20+00.00	0	831
20+50.00	0	968
21+00.00	0	889
21+50.00	0	777
22+00.00	0	697

Station L (LT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
22+00.00	0	0	0
22+50.00	0	247	0
23+00.00	0	249	0
23+50.00	0	254	0
24+00.00	0	276	0
24+50.00	0	296	0
25+00.00	0	302	0
25+50.00	0	318	0
26+00.00	0	340	0
26+50.00	0	354	0
27+00.00	0	356	0
27+50.00	0	359	0
28+00.00	0	374	0
28+50.00	0	388	0
29+00.00	0	384	0
29+50.00	0	379	0
30+00.00	0	388	0
30+50.00	0	398	0
31+00.00	0	406	0
31+50.00	0	396	0
32+00.00	0	386	0
32+50.00	0	380	0
33+00.00	0	361	0
33+50.00	0	361	0
34+00.00	0	364	0
34+50.00	0	348	0
35+00.00	0	342	0
35+50.00	0	358	0

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
22+00.00	0	0	0
22+50.00	0	317	0
23+00.00	0	336	0
23+50.00	0	367	0
24+00.00	0	405	0
24+50.00	0	445	0
25+00.00	0	451	0
25+50.00	0	428	0
26+00.00	0	411	0
26+50.00	0	394	0
27+00.00	0	371	0
27+50.00	0	366	0
28+00.00	0	370	0
28+50.00	0	372	0
29+00.00	0	371	0
29+50.00	0	377	0
30+00.00	0	378	0
30+50.00	0	377	0
31+00.00	0	565	0
31+50.00	0	543	0
32+00.00	0	338	0

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
32+50.00	0	332	0
33+00.00	0	305	0
33+50.00	0	286	0
34+00.00	0	278	0
34+50.00	0	267	0
35+00.00	0	259	0
35+50.00	0	248	0

Station L (FULL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
35+50.00	0	0	0
36+00.00	0	569	0
36+50.00	0	541	0
37+00.00	0	554	0
37+50.00	0	550	0
38+00.00	0	522	0
38+50.00	0	485	0
39+00.00	0	463	0
39+50.00	0	410	0
40+00.00	0	367	0
40+50.00	0	360	0
41+00.00	0	339	0
41+50.00	0	323	0
42+00.00	0	332	0
42+50.00	0	345	0
43+00.00	0	328	0
43+50.00	0	340	0
44+00.00	0	352	0
44+50.00	0	328	0
45+00.00	3	310	21
45+50.00	3	339	21
46+00.00	0	388	0
46+50.00	0	404	0
47+00.00	0	473	0
47+50.00	0	588	0
48+00.00	0	630	0
48+50.00	0	630	0
49+00.00	0	627	0
49+50.00	0	597	0
50+00.00	0	577	0
50+50.00	0	562	0
51+00.00	0	551	0
51+50.00	0	554	0
52+00.00	0	540	0
52+50.00	0	514	0
53+00.00	0	525	0
53+50.00	0	552	0
54+00.00	0	558	0
54+50.00	0	550	0
55+00.00	0	541	0
55+50.00	0	534	0
56+00.00	0	544	0

Station L (FULL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
56+50.00	0	524	0
57+00.00	0	495	0
57+50.00	0	560	0
58+00.00	0	649	0
58+50.00	0	704	0
59+00.00	0	767	0
59+50.00	0	813	0
60+00.00	0	838	0
60+50.00	0	833	0
61+00.00	0	801	0
61+50.00	0	751	0
62+00.00	0	678	0
62+50.00	0	628	0
63+00.00	0	565	0
63+50.00	0	480	0
64+00.00	0	434	0
64+50.00	0	416	0
65+00.00	0	384	0
65+50.00	0	348	0

Station L (FULL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
65+50.00	0	0	0
66+00.00	0	314	0
66+50.00	0	320	0
67+00.00	0	299	0
67+50.00	0	257	0
68+00.00	0	275	0
68+50.00	0	305	0
69+00.00	0	315	0
69+50.00	0	309	0
70+00.00	0	410	0
70+50.00	0	561	0
71+00.00	0	521	0
71+50.00	0	442	0
72+00.00	0	453	0
72+50.00	0	455	0
73+00.00	0	490	0
73+50.00	0	544	0
74+00.00	0	579	0
74+50.00	0	621	0
75+00.00	0	631	0
75+50.00	0	612	0
76+00.00	0	603	0
76+50.00	0	585	0
77+00.00	0	567	0
77+50.00	0	588	0
78+00.00	0	642	0
78+50.00	0	616	0
79+00.00	0	552	0
79+50.00	0	516	0
80+00.00	0	491	0