PROJECT REFERENCE NO.	SHEET NO.
U-2579B	1A-1

ROADWAY DESIGN ENGINEER
8/15/2014

NORTH CAROLINA PROFESSIONAL SEAL 18494 ENGINEER ANTHONY AARON HOUSER

DocuSigned by: Anthony Houser
3F7D4DCEBE364ED...

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1A-1 THRU 1A-2	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS
1B	CONVENTIONAL SYMBOLS
1C-1 THRU 1C-4	SURVEY CONTROL SHEETS
1D-1 THRU 1D-2	CENTERLINE COORDINATE DATA SHEETS
2A-1 THRU 2A-15	PAVEMENT SCHEDULE, TYPICAL SECTIONS, WEDGING AND RETAINING WALL DETAILS
2A-16	SHOULDER DRAIN DETAILS
2A-17	DETAIL OF NOISE WALL WITH SHOULDER DRAIN
2A-18 THRU 2A-23	STRUCTURE TYPICAL SECTIONS
2B-1 THRU 2B-4	BRIDGE SKETCHES
2B-5 THRU 2B-7	DETOUR DETAILS
2B-8 THRU 2B-9	SHEAR POINT DIAGRAMS
2B-10 TO 2B-19	GORE DETAILS
2B-20 THRU 2B-34	NOISE WALL LOCATION DETAILS
2C-1 THRU 2C-2	METHOD OF SHOULDER CONSTRUCTION DETAILS
2C-3	STRUCTURE ANCHOR UNIT DETAIL
2D-1	PREFORMED SCOUR HOLE, ENERGY DISSIPATOR, ROCK CROSS VANE, AND MULT-BARREL LOW FLOW CHANNEL DETAILS
2D-2	FALSE SUMP DETAILS
2D-3	DETAIL FOR CONVERSION OF CB OR DI TO JB
2D-4	DETAIL FOR CONVERSTION OF OTCB TO 2-GI
2D-5	ENDWALL DETAIL
2D-6	MODIFIED CONCRETE FLUME DETAIL
2G-1	TEMPORARY SHORING DETAIL
2S-1	GUARDRAIL LOCATION DETAIL FOR OVERHEAD SIGN 'N'
3B-1 THRU 3B-4	SUMMARY OF EARTHWORK
3B-5 THRU 3B-8	GUARDRAIL SUMMARY
3B-9	SHOULDER BERM GUTTER AND WOVEN WIRE FENCE SUMMARIES
3B-10	REMOVAL OF EXISTING ASPHALT, BREAKING OF EXISTING ASPHALT, AND SHOULDER DRAIN SUMMARIES
3D-1 THRU 3D-23	DRAINAGE SUMMARY
3G-1	SUMMARY OF GEOTECHNICAL QUANTITIES
3P-1 THRU 3P-2	PARCEL INDEX SHEETS
4 THRU 31	PLAN SHEETS
32 THRU 91	PROFILE SHEETS
TMP-1 THRU TMP-45	TRANSPORTATION MANAGEMENT PLANS
PMP-1 THRU PMP-30	PAVEMENT MARKING PLANS
EC-1 THRU EC-68	EROSION CONTROL PLANS
RF-1 THRU RF-3	REFORESTATION PLANS
SIGN-1 THRU SIGN-20	SIGNING PLANS
SIG-1 THRU SIG-32	SIGNAL PLANS
SCP-1	WIRELESS COMMUNICATIONS PLANS
ITS-1 THRU ITS-62	INTELLIGENT TRANSPORTATION SYSTEMS PLANS
UC-1 THRU UC-29	UTILITY CONSTRUCTION PLANS
UO-1 THRU UO-20	UTILITIES BY OTHERS PLANS
X-0 THRU X-322	CROSS-SECTIONS (VOLUME 1 OF 2)
X-323 THRU X-675	CROSS-SECTIONS (VOLUME 2 OF 2)
S-1 THRU S- 707	BRIDGE PLANS
C-1 THRU C-30	CULVERT PLANS
W-1 THRU W-9	RETAINING WALL PLANS
W-10 THRU W-13	SOUND BARRIER WALL PLANS

GENERAL NOTES

2012 SPECIFICATIONS
EFFECTIVE: 01-17-12
REVISED: 07/30/12

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 AND 225.05 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH DETAILS 2C-1 AND 2C-2..

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

BERM DITCHES:

BERM DITCHES SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 240.01 AT LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

UNDERDRAINS:

UNDERDRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.03 AT LOCATIONS DIRECTED BY THE ENGINEER.

SHOULDER DRAINS:

SHOULDER DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 816.03 AND DETAILS IN PLANS AT LOCATIONS DIRECTED BY THE ENGINEER.

DRIVEWAYS:

DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 848.02 USING 3' RADII OR RADII AS SHOWN ON THE PLANS. LOCATIONS OF DRIVES WILL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

STREET TURNOUT:

STREET RETURNS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 848.04 USING THE RADII NOTED ON PLANS.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC NOT SHOWN ON THE PLANS WILL BE PAID FOR AT THE CONTRACT PRICE FOR "TEMPORARY SHORING".

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE:
WINSTON-SALEM / FORSYTH COUNTY UTILITIES COMMISSION - SEWER
WINSTON-SALEM / FORSYTH COUNTY UTILITIES COMMISSION - WATER
DUKE ENERGY PROGRESS - POWER DISTRIBUTION
AT&T - TELEPHONE
CENTURY LINK - TELEPHONE
TIME WARNER CABLE - CABLE TV
PIEDMONT NATURAL GAS - NATURAL GAS
ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT AS SHOWN ON THE PLANS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

8/17/99
15-AUG-2014 14:02
s:\Roadway\Proj\Project Letters & Comments\U-2579\u2579b_rdy_general_sheet_1A-1.dgn
$$USER$$ houser