DocuSign Envelope ID: 9902AAAD-E369-4BAA-98A5-8226DAF4240A

PROJECT REFERENCE NO.	SHEET NO.
U-2579B	ITS-2

INDEX OF SHEETS

ITS–1	TITLE SHEET (PROJECT OVERVIEW)
ITS–2	INDEX OF SHEETS, LEGEND, GENERAL NOTES, AND ABBREVIATIONS
ITS–3	CONSTRUCTION NOTES
ITS–4, ITS–5	SUMMARY OF QUANTITIES
ITS–6	CENTRAL BLOCK DIAGRAM
ITS–7	CABLE LAYOUT PLANS KEY SHEET
ITS–8 THRU ITS–18	TEMPORARY CABLE LAYOUT PLANS
ITS–19 THRU ITS–47	CABLE LAYOUT PLANS
ITS–48	CCTV CAMERA INSTALLATION, METAL POLE U/G ELEC. SERVICE
ITS–49	CCTV CABINET ASSEMBLY LAYOUT
ITS–50	D9–DMS 37 ELEVATION VIEW
ITS–51	D9–DMS 38 ELEVATION VIEW
ITS–52	D7–DMS 9 ELEVATION VIEW
ITS–53	DMS U/G ELECTRIC SERVICE
ITS–54	O/H ELECTRIC SERVICE
ITS–55	ELECTRICAL SERVICE DETAILS
ITS–56	NEW ELECTRICAL SERVICE AND GROUNDING DETAIL WITH TRANSFORMER
ITS–57	HUB CABINET DETAIL
ITS–58	COMMUNICATIONS CABLE SCHEMATIC
ITS–59 THRU ITS–62	FIBER–OPTIC SPLICING DETAILS

LEGEND

PROPOSED		EXISTING
FO	OVERHEAD FIBER OPTIC CABLE	EXI
DD	DIRECTIONAL DRILLED CONDUIT	N/A
B&J	NEW BORED AND JACKED CONDUIT	N/A
	TRENCHED CONDUIT	
	WOOD POLE	
	METAL POLE	
	STANDARD JUNCTION BOX	
	OVERSIZED /SPECIAL SIZED JUNCTION BOX	
E	ELECTRIC JUNCTION BOX	E
	CAMERA ASSEMBLY	
	EQUIPMENT CABINET	
S	POLE MOUNTED SPLICE CABINET	
CCTV–X	CCTV CAMERA /DMS NUMBER	
	OVERHEAD SIGN ASSEMBLY	
S	SPLICE ENCLOSURE	S
DMS	DMS SIGN	DMS

GENERAL NOTES

1. THE FIELD LOCATION OF ANY ITEM TO BE INSTALLED AS PART OF THIS PROJECT SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.

2. BURIED UTILITIES AND STRUCTURES: PIPELINES, STORM SEWERS, POWER CABLES, UTILITY CABLES, AND OTHER PUBLICLY AND PRIVATELY OWNED UNDERGROUND OBSTRUCTIONS MAY EXIST ADJACENT TO AND WITHIN THE ROADWAY RIGHT–OF–WAY WITHIN THE CONSTRUCTION LIMITS OF THIS PROJECT. INVESTIGATE THE LOCATION OF SUCH BURIED UTILITIES AND STRUCTURES WITH PUBLIC AND PRIVATE UTILITIES.

3. THE PLAN SHEETS HAVE BEEN DEVELOPED AS CLOSE TO SCALE AS PRACTICAL. ACTUAL FIELD CONDITIONS, HOWEVER, SHALL PROVIDE THE BASIS FOR APPLYING THE WORK SHOWN.

4. THE ROADWAY STANDARD DRAWINGS AND THE SPECIFIC DETAILS PROVIDED IN THIS PLAN SET SHALL ALL APPLY TO ALL WORK REQUIRED IN THIS PROJECT. WHETHER A PARTICULAR DETAIL IS SPECIFICALLY REFERENCED TO A WORK ITEM OR NOT, IN THE EVENT OF A CONFLICT, THE ORDER OF PRECEDENCE SHALL BE: THE PROJECT SPECIAL PROVISIONS, THE SPECIAL DETAILS, THE STANDARD DETAILS, THE ROADWAY STANDARD DRAWINGS, AND THEN THE STANDARD SPECIFICATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR APPLYING THE PROPER DETAILS.

5. ANY OF THE CONTRACTOR'S WORK ACTIVITIES WHICH IMPACT ANY UTILITY FACILITY SHALL BE COORDINATED WITH THE OWNER OF ALL AFFECTED UTILITIES. THE CONTRACTOR SHALL FOLLOW ANY AND ALL WORK PROCEDURES THE UTILITY OWNERS MAY REQUIRE.

6. ALL WORK SHOWN ON THESE PLANS SHALL BE PERFORMED BY THE CONTRACTOR UNLESS IT IS SPECIFICALLY NOTED THAT THE WORK WILL BE PERFORMED BY OTHERS.

ABBREVIATIONS

HDPE	HIGH DENSITY POLYETHYLENE
N.T.S.	NOT TO SCALE
DMS	DYNAMIC MESSAGE SIGN
CCTV	CLOSED CIRCUIT TELEVISION
COMP	COMPOSITE CABLE

ATKINS 5200 77 CENTER DR, SUITE 500
CHARLOTTE, NC 28217
704.665.4411 NCBEES #F-0326

Prepared in the Offices of:
Transportation Mobility and Safety Division
STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
Intelligent Transportation Systems Section
750 N. Greenfield Pkwy., Garner, NC 27529

SCALE

Index of Sheets, Legend, General Notes, and Abbreviations

DIVISION 09 FORSYTH CO KERNERSVILLE

PLAN DATE:	JUNE 2014	REVIEWED BY:	HAB
PREPARED BY:	BJS	REVIEWED BY:	JTB

REVISIONS	INIT.	DATE

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 019962 ENGINEER HENRY ALFRED BADGETT
DocuSigned by: Alf Badgett 6/9/2014
SIGNATURE DATE

CADD Filename: 2_LegendGenNotes.dgn