PROJECT REFERENCE NO.	SHEET NO.
U-2579B	UC-10

UTILITY CONSTRUCTION PLANS ONLY

NORTH CAROLINA PROFESSIONAL SEAL 037995 ENGINEERING STUDIES, PLLC. STUART C. WEBB

9BAD7538B9B4B4A... 8/12/2014

50' 25' 0 50' 100'

8/17/99

REVISIONS

MATCHLINE -Y4RPA- STA.26+95 SHEET UC-15

MATCHLINE -Y4- STA.82+26 SHEET UC-15

MATCHLINE -Y4RPBD- STA.63+00.00 SHEET UC-15

MATCHLINE -Y5- STA.18+00.00 SHEET UC-15

MATCHLINE -Y4RPB- STA.20+50 SHEET UC-9

MATCHLINE - L - STA.633+00 SHEET UC-9

MATCHLINE - L - STA.656+51 SHEET UC-11

MATCHLINE -Y4RPB- STA.32+27 SHEET UC-9

MATCHLINE -Y4RPB- STA.15+00 SHEET UC-17

MATCHLINE -Y4- STA.102+90 SHEET UC-17

MATCHLINE -Y5- STA. 38+50 SHEET UC-17

NEAREST WATER VALVE APPROX. 275 LF CITY PROJECT #7813

16" GATE VALVE

90° BEND STA. 16+36.29 WL-3

16" x 6" TEE

16" PLUG (TEMPORARY)

45° BEND (ROTATE DOWN) STA. 15+91.62 WL-3

45° BEND STA. 15+63.30 WL-3

ABANDON 370 LF 16" UTILITY PIPE

REMOVE WATER METER

REMOVE WATER METER

45° BEND STA. 12+12.18 WL-3

45° BEND STA. 11+11.73 WL-3

ABANDON

ABANDON

11 1/4° VERTICAL BEND STA. 10+73.81 WL-3

11 1/4° VERTICAL BEND STA. 10+45.73 WL-3

100 LF 30" ENCASEMENT PIPE 0.250" THICK OPEN CUT

ABANDON 270 LF 16" UTILITY PIPE

22 1/2° VERTICAL BEND STA. 8+08.97 WL-3

11 1/4° VERTICAL BEND STA. 7+72.64 WL-3

300 LF 30" ENCASEMENT PIPE 0.250" THICK OPEN CUT

REMOVE FIRE HYDRANT

ABANDON

22 1/2° VERTICAL BEND STA. 4+53.49 WL-3

11 1/4° VERTICAL BEND STA. 4+07.27 WL-3

ABANDON

1" AIR RELEASE VALVE

45° BEND STA. 3+75.65 WL-3

22 1/2° BEND STA. 3+45.37 WL-3

22 1/2° BEND STA. 2+77.20 WL-3

45° BEND STA. 2+58.51 WL-3

ABANDON 260 LF 16" UTILITY PIPE

1,637 LF 16" WATER LINE DI RESTRAINED JOINT PIPE PC350

90° BEND STA. 00+00.00 WL-3

45° BEND STA. 0+65.26 WL-3

45° BEND STA. 0+41.51 WL-3 (ROTATE DOWN)

EXIST. AIR RELEASE VALVE TO REMAIN

6" GATE VALVE TO BE LOCATED MIN. 40 LF FROM PROP. TEE

16" PLUG (TEMPORARY)

16" x 6" TEE

16" GATE VALVE TO BE LOCATED MIN. 140 LF FROM PROP. BEND

NEAREST WATER VALVE APPROX. 845 LF SEE COUNTY DWG. 14

NOTE:
FOR WL-3 PROFILE, SEE SHEET UC-27

16" & 6" D.I. WATER MAIN RELOCATION - PROJECT 74332

9332

CITY OF WINSTON-SALEM
PERMIT NUMBER
WATER 2637
DATE 6-6-14