COMPUTED BY: RLC	DATE: 7/18/14		PROJECT NO.	SHEET NO.
CHECKED BY: AEV	DATE:	9/17/2014	B-5325	3G-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF SETTLEMENT GAUGES

Gauge No.	LINE	Approx. Station	Approx. Offset
1	-L-	18+61.00	18 ft Left
2	-L-	18+61.00	18 ft Right
TOTAL GAUGES (EACH):			2

SUMMARY OF BRIDGE WAITING PERIODS

Bridge Description	End Bent/ Bent No.	MONTHS
Bridge No. 12 over Cedar Creek on SR 1116	2	1.5

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
CONTINGENCY				UD	200
				TOTAL LF:	200

*UD = Underdrain
*BD = Blind Drain
*SD = Subsurface Drain

SUMMARY OF SURCHARGES AND SURCHARGE WAITING PERIODS

LINE	Station	Station	Surcharge Height	MONTHS
-L-	18+56.79	19+56.79	2'	1.5