PROJECT REFERENCE NO.	SHEET NO.
B-5325	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	13+00	15+00	RT	140
4	-L-	13+00	14+50	LT	105
4	-L-	16+50	17+20	RT	50
4	-L-	22+50	23+50	LT	70
4	-L-	23+50	24+00	RT	35
			SUBTOTAL		400
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					3,500
			TOTAL		3,900
			SAY		4,000

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	25+50	26+00	RT	20
			SUBTOTAL		20
ADDITIONAL PSRM TO BE INSTALLED					110
			TOTAL		130
			SAY		130