PROJ. REFERENCE NO.	SHEET NO.
B-5325	X-0

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
12+50.00	0	0	
13+00.00	42	8	
13+32.00	90	10	
13+50.00	69	7	
14+00.00	121	27	
14+50.00	42	37	
14+71.49	10	19	
15+00.00	7	28	
15+50.00	5	57	
16+00.00	3	139	
16+13.87	1	59	
16+50.00	9	140	
17+00.00	34	285	
17+20.13	22	166	

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
18+52.67	0	0	
19+00.00	0	763	
19+50.00	0	727	
19+78.20	0	368	
20+00.00	0	269	
20+50.00	0	602	
21+00.00	0	621	
21+50.00	0	627	
22+00.00	0	445	
22+50.00	6	176	81
23+00.00	20	42	99
23+50.00	21	39	44
23+75.00	9	37	
24+00.00	11	45	
24+50.00	14	107	
25+00.00	6	84	
25+50.00	5	40	
25+57.28	1	4	
25+68.00	1	6	
26+00.00	2	14	
26+50.00	3	7	