PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10321.28, 5CR.20321.28	17	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	INCIDENTAL STONE BASE TONS	SHOULDER RECON STRUCTION SMI	1½" MILLING SY	3" MILLING SY	2.5" MILLING SY	2.0" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	INTER MEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE) LF	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP LF
5CR.10321.28	Durham	1	NC 751	NC 54 TO I 40	3	2	NO	NO	1.037	24-72				30,035								3,323	199	100		2					1,200
5CR.10321.28	Durham	2	BUS 15-501	TOWER BLVD TO UNIVERSITY DRIVE	9, 10	4	NO	NO	2.045	44-96				71,005								6,276	377	400							4,020
		"	"	GARRET ROAD TO TOWER BLVD	8	5	NO	NO	1.24	48-108				86,597								7,646	459	200	14,520						2,400
TOTAL FOR MAP NO. 2									**3.285**					**157,602**								**13,922**	**836**	**600**	**14,520**						**6,420**
5CR.10321.28	Durham	3	US 70 BUS 9TH ST	US 70 BUS MAIN ST TO US 70 BUS HILLSBOROUGH RD	2	4	NO	NO	0.246	44					6,350				75			562	34	50		5	3				600
5CR.10321.28	Durham	4	US 70 BUS HILLSBOROUGH RD	US 70 BUS 9TH ST TO STRUCTURE OVER HILLANDALE RD/FULTON ST	4	3	NO	NO	0.928	30-56				20,037								2,124	127	100		3					1,320
5CR.10321.28	Durham	5	NC 157 - GUESS RD	SR 2354 (NORTH POINT DR) TO SR 2482 (PRISON CAMP RD)	1	5	NO	NO	2.273	62-74				64,008								5,859	352	250		4					2,350
		"	"	SR 2482 (PRISON CAMP RD) TO SR 2399 (SIX GABLES RD)	3	2	NO	NO	1.742	52-76				63,608								5,621	337	180		3					600
TOTAL FOR MAP NO. 5									**4.015**					**127,616**								**11,480**	**689**	**430**		**7**					**2,950**
5CR.10321.28	Durham	6	NC 54	SR 1959 (MIAMI BLVD) TO JOINT NEAR WAKE CO. LINE	3	5	NO	NO	0.88	60-74				33,219								2,936	176	150		5					1,600
TOTAL FOR PROJ NO. 5CR.10321.28									**10.391**					**368,509**	**6,350**				**75**			**34,347**	**2,061**	**1,430**	**14,520**	**22**	**3**				**14,090**
5CR.20321.28	Durham	7	SR 1926 - ANGIER AVENUE	SR 1959 (MIAMI BLVD) TO US 70	7	2	NO	NO	1.203	24-36				19,372								1,716	103	150							800
5CR.20321.28	Durham	8	SR 2294 - MOUNT MORIAH ROAD	US 15-501 TO ORANGE CO.	3	2	NO	NO	0.657	24-88				16,570								1,466	88	100							600
5CR.20321.28	Durham	9	SR 1322 - GUESS ROAD	JOINT SOUTH OF I-85 TO SR 1322 (BROAD ST)	1	4	NO	NO	0.346	44-56				9,448								836	50	125		3	2				1,600
5CR.20321.28	Durham	10	SR 1364 - JACKIE ROBINSON ROAD	SR 1118 (FAYETTEVILLE ST) TO BLACKWELL ST	1	2	NO	NO	0.54	26-38				12,408								1,098	66	50		5					920
5CR.20321.28	Durham	11	SR 1365 - MOREHEAD AVENUE	SR 1118 (FAYETTEVILLE ST) TO BLACKWELL ST	1	2	NO	NO	0.52	28-40				11,886								1,052	63	75		6					640
5CR.20321.28	Durham	12	SR 2104 - SLATER ROAD	SR 2103 (EMPEROR BLVD) TO JOINT NEAR WAKE CO.	6	2	NO	NO	0.673	26-38	135	25	1.35			13,288		575	45		2,000	1,176	167	125		4		100	100	0.98	
5CR.20321.28	Durham	13	SR 1261 - AMHURST ROAD	NC 54 TO SR 1106 (BARBEE RD)	7	2	NO	NO	0.269	22				3,472								308	18	20							
5CR.20321.28	Durham	14	SR 1104 - HERNDON RD	SR 1103 (SCOTT KING RD) TO SR 1106 (BARBEE RD)	3	2	NO	NO	1.9	22-34				28,395								2,510	151	200							
5CR.20321.28	Durham	15	SR 1321 - HILLANDALE RD	NEW PAVEMENT TO PINE TREE COURT	1	2	NO	NO	0.214	29				3,641								323	19	35		2					
5CR.20321.28	Durham	16	SR 1116 - GARRETT RD	NC 751 (HOPE VALLEY RD) TO US 15-501	3	2	NO	NO	3.087	24-72				64,173								5,680	341	325		9	5				3,200
5CR.20321.28	Durham	17	SR 1127 - CHAPEL HILL ROAD	SR 1365 (MOREHEAD AVE) TO US 15-501 BUS	1	2	NO	NO	1.51	26-49				34,053								3,013	181	200		7	3				
5CR.20321.28	Durham	18	SR 1902 - KEMP ROAD	SR 1900 (COLEY RD) TO SR 1901 (CARPENTER POND RD)	5	2	NO	NO	0.654	24	131	65	1.31			7,674				590	1,160	816	131	80				175	50	0.95	
5CR.20321.28	Durham	19	SR 1471 - RED MOUNTAIN ROAD	SR 1601 (MOORES MILL RD) TO SR 1605 (MORIAH RD)	7	2	NO	NO	2.716	24							38,241					4,528	272	270							
5CR.20321.28	Durham	20	GUESS ROAD	FROM BROAD ST TO CLUB BLVD	1	4	NO	NO	0.6	44-56				17,419								1,540	92	250		3	2				800
TOTAL FOR PROJ NO. 5CR.20321.28									**14.889**		**266**	**90**	**2.66**	**220,837**		**20,962**	**38,241**	**575**	**45**	**590**	**3,160**	**26,062**	**1,742**	**2,005**		**39**	**12**	**275**	**150**	**1.93**	**8,560**
GRAND TOTAL									**25.28**		**266**	**90**	**2.66**	**589,346**	**6,350**	**20,962**	**38,241**	**575**	**120**	**590**	**3,160**	**60,409**	**3,803**	**3,435**	**14,520**	**61**	**15**	**275**	**150**	**1.93**	**22,650**