PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10321.28, 5CR.20321.28	18	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000-I WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	4457000000 TEMPORARY TRAFFIC CONTROL LS	4510000000 LAW ENFORCEMENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4" X 120 M WHITE THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	8" X 90 M YELLOW THERMO LF	4697000000 8" X 120 M WHITE THERMO LF	4702000000 12" X 120 M WHITE THERMO LF	4710000000 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG ONLY 120 M EA	THERMO MSG SCHOOL 120 M EA	THERMO MSG AHEAD 120 M EA	THERMO MSG STOP 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	THERMO MERGE ARROW 90 M EA	THERMO SYMBOL (HELMETED BICYCLIST) EA	THERMO SYMBOL (BIKE STR ARROW) EA	THERMO SYMBOL (SHARROW) EA	THERMO RAMP ARROW 90 M EA	THERMO STR & LT ARROW 90 M EA	THERMO LT STR RT ARROW 90 M EA
5CR.10321.28	Durham	1	NC 751	NC 54 TO I 40	3	2	1.037	24-72	112		24	11,158		6,844	770	210	375	260		250					18	7	18	6	7						
5CR.10321.28	Durham	2	BUS 15-501	TOWER BLVD TO UNIVERSITY DRIVE	8	4	2.045	44-96	224		100	22,413		13,497		700				364					52	15	26	6	4						
		"	"	GARRET ROAD TO TOWER BLVD	8	5	1.24	48-108	139		60	13,590	13,094		3,274				480	370					30	14	35	4	3						
TOTAL FOR MAP NO. 2							**3.285**		**363**		**160**	**36,003**	**13,094**	**13,497**	**3,274**	**700**			**480**	**734**					**82**	**29**	**61**	**10**	**7**						
5CR.10321.28	Durham	3	US 70 BUS 9TH ST	US 70 BUS MAIN ST TO US 70 BUS HILLSBOROUGH RD	2	4	0.246	44	34			2,647		1,624				288		156					5		1	2							
5CR.10321.28	Durham	4	US 70 BUS HILLSBOROUGH RD	US 70 BUS 9TH ST TO STRUCTURE OVER HILLANDALE RD/FULTON ST	4	3	0.928	30-56	93	*		9,985		6,125				220		142					15	3	6			7	7	10			
5CR.10321.28	Durham	5	NC 157 - GUESS RD - ONE	SR 2354 (NORTH POINT DR) TO SR 2482 (PRISON CAMP RD)	1	5	2.273	62-74	258			24,912		30,004	500			792		260					74	10	15								
		"	"	SR 2482 (PRISON CAMP RD) TO SR 2399 (SIX GABLES RD)	3	2	1.742	52-76	195			18,744		11,497	450		375	1,648		410					28	4	23	8					3		
TOTAL FOR MAP NO. 5							**4.015**		**453**			**43,656**		**41,501**	**950**		**375**	**2,440**		**670**					**102**	**14**	**38**	**8**					**3**		
5CR.10321.28	Durham	6	NC 54	SR 1959 (MIAMI BLVD) TO JOINT NEAR WAKE CO. LINE	3	5	0.88	60-74	101			9,645		11,616	3,226			310		262					27	5	19	4							
TOTAL FOR PROJ NO. 5CR.10321.28							**10.391**		**1,156**	**1**	**184**	**113,094**	**13,094**	**81,207**	**8,220**	**910**	**750**	**3,518**	**480**	**2,214**					**249**	**58**	**143**	**30**	**14**	**7**	**7**	**10**	**3**		
												126,188		**89,427**		**1,660**									**521**										
5CR.20321.28	Durham	7	SR 1926 - ANGIER AVENUE	SR 1959 (MIAMI BLVD) TO US 70	7	2	1.203	24-36	135			12,944		12,704	150		600			60					6			2						4	1
5CR.20321.28	Durham	8	SR 2294 - MOUNT MORIAH ROAD	US 15-501 TO ORANGE CO.	3	2	0.657	24-88	68			7,069		4,336	792		75	150		300					19	13	6	1							
5CR.20321.28	Durham	9	SR 1322 - GUESS ROAD	JOINT SOUTH OF I-85 TO SR 1322 (BROAD ST)	1	4	0.346	44-56	40			3,792		3,654	200			810		150							2	11							
5CR.20321.28	Durham	10	SR 1364 - JACKIE ROBINSON ROAD	SR 1118 (FAYETTEVILLE ST) TO BLACKWELL ST	1	2	0.54	26-38	59			2,690				150																			
5CR.20321.28	Durham	11	SR 1365 - MOREHEAD AVENUE	SR 1118 (FAYETTEVILLE ST) TO BLACKWELL ST	1	2	0.52	28-40	58			5,595		3,432		270		226		88					4		4							1	
5CR.20321.28	Durham	12	SR 2104 - SLATER ROAD	SR 2103 (EMPEROR BLVD) TO JOINT NEAR WAKE CO.	6	2	0.673	26-38	76			7,241		4,442	250			240		30	8				10	2	3							2	
5CR.20321.28	Durham	13	SR 1261 - AMHURST ROAD	NC 54 TO SR 1106 (BARBEE RD)	7	2	0.269	22	26			2,894		1,775																					
5CR.20321.28	Durham	14	SR 1104 - HERNDON RD	SR 1103 (SCOTT KING RD) TO SR 1106 (BARBEE RD)	3	2	1.9	22-34	213	*		20,444		12,540	550		600			22					10	1									
5CR.20321.28	Durham	15	SR 1321 - HILLANDALE RD	NEW PAVEMENT TO PINE TREE COURT	1	2	0.214	29	24			2,303		1,412																					
5CR.20321.28	Durham	16	SR 1116 - GARRETT RD	NC 751 (HOPE VALLEY RD) TO US 15-501	3	2	3.087	24-72	348			33,216		20,374	400		1,100	1,135		830		12			58	15	11	2					6		
5CR.20321.28	Durham	17	SR 1127 - CHAPEL HILL ROAD	SR 1365 (MOREHEAD AVE) TO US 15-501 BUS	1	2	1.51	26-49	170			16,248		9,966	400		750	350		544		18	5	4	19	3	3	3							
5CR.20321.28	Durham	18	SR 1902 - KEMP ROAD	SR 1900 (COLEY RD) TO SR 1901 (CARPENTER POND RD)	5	2	0.654	24	74			7,037		4,316																					
5CR.20321.28	Durham	19	SR 1471 - RED MOUNTAIN ROAD	SR 1601 (MOORES MILL RD) TO SR 1605 (MORIAH RD)	7	2	2.716	24	305			29,224		17,926						48															
5CR.20321.28	Durham	20	GUESS ROAD	FROM BROAD ST TO CLUB BLVD	1	4	0.6	44-56	80					7,128	2,034			534		150					8	1	6	7						2	
TOTAL FOR PROJ NO. 5CR.20321.28							**14.889**		**1,676**	**1**		**150,697**		**104,005**	**4,776**	**420**	**3,125**	**3,445**		**2,222**	**8**	**30**	**5**	**4**	**134**	**35**	**35**	**26**					**6**	**9**	**1**
												150,697		**108,781**		**3,545**						**47**			**246**										
GRAND TOTAL							**25.28**		**2,832**	**1**	**184**	**263,791**	**13,094**	**185,212**	**12,996**	**1,330**	**3,875**	**6,963**	**480**	**4,436**	**8**	**30**	**5**	**4**	**383**	**93**	**178**	**56**	**14**	**7**	**7**	**10**	**9**	**9**	**1**
												276,885		**198,208**		**5,205**						**47**			**767**										