PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10321.28, 5CR.20321.28	19	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4770000000-E 4" YELLOW COLD APPLIED PLASTIC, TYPE III LF	4770000000-E 4" WHITE COLD APPLIED PLASTIC, TYPE III LF	4810000000-E 4" WHITE PAINT LF	4810000000-E 4" YELLOW PAINT LF	4820000000-E 8" WHITE PAINT LF	4820000000-E 8" YELLOW PAINT LF	4825000 12" WHITE PAINT LF	483500 24" WHITE PAINT LF	4840000000-N PAINT MSG ONLY EA	4840000000-N PAINT MSG SCHOOL EA	4840000000-N PAINT MSG AHEAD EA	4840000000-N PAINT MSG STOP EA	4845000000-N PAINT LT ARROW EA	4845000000-N PAINT RT ARROW EA	4845000000-N PAINT STR ARROW EA	4845000000-N PAINT STR & RT ARROW EA	4845000000-N PAINT MERGE ARROW EA	4845000000-N PAINT STR & LT ARROW EA	4845000000-N PAINT LT STR RT ARROW EA	48500000 4" LINE REMOVAL LF	4900000000-N CRYSTAL & RED MARKERS EA	4905000000-N YELLOW & YELLOW MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS EA
5CR.10321.28	Durham	1	NC 751	NC 54 TO I 40	3	2	1.037	24-72	400	400	11,928	6,844	470	375		250					18	7	18	6	7			800	125	68	
5CR.10321.28	Durham	2	BUS 15-501	TOWER BLVD TO UNIVERSITY DRIVE	8	4	2.045	44-96			22,413	13,497	700			364					52	15	26	6	4						385
		"	"	GARRET ROAD TO TOWER BLVD	8	5	1.24	48-108			16,864	15,000			480	370					30	14	35	4	3						292
TOTAL FOR MAP NO. 2							**3.285**				**39,277**	**28,497**	**700**		**480**	**734**					**82**	**29**	**61**	**10**	**7**						**677**
5CR.10321.28	Durham	3	US 70 BUS 9TH ST	US 70 BUS MAIN ST TO US 70 BUS HILLSBOROUGH RD	2	4	0.246	44			2,647	1,624	288			156					5		1	2							
5CR.10321.28	Durham	4	US 70 BUS HILLSBOROUGH RD	US 70 BUS 9TH ST TO STRUCTURE OVER HILLANDALE RD/FULTON ST	4	3	0.928	30-56			8,963	5,498	220			142					15	3	8						36		
5CR.10321.28	Durham	5	NC 157 - GUESS RD - ONE	SR 2354 (NORTH POINT DR) TO SR 2482 (PRISON CAMP RD)	1	5	2.273	62-74			25,412	30,004	792			260					74	10	15								375
		"	"	SR 2482 (PRISON CAMP RD) TO SR 2399 (SIX GABLES RD)	3	2	1.742	52-76		375	19,194	11,497	1,648	375		410					28	4	23	8	3			375			270
TOTAL FOR MAP NO. 5							**4.015**			**375**	**44,606**	**41,501**	**2,440**	**375**		**670**					**102**	**14**	**38**	**8**	**3**			**375**			**645**
5CR.10321.28	Durham	6	NC 54	SR 1959 (MIAMI BLVD) TO JOINT NEAR WAKE CO. LINE	3	5	0.88	60-74			11,345	11,616	310			262					27	5	19	4					325	120	
TOTAL FOR PROJ NO. 5CR.10321.28							**10.391**		**400**	**775**	**118,766**	**95,580**	**4,428**	**750**	**480**	**2,214**					**249**	**58**	**145**	**30**	**17**			**1,175**	**486**	**188**	**1,322**
									1,175		**214,346**		**5,178**								**499**								**674**		
5CR.20321.28	Durham	7	SR 1926 - ANGIER AVENUE	SR 1959 (MIAMI BLVD) TO US 70	7	2	1.203	24-36			13,094	12,704		600		60					6			2					15	79	
5CR.20321.28	Durham	8	SR 2294 - MOUNT MORIAH ROAD	US 15-501 TO ORANGE CO.	3	2	0.657	24-88			7,861	4,336	150	75		300					19	13	6	1					55	43	
5CR.20321.28	Durham	9	SR 1322 - GUESS ROAD	JOINT SOUTH OF I-85 TO SR 1322 (BROAD ST)	1	4	0.346	44-56			3,992	3,654	810			150							2	11		4	1		30	23	
5CR.20321.28	Durham	10	SR 1364 - JACKIE ROBINSON ROAD	SR 1118 (FAYETTEVILLE ST) TO BLACKWELL ST	1	2	0.54	26-38			2,690		150																40		
5CR.20321.28	Durham	11	SR 1365 - MOREHEAD AVENUE	SR 1118 (FAYETTEVILLE ST) TO BLACKWELL ST	1	2	0.52	28-40			5,466	3,353	496			88					4		4			1			55		
5CR.20321.28	Durham	12	SR 2104 - SLATER ROAD	SR 2103 (EMPEROR BLVD) TO JOINT NEAR WAKE CO.	6	2	0.673	26-38			7,491	4,442	240			30	4				10	2	3			2			40	44	
5CR.20321.28	Durham	13	SR 1261 - AMHURST ROAD	NC 54 TO SR 1106 (BARBEE RD)	7	2	0.269	22			2,894	1,775																		18	
5CR.20321.28	Durham	14	SR 1104 - HERNDON RD	SR 1103 (SCOTT KING RD) TO SR 1106 (BARBEE RD)	3	2	1.9	22-34			20,994	12,540		600		22					10	1							20	125	
5CR.20321.28	Durham	15	SR 1321 - HILLANDALE RD	NEW PAVEMENT TO PINE TREE COURT	1	2	0.214	29			2,303	1,412																		14	
5CR.20321.28	Durham	16	SR 1116 - GARRETT RD	NC 751 (HOPE VALLEY RD) TO US 15-501	3	2	3.087	24-72	750		33,616	20,374	1,135	1,100		930		12			58	15	11	2	6			750	275	407	
5CR.20321.28	Durham	17	SR 1127 - CHAPEL HILL ROAD	SR 1365 (MOREHEAD AVE) TO US 15-501 BUS	1	2	1.51	26-49			16,648	9,966	350	750		694		18	5	4	19	3	3	3					75	100	
5CR.20321.28	Durham	18	SR 1902 - KEMP ROAD	SR 1900 (COLEY RD) TO SR 1901 (CARPENTER POND RD)	5	2	0.654	24			7,037	4,316																		43	
5CR.20321.28	Durham	19	SR 1471 - RED MOUNTAIN ROAD	SR 1601 (MOORES MILL RD) TO SR 1605 (MORIAH RD)	7	2	2.716	24			29,224	17,926				48														179	
5CR.20321.28	Durham	20	GUESS ROAD	FROM BROAD ST TO CLUB BLVD	1	4	0.6	44-56			2,034	7,128	534			150					8	1	6	7		2			92	60	
TOTAL FOR PROJ NO. 5CR.20321.28							**14.889**		**750**		**155,344**	**103,926**	**3,865**	**3,125**		**2,472**	**4**	**30**	**5**	**4**	**134**	**35**	**35**	**26**	**6**	**9**	**1**	**750**	**697**	**1,135**	
									750		**259,270**		**6,990**					**43**			**246**								**1,832**		
GRAND TOTAL							**25.28**		**1,150**	**775**	**274,110**	**199,506**	**8,293**	**3,875**	**480**	**4,686**	**4**	**30**	**5**	**4**	**383**	**93**	**180**	**56**	**23**	**9**	**1**	**1,925**	**1,183**	**1,323**	**1,322**
									1,925		**473,616**		**12,168**					**43**			**745**								**2,506**		