PROJECT REFERENCE NO.	SHEET NO.
R-5115	EC-3A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	11+25	12+25	LT	120
4	-L-	10+50	12+25	RT	185
4	-L-	12+75	13+50	RT	135
4	-L-	13+75	15+50	LT	200
4	-L-	15+50	16+25	LT	75
4	-Y23-	15+00	16+00	RT	115
4	-Y23-	16+00	18+50	RT	330
				SUBTOTAL	1160
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					7875
				TOTAL	9035
				SAY	9100

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	10+25	11+25	LT	95
4	-L-	16+50	17+25	LT	150
4	-Y23-	12+50	14+00	RT	90
				SUBTOTAL	335
		ADDITIONAL PSRM TO BE INSTALLED			0
				TOTAL	335
				SAY	350