8/17/99

PROJECT REFERENCE NO.	SHEET NO.
R-2519B	1-A

ROADWAY DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 25477 ENGINEER THAD F. DUNCAN

DocuSigned by: Thad F. Duncan 9/19/2014

12B4BCAA831748E...

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1A	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS
1B	CONVENTIONAL SYMBOLS
1C-1 THRU 1C-12	SURVEY CONTROL SHEETS
2A-1 THRU 2A-4	PAVEMENT SCHEDULE AND TYPICAL SECTIONS
2C-1	DETAIL OF SHOULDER BERM GUTTER TO EXPRESSWAY GUTTER TRANSITION SECTION
2C-2	CHAIN LINK FENCE ON CONCRETE BARRIER
2C-3	GUARDRAIL ANCHOR UNIT TYPE B-77
2C-4 THRU 2C-5	TRAFFIC BEARING JUNCTION BOX
2C-6	EMERGENCY VEHICLE ACCESS FOR CONCRETE ISLAND
2C-7	WELDED STEEL PIPE LINER INSIDE CORRUGATED STEEL PIPE
2C-8	DETAIL OF 2'9" TO 2'6" CURB AND GUTTER TRANSITION SECTION
2C-9	2'9" CONCRETE CURB AND GUTTER
2C-10	CONCRETE CATCH BASIN (3 OR 4 SIDE OPEN THROAT) (MANHOLE OPTION)
2C-11	TRAFFIC BEARING JUNCTION BOX FOR EXISTING 4X4' RCBC AND PROPOSED 60" RCP
2D-1 THRU 2D-4	DRAINAGE DITCH DETAILS
2D-5	UT TO BRUSHY CREEK STREAM RELOCATION
2D-6	LONG BRANCH STREAM RELOCATION
2D-7	PERFORATED CONCRETE CATCH BASIN W/SINGLE PIPE
2G-1 THRU 2G-2	STANDARD REINFORCED SOIL SLOPES
2G-3	STANDARD TEMPORARY SHORING
2G-4 THRU 2G-6	STANDARD TEMPORARY WALL
3B-1 THRU 3B-4	EARTHWORK, GUARDRAIL, ASPHALT REMOVAL & ASPHALT BREAKING
3D-1 THRU 3D-25	DRAINAGE SUMMARIES
3G-1	SUBSURFACE DRAINAGE, GEOTEXTILE & AGGREGATE STABILIZATION
3P-1 THRU 3P-3	PARCEL INDEX SHEETS
4 THRU 34	PLAN SHEETS
35 THRU 71	PROFILE SHEETS
TMP-1 THRU TMP-116	TRANSPORTATION MANAGEMENT PLANS
PMP-1 THRU PMP-34	PAVEMENT MARKING PLANS
EC-1 THRU EC-65A	EROSION CONTROL PLANS
RF-1 THRU RF-3	REFORESTATION PLANS
SIGN-1 THRU SIGN-34	SIGNING PLANS
UO-1 THRU UO-30	UTILITIES BY OTHERS PLANS
X-A	CROSS SECTION INDEX SUMMARY
X-1A THRU X-1H	CROSS SECTION SUMMARY
X-1 THRU X-600	CROSS SECTIONS
S-1 THRU S-194	STRUCTURE PLANS
C-1 THRU C-87	CULVERT PLANS
W-1 THRU W-12	RETAINING WALL PLANS

GENERAL NOTES:

2012 SPECIFICATIONS
EFFECTIVE: 01-17-12
REVISED: 07/30/12

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

BERM DITCHES:

BERM DITCHES SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 240.01 AT LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

UNDERDRAINS:

UNDERDRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.03 AT LOCATIONS DIRECTED BY THE ENGINEER.

DRIVEWAYS:

DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 848.02 USING 3' RADII OR RADII AS SHOWN ON THE PLANS. LOCATIONS OF DRIVES WILL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC NOT SHOWN ON THE PLANS WILL BE PAID FOR AT THE CONTRACT PRICE FOR "TEMPORARY SHORING".

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE DUKE ENERGY PROGRESS-TRANSMISSION POWER, DUKE ENERGY PROGRESS-DISTRIBUTION POWER, FRENCH BOARD EMC-DISTRIBUTION POWER, FRONTIER COMMUNICATION-TELEPHONE, AT&T-TELEPHONE, CHARTER COMMUNICATION-CATV, COUNTRY CABLEVISION-CATV,

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

ROCK:

ROCK IS ANTICIPATED BETWEEN...

LINE	STATION INTERVAL
-Y5-	10+50 TO 11+50 LT
-Y5-	12+15 TO 12+25 LT
-L-	49+40 TO 50+95 RT
-L-	55+00 TO 55+50 RT
-L-	88+25 TO 88+40 RT
-L-	89+05 TO 89+45 RT
-L-	90+25 TO 90+40 RT
-L-	91+00 TO 91+30 RT
-L-	128+50 TO 134+60 RT
-Y16-	10+30 TO 10+80 RT
-L-	159+00 TO 164+10 RT
-L-	231+05 TO 232+10 LT
-L-	278+10 TO 278+20 LT
-L-	278+30 TO 278+40 LT
-L-	278+50 TO 279+30 LT

LINE	STATION INTERVAL
-L-	287+00 TO 287+10 LT
-L-	287+20 TO 287+35 LT
-L-	308+90 TO 309+35 LT
-DR11-	10+90 TO 13+30 RT
-L-	324+85 TO 325+05 LT
-L-	325+65 TO 326+35 LT
-L-	340+25 TO 340+40 RT
-L-	340+90 TO 341+20 RT
-L-	353+00 TO 353+15 LT
-L-	423+00 TO 424+45 LT

BLASTING MAY BE REQUIRED FOR EXCAVATION ON THE PROJECT. SEE SECTION 220 OF THE STANDARD SPECIFICATIONS AND IF APPLICABLE, ROCK BLASTING PROVISION.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	Method of Clearing - Method II
225.02	Guide for Grading Subgrade - Secondary and Local
225.04	Method of Obtaining Superelevation - Two Lane Pavement
225.06	Method of Grading Sight Distance at Intersections
240.01	Guide for Berm Ditch Construction
DIVISION 3 - PIPE CULVERTS	
300.01	Method of Pipe Installation
310.02	Parallel Pipe End Section - Precast Concrete Section for 15" to 24" Pipe
310.04	Parallel Pipe End Section - Prefabricated Steel Section for 15" to 24" Pipe
310.10	Driveway Pipe Construction
DIVISION 4 - MAJOR STRUCTURES	
422.10	Reinforced Bridge Approach Fills
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS	
560.01	Method of Shoulder Construction - High Side of Superelevated Curve - Method I
DIVISION 6 - ASPHALT BASES AND PAVEMENTS	
654.01	Pavement Repairs
DIVISION 8 - INCIDENTALS	
806.01	Concrete Right-of-Way Marker
806.02	Granite Right-of-Way Marker
815.02	Subsurface Drain
815.03	Pipe Underdrain and Blind Drain
838.01	Concrete Endwall for Single and Double Pipe Culverts - 15" thru 48" Pipe 90 Skew
838.02	Concrete Endwall and Sluice Gate - 15" thru 36" Pipe 90 Skew
838.11	Brick Endwall for Single and Double Pipe Culverts - 15" thru 48" Pipe 90 Skew
838.21	Reinforced Concrete Endwall - for Single 54" Pipe 90 Skew
838.27	Reinforced Concrete Endwall - for Single 60" Pipe 90 Skew
838.45	Notes for Reinforced Concrete Endwall - Std. Dwg 838.21 thru 838.40
838.51	Reinforced Brick Endwall - for Single 54" Pipe 90 Skew
838.57	Reinforced Brick Endwall - for Single 60" Pipe 90 Skew
838.75	Notes for Reinforced Brick Endwall - Std. Dwg 838.51 thru 838.70
838.80	Precast Endwalls - 12" thru 72" Pipe 90 Skew
840.00	Concrete Base Pad for Drainage Structures
840.01	Brick Catch Basin - 12" thru 54" Pipe
840.02	Concrete Catch Basin - 12" thru 54" Pipe
840.03	Frame, Grates and Hood - for Use on Standard Catch Basin
840.04	Concrete Open Throat Catch Basin - 12" thru 48" Pipe
840.05	Brick Open Throat Catch Basin - 12" thru 48" Pipe
840.14	Concrete Drop Inlet - 12" thru 30" Pipe
840.15	Brick Drop Inlet - 12" thru 30" Pipe
840.16	Drop Inlet Frame and Grates - for use with Std. Dwg 840.14 and 840.15
840.17	Concrete Grated Drop Inlet Type 'A' - 12" thru 72" Pipe
840.18	Concrete Grated Drop Inlet Type 'B' - 12" thru 36" Pipe
840.19	Concrete Grated Drop Inlet Type 'D' - 12" thru 36" Pipe
840.24	Frames and Narrow Slot Sag Grates
840.26	Brick Grated Drop Inlet Type 'A' - 12" thru 72" Pipe
840.27	Brick Grated Drop Inlet Type 'B' - 12" thru 36" Pipe
840.28	Brick Grated Drop Inlet Type 'D' - 12" thru 36" Pipe
840.29	Frames and Narrow Slot Flat Grates
840.31	Concrete Junction Box - 12" thru 66" Pipe
840.32	Brick Junction Box - 12" thru 66" Pipe
840.34	Traffic Bearing Junction Box - For Use With Pipes 42" And Under
840.35	Traffic Bearing Grated Drop Inlet - for Cast Iron Double Frame and Grates
840.41	Spring Box - Concrete or Brick
840.45	Precast Drainage Structure
840.46	Traffic Bearing Precast Drainage Structure
840.52	Precast Manhole 4', 5' and 6' Diameter - 12" thru 48" Pipe
840.54	Manhole Frame and Cover
840.66	Drainage Structure Steps
840.71	Concrete and Brick Pipe Plug
840.72	Pipe Collar
846.01	Concrete Curb, Gutter and Curb & Gutter
846.02	Drop Inlet Installation in Expressway Gutter
846.04	Drop Inlet Installation in Shoulder Berm Gutter
848.02	Driveway Turnout - Radius Type
850.01	Concrete Paved Ditches
850.10	Guide for Berm Drainage Outlet - 15" and 18" Pipe
850.11	Guide for Berm Drainage Outlet - 24" and 30" Pipe
852.01	Concrete Islands
852.04	Method for Placement of Drop Inlets in Grassed Median - Using 1'-6" Curb and Gutter
852.05	Median Curb for Catch Basin - for Use with 1'-6" Curb and Gutter
852.06	Method for Placement of Drop Inlets in Concrete Islands
857.01	Precast Reinforced Concrete Barrier - 41" Single Faced
862.01	Guardrail Placement
862.02	Guardrail Installation
862.04	Anchoring End of Guardrail - B-77 and B-83 Anchor Units
866.01	Chain Link Fence - 4', 5' and 6' High Fence
866.02	Woven Wire Fence - with Wood Post
876.01	Rip Rap in Channels
876.02	Guide for Rip Rap at Pipe Outlets
876.04	Drainage Ditches with Class 'B' Rip Rap

17-SEP-2014 09:26
R:\Roadway\Proj\r2519b_rdy_tsh.dgn
$$$$USERNAME$$$$