PROJ. REFERENCE NO.	SHEET NO.
R-2516B	X-1B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
162+00.00	53	15
162+50.00	75	21
163+00.00	105	21
163+50.00	120	21
164+00.00	113	20
164+50.00	112	9
165+00.00	108	11
165+50.00	98	21
166+00.00	98	16
166+50.00	86	17
167+00.00	76	20
167+50.00	86	24
168+00.00	90	21
168+50.00	90	8
169+00.00	89	1
169+50.00	81	18
170+00.00	73	28
170+50.00	65	21
171+00.00	63	21
171+50.00	67	20
172+00.00	63	22
172+50.00	48	20
173+00.00	30	15

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
173+00.00	0	0
173+50.00	28	14
174+00.00	51	15
174+50.00	65	15
175+00.00	55	15
175+50.00	46	17
176+00.00	30	20
176+50.00	15	25
177+00.00	11	29
177+50.00	10	30
178+00.00	8	32
178+50.00	7	33
179+00.00	8	33
179+50.00	71	30
180+00.00	146	26
180+50.00	84	29
181+00.00	11	24
181+50.00	26	15
182+00.00	45	15
182+50.00	46	11
183+00.00	42	8
183+50.00	45	8
184+00.00	44	10
184+50.00	35	9
185+00.00	47	9
185+50.00	60	7

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
186+00.00	54	8
186+50.00	46	9
187+00.00	52	7
187+50.00	83	7
188+00.00	93	8
188+50.00	71	8
189+00.00	69	7
189+50.00	84	6
190+00.00	86	6
190+50.00	84	6
191+00.00	70	5
191+50.00	96	4
192+00.00	133	6
192+50.00	111	7
193+00.00	112	3
193+50.00	127	0
194+00.00	110	0
194+50.00	63	48
195+00.00	32	152
195+50.00	29	104
196+00.00	33	25
196+50.00	106	26
197+00.00	134	2
197+50.00	95	0
198+00.00	59	27

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
198+00.00	0	0
198+50.00	67	34
199+00.00	112	22
199+50.00	112	35
200+00.00	108	42
200+50.00	104	42
201+00.00	94	43
201+50.00	112	41
202+00.00	133	42
202+50.00	138	44
203+00.00	115	36
203+50.00	42	48
204+00.00	0	74
204+50.00	0	110
205+00.00	0	120
205+50.00	0	209
206+00.00	0	473
206+50.00	0	699
207+00.00	0	757
207+50.00	0	785
208+00.00	0	1004
208+50.00	0	1295
209+00.00	0	1045
209+50.00	0	429

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
210+00.00	5	118
210+50.00	10	70
211+00.00	5	105
211+50.00	0	183
212+00.00	0	162
212+50.00	2	81
213+00.00	2	90
213+50.00	0	1163
214+00.00	0	3566
214+50.00	0	4238
215+00.00	0	2010
215+50.00	2	243
216+00.00	241	13
216+50.00	1500	0
217+00.00	3669	0
217+50.00	5872	0
218+00.00	7808	0
218+50.00	8294	0
219+00.00	6985	1
219+50.00	5866	1
220+00.00	4910	0
220+50.00	4090	0
221+00.00	4328	9
221+50.00	4755	9
222+00.00	4650	0
222+50.00	4014	12
223+00.00	1833	17

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
223+00.00	0	0
223+50.00	53	16
224+00.00	24	129
224+50.00	12	400
225+00.00	13	637
225+50.00	22	476
226+00.00	80	135
226+50.00	179	48
227+00.00	391	87
227+50.00	968	79
228+00.00	1764	38
228+50.00	2502	20
229+00.00	3469	21
229+50.00	4516	22
230+00.00	5124	21
230+50.00	5197	22
231+00.00	4764	22
231+50.00	4108	23
232+00.00	3536	25
232+50.00	1647	21
233+00.00	700	17
233+50.00	1385	24

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
234+00.00	1178	18
234+50.00	488	54
235+00.00	4	352
235+50.00	211	309
236+00.00	838	13
236+50.00	1565	13
237+00.00	2316	20
237+50.00	3168	25
238+00.00	3911	24
238+50.00	4561	24
239+00.00	5042	25
239+50.00	5268	30
240+00.00	4496	35
240+50.00	2903	36
241+00.00	2003	39
241+50.00	1840	43
242+00.00	1621	65
242+50.00	1135	117
243+00.00	574	330
243+50.00	149	652
244+00.00	0	862
244+50.00	0	995
245+00.00	0	1084
245+50.00	0	2474
246+00.00	0	4138
246+50.00	0	4497
247+00.77	0	4625

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
248+85.77	0	2996
249+50.00	0	0
250+00.00	0	1578
250+50.00	0	767
251+00.00	0	735
251+50.00	0	800
252+00.00	1183	560
252+50.00	3429	174
253+00.00	5217	61
253+50.00	6622	43
254+00.00	7119	25
254+50.00	7366	16
255+00.00	8066	9
255+50.00	8752	5
256+00.00	9437	2
256+50.00	9608	0
257+00.00	8575	0
257+50.00	5825	4
258+00.00	2380	8
258+50.00	636	7
259+00.00	422	7
259+50.00	956	4

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
260+00.00	2777	0
260+50.00	4971	0
261+00.00	7056	1
261+50.00	10086	12
262+00.00	12951	17
262+50.00	14055	10
263+00.00	14056	6
263+50.00	13130	3
264+00.00	11889	2
264+50.00	10471	6
265+00.00	7793	14
265+50.00	3505	11
266+00.00	697	19
266+50.00	207	78
267+00.00	525	71
267+50.00	1438	27
268+00.00	1812	23
268+50.00	1600	18
269+00.00	1222	26
269+50.00	836	26
270+00.00	489	26

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
270+00.00	0	0
270+50.00	206	20
271+00.00	929	19
271+50.00	1829	33
272+00.00	1703	49
272+50.00	1406	53
273+00.00	1169	47
273+50.00	880	35
274+00.00	521	23
274+50.00	239	32
275+00.00	67	228
275+50.00	0	473
276+00.00	0	393
276+50.00	1	212
277+00.00	62	95
277+50.00	431	15
278+00.00	1164	20
278+50.00	2299	23
279+00.00	2826	21
279+50.00	2994	21
280+00.00	3456	16
280+50.00	3828	15
281+00.00	4012	19
281+50.00	3645	13
282+00.00	2544	15
282+50.00	935	162
283+00.00	70	606
283+50.00	0	1029

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
284+00.00	0	1159
284+50.00	135	802
285+00.00	759	227
285+50.00	1541	19
286+00.00	2467	15
286+50.00	3638	15
287+00.00	4792	18
287+50.00	6018	14
288+00.00	7133	6
288+50.00	8174	7
289+00.00	10685	5
289+50.00	12430	3
290+00.00	11381	19

Station LEFT L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
290+00.00	0	0
290+50.00	9900	39
291+00.00	8619	34
291+50.00	4109	12
292+00.00	5047	9
292+50.00	8911	27
293+00.00	6041	38
293+50.00	2937	48
294+00.00	1719	44
294+50.00	2943	20
295+00.00	5116	8
295+50.00	6395	17
296+00.00	6459	26
296+50.00	5822	31
297+00.00	5044	17
297+50.00	4609	14
298+00.00	5076	14
298+50.00	5706	12
299+00.00	5227	21
299+50.00	3690	16
300+00.00	2533	51
300+50.00	2270	354
301+00.00	1652	1010
301+50.00	546	1955
302+00.00	15	4567
302+50.00	13	6389
303+00.00	14	5870
303+50.00	16	4456
304+00.00	16	2567
304+50.00	13	1490
305+00.00	8	940
305+50.00	4	966
306+00.00	1	772
306+50.00	0	194
307+00.00	308	63
307+50.00	1006	49