PROJ. REFERENCE NO.	SHEET NO.
R-0623	PMP-1A

FINAL PAVEMENT MARKING SCHEDULE

MATERIAL	SYMBOL	DESCRIPTION
PAVEMENT MARKING		
THERMOPLASTIC (4″, 90 MILS)		
	TA	WHITE EDGELINE
	TB	YELLOW EDGELINE
THERMOPLASTIC (4″, 120 MILS)		
	T8	WHITE MINI-SKIP 2′/6′
	T9	YELLOW MINI-SKIP 2′/6′
	TC	10′ WHITE SKIP
	TD	WHITE MINI-SKIP 3′/9′
	TE	WHITE SOLID LANE LINE
	TI	YELLOW DOUBLE CENTER LINE
COLD APPLIED PLASTICS (4″) TYPE 3 - PERMANENT WET REFLECTIVE		
	CA	WHITE EDGELINE
	CB	YELLOW EDGELINE
	CC	10′ WHITE SKIP
THERMOPLASTIC (8″, 90 MILS)		
	TN	WHITE GORE LINE
	TO	WHITE DIAGONAL
	TP	YELLOW DIAGONAL
THERMOPLASTIC (24″, 120 MILS)		
	T2	WHITE STOP BAR
THERMOPLASTIC SYMBOL (90 MILS)		
	UA	LEFT TURN ARROW
	UB	RIGHT TURN ARROW
	UC	STRAIGHT ARROW
	UE	STRAIGHT/RIGHT ARROW
	UN	24″ YIELD LINE TRIANGLE
	UP	MERGE ARROW
	UT	U-TURN SYMBOL
THERMOPLASTIC CHARACTER (120 MILS)		
	UI	ALPHANUMERIC CHARACTER
PAVEMENT MARKERS		
PERMANENT RAISED		
	MB	CRYSTAL & RED
SNOWPLOWABLE RAISED		
	ME	YELLOW & YELLOW
	MF	CRYSTAL & RED

NOTE: ALL LANE WIDTHS ARE 12′ UNLESS OTHERWISE SHOWN.

LEGEND

GENERAL

DIRECTION OF TRAFFIC FLOW

NORTH ARROW

PROPOSED PVMT. ---------- EXIST. PVMT.

PAVEMENT MARKINGS

PAVEMENT MARKING SYMBOLS

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

APPROVED: Rhonda B. Early DATE: 8/4/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 023521 ENGINEER RHONDA B. EARLY

FINAL PAVEMENT MARKING PLANS

8/17/99

REVISIONS

QA/QC STAGE:

REVIEW:

CONCUR:

REVISE:

VERIFY:

11:05:53 AM
:\PMP\Plans\R0623_pmp_01.dgn
$$$$USERNAME$$$$