T.I.P.: R-0623

CONTRACT:

TIP NO.	SHEET NO.
R-0623	SIGN-1

APPROVED: DocuSigned by: Charles A. Johnson, III 59A1565B47F54A6...

DATE: 8/4/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 20675 ENGINEER CHARLES A. JOHNSON III

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
MONTGOMERY COUNTY

LOCATION: NC-24/27 TROY BYPASS FROM WEST OF SR 1138 (DAIRY RD) TO JUST EAST OF LITTLE RIVER

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.50	ARROWS AND SHIELDS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	4902	LF
4096000000	904	SIGN ERECTION, TYPE D	15	EA
4102000000	904	SIGN ERECTION, TYPE E	178	EA
4108000000	904	SIGN ERECTION, TYPE F	57	EA
4116100000	904	SIGN ERECTION, RELOCATE SIGN TYPE D	3	EA
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	45	EA
4238000000	907	DISPOSAL OF SIGN, D, E OR F	3	EA
4360000000	SP	DISPOSAL OF SIGN SYSTEM ON SPAN WIRE	1	EA

PAY ITEM NOTES

1 SIGN ERECTION, TYPE D, E, AND F
2 SIGN ERECTION, RELOCATE SIGN TYPE D
3 DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4 DISPOSAL OF SUPPORT, U-CHANNEL
5 DISPOSAL OF SIGN, D, E OR F
6 DISPOSAL OF SIGN SYSTEM ON SPAN WIRE

GENERAL NOTES

. SIGNS FURNISHED BY STATE

. **ALL EXISTING SIGNS/SIGN SYSTEMS WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON THE PLANS. THE SIGNS TO BE DISPOSED ARE NOT SHOWN ON THE PLANS; HOWEVER THE PAY ITEM/QUANTITY IS INCLUDED IN THE CONTRACT.**

. ALL PROPOSED SIGNS SEE PAY ITEM NOTE 1 UNLESS OTHERWISE NOTED ON PLAN SHEETS.

. ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING, SEE TRAFFIC CONTROL PLANS. SEE PAVEMENT MARKING PLAN FOR PAVEMENT MARKING DESIGN.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL TYPE 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.

. THE BACKGROUND FOR TYPE 'E' AND 'F' SIGNS SHALL BE GRADE C REFLECTIVE SHEETING UNLESS OTHERWISE NOTED.

. SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2	KEY SHEET
SIGN-3-3C	SIGN DESIGNS
SIGN-4-4B	SIGN DESIGNS, TYPE E & F SIGNS
SIGN-5-19	SIGN DETAIL SHEETS

PLAN PREPARED BY :

HNTB

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

C.A. JOHNSON, III, PE — *SIGNING PROJECT ENGINEER*
A.D. KLINKSIEK, PE, PTOE — *SIGNING DESIGN ENGINEER*
T.R. TERRELL — *SIGNING DESIGN TECHNICIAN*

CONTACTS: N.C.D.O.T. SIGNING AND DELINEATION UNIT

SUSAN KUNZ — SIGNING & DELINEATION REGIONAL ENGINEER
STACEY JOHNS — SIGNING & DELINEATION PROJECT DESIGN ENGINEER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION