STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	R-0623	1	158

STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION
34352.1.1	STP-24(6)	P.E.
		R/W & UTIL.

NOTE: SEE SHEET 2A FOR PLAN SHEET LAYOUT AT TIME OF INVESTIGATION

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

ROADWAY SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 34352.1.1(R-0623) F.A. PROJ. STP-24(6)

COUNTY MONTGOMERY

PROJECT DESCRIPTION NC 24/27 TROY BYPASS FROM SR 1138 (DAIRY RD.) TO EAST OF LITTLE RIVER

INVENTORY

CONTENTS

LINE	STATION	PLAN	PROFILE	XSECT
-L1-	17+00 to 28+91	4-5	36	
-L2-	18+50 to 28+91	4-5	36	
-L-	28+84 to 368+00	5-31	37-50	56-142
-Y1-	14+00 to 20+00	6	51	
-Y2-	10+47 to 15+50	7	51	
-Y3-	10+47 to 12+25	8	51	
-Y5-	11+50 to 12+82	6	52	
-Y6-	11+00 to 19+65	15,33	52	
-Y7-	10+09 to 25+00	33-34	52-53	
-Y8-	11+60 to 17+50	22	53	
-Y9-	11+50 to 23+66	26,35	53	143-144
-Y10-	14+00 to 22+00	27	54	
-Y11-	13+50 to 22+00	26-27,35	54	
-Y12-	15+00 to 18+14	9,32	55	
-Y13-	10+50 to 25+00	10,32	55	

DESCRIPTION	SHEET
ROCK PHOTOS	145-151
ROCK TEST RESULTS	152-155
SOIL TEST RESULTS	156
ADDITIONAL LOGS	157-158

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

PERSONNEL

AMERIDRILL

M. BACHMAN

A. LOFTIN

S. WHITE

B. FRENCH

J. HVOZDIK

S. CROCKETT

INVESTIGATED BY P. ZHANG

CHECKED BY G. LANG

SUBMITTED BY P. ZHANG

DATE APRIL, 2013

NORTH CAROLINA PROFESSIONAL SEAL 030788 ENGINEER PU ZHANG

URS

URS CORPORATION - NORTH CAROLINA
1600 PERIMETER PARK DRIVE, SUITE 400
MORRISVILLE, NORTH CAROLINA 27560

4-29-13

SIGNATURE

DRAWN BY: P. ZHANG, S. CROCKETT

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

CONTRACT: ID: R-0623