RD223236

COMPUTED BY:	JDG	DATE:	5/28/2014
CHECKED BY:	SCL	DATE:	9/7/2014

PROJECT NO.	SHEET NO.
R-4903	3G-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUBSURFACE DRAINS

LINE	STATION	STATION	LOC	FT
-L-	39+50.00	57+50.00	LT/RT	1,800
-L-	67+00.00	75+10.00	LT/RT	810
-L-	20+00.00	27+44.00	LT	744
-L-	20+00.00	23+99.00	LT	399
	CONTINGENCY			1,000
			TOTAL:	4,753
			SAY:	**4,760**

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	Station	Station	Aggregate Type* ASU/AST	Aggregate Thickness INCHES	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Soil Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
CONTINGENCY							5,300		
CONTINGENCY			ASU		300	600			
			TOTAL CY/TONS/SY:		300	600	5,300		

***ASU = Aggregate Subgrade**
***AST = Aggregate Stabilization**