PROJECT REFERENCE NO.	SHEET NO.
B-4741	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	12+50	14+00	LT	315
4	-L-	14+00	15+50	RT	265
4	-L-	17+50	19+00	LT	105
4	-DRW1A-	10+75	11+25	RT	115
4	-DRW2-	11+75	12+00	RT	40
				SUBTOTAL	840
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					10000
				TOTAL	10840
				SAY	10900

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	15+50	16+00	LT	170
4	-L-	17+00	17+50	LT	125
4	-L-	16+00	17+00	RT	115
5	-L-	25+00	27+50	RT	270
5	-L-	22+50	23+50	LT	55
				SUBTOTAL	735
		ADDITIONAL PSRM TO BE INSTALLED			0
				TOTAL	735
				SAY	750