STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
B-4953	X-1

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+00.00	0	0
14+25.00	32	0
14+50.00	63	0
14+75.00	61	0
15+00.00	64	0
15+25.00	48	0
15+50.00	24	2
15+65.88	12	2
16+38.13	0	0
16+50.00	9	1
16+75.00	30	1
17+00.00	35	0
17+25.00	31	0
17+50.00	17	0

Station DRV1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+25.00	53	0
10+50.00	59	0
10+60.00	5	0

Station DRV2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+25.00	14	0
10+50.00	40	0
10+62.70	27	0

Station DRV2A	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+25.00	1	7
10+37.21	1	6