TIP NO.	SHEET NO.
R-4463AA	PMP-2

APPROVED: DocuSigned by: Ayman Alqudwah F32AC5CAF965472...

DATE: 9/23/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 028387 ENGINEER AYMAN I. ALQUDWAH

FINAL PAVEMENT MARKING SCHEDULE

PAVEMENT MARKINGS

THERMOPLASTIC(4 IN., 90 MILS)

TA	WHITE EDGELINE
TB	YELLOW EDGELINE

THERMOPLASTIC(4 IN., 120 MILS)

T8	2 FT.-6 FT./SP WHITE MINISKIP
TC	WHITE SKIP LINE
TD	3 FT.-9 FT./SP WHITE MINISKIP
TE	WHITE SOLID LANE LINE
TI	YELLOW DOUBLE CENTER

THERMOPLASTIC(8 IN., 90 MILS)

TO	WHITE DIAGONAL
TP	YELLOW DIAGONAL

THERMOPLASTIC(24 IN., 120 MILS)

T2	WHITE STOPBAR

THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)

UA	LEFT TURN ARROW
UB	RIGHT TURN ARROW
UC	STRAIGHT ARROW
UN	24″ YIELD LINE TRIANGLE

THERMOPLASTIC PAVEMENT MARKING SYMBOLS (120 MILS)

UI	ALPHANUMERIC CHAR.

COLD APPLIED PLASTIC

CB	YELLOW EDGELINE
CD	3 FT.-9 FT./SP WHITE MINISKIP

FINAL PAVEMENT MARKERS SCHEDULE

MARKERS

PERMANENT RAISED MARKERS

MA	YELLOW & YELLOW
MB	CRYSTAL & RED

SNOWPLOWABLE MARKERS

MF	CRYSTAL & RED

PAVEMENT MARKING SCHEDULE

9/8/2014
R:\Projects-R\R4463AA\Traffic\Signing\CADD\Pmp\r4463aa_pmp_title.dgn
User:mcatron