PROJ. REFERENCE NO.	SHEET NO.
B-5119	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

NOTE: APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, REMOVAL OF EXISTING PAVEMENT, AND BREAKING OF ASPHALT PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING."

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+45.00	0	0
16+50.00	0	0
17+00.00	5	0
17+50.00	10	3
18+00.00	9	9
18+50.00	7	13
19+00.00	6	18
19+50.00	10	18
20+00.00	24	10
20+50.00	43	2
21+00.00	77	0
21+50.00	104	1
22+00.00	96	9
22+50.00	79	11
23+00.00	61	12
23+50.00	42	35
24+00.00	34	115
24+50.00	27	232
25+00.00	17	594
25+28.00	3	400

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
27+27.75	0	0
27+50.00	0	135
28+00.00	0	655
28+50.00	0	743
29+00.00	0	596
29+50.00	0	445
30+00.00	0	324
30+50.00	0	261
31+00.00	0	226
31+50.00	0	141
32+00.00	0	65
32+50.00	0	40
33+00.00	0	12
33+50.00	0	0
34+00.00	0	0
34+50.00	0	0
35+00.00	0	0
35+50.00	0	0
36+00.00	0	0
36+50.00	0	0
37+00.00	0	0
37+50.00	0	0
37+61.50	0	0
38+00.00	4	2
38+50.00	12	4
39+00.00	7	1
39+50.00	0	0
39+66.00	0	0

Station -RP-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
2+09.24	0	0
2+20.79	1	2
2+70.79	6	10
3+20.78	7	9
3+70.82	9	7
4+20.50	7	7
4+70.06	2	66
5+19.32	0	134
5+68.38	0	195
6+17.39	0	320
6+66.52	0	483
7+20.00	0	602
7+70.00	0	579
8+20.00	0	682
8+70.00	0	821
9+20.00	0	941
9+72.00	0	998
10+25.00	0	990
10+78.00	0	1128
11+00.00	0	555
11+31.50	0	775
11+76.50	0	871

Station -RP-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+83.00	0	0
13+01.00	0	489
13+50.00	0	965
14+00.00	0	335
14+50.00	0	304
15+00.00	1	175
15+50.00	3	52
16+00.00	3	65
16+50.00	3	75
17+00.00	5	55
17+50.00	9	28
18+00.00	7	6
18+50.00	2	1
19+00.00	3	7
19+50.00	4	16
20+00.00	4	18
20+50.00	3	17
21+00.00	3	13
21+50.00	7	6
22+00.00	6	3
22+20.00	1	1

Station -DET1-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
1+32.80	0	0
1+50.00	4	4
1+83.44	2	18
2+00.00	1	11
2+50.00	2	32
3+00.00	3	29
3+50.00	4	27
4+00.00	7	14
4+50.00	5	2
4+70.00	0	0

Station -DET2-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
0+00.00	0	0
0+50.00	0	380
1+00.00	0	271
1+50.00	0	217
2+00.00	0	134
2+50.00	0	74
3+00.00	0	50
3+50.00	1	54
3+76.55	1	21
4+00.00	2	13
4+50.00	4	15
5+00.00	1	0
5+50.00	1	2
5+72.38	1	4
6+00.00	2	7
6+50.00	33	9
7+00.00	54	3
7+50.00	46	2
7+71.46	10	0

Station -DET3-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
1+63.51	0	0
1+86.95	1	22
2+36.31	3	54
2+85.66	2	49
3+50.00	7	26
4+00.00	6	1
4+50.00	2	2
5+00.00	0	1