DocuSign Envelope ID: B90AB89D-86B4-4A96-AB7A-BF2296D38917

TIP NO.	SHEET NO.
U-3615B	SIGN-2

APPROVED: DocuSigned by: Betsy L. Watson 35E67BB34F8743F...

DATE: 10/1/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 29449 ENGINEER BETSY L. WATSON

Stantec
Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27606
Tel. (919) 851-6866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672

401 QUANTITY REQ'D 25

30 X 36
R2-1

ONE "U" POST PER SIGN

402 QUANTITY REQ'D 2

24 X 30
R2-1

ONE "U" POST PER SIGN

403 QUANTITY REQ'D 1

24 X 30
R2-1

ONE "U" POST PER SIGN

404 QUANTITY REQ'D 1

24 X 30
R2-1

ONE "U" POST PER SIGN

405 QUANTITY REQ'D 2

24 X 30
R2-1

ONE "U" POST PER SIGN

406 QUANTITY REQ'D 1

36 X 36
W4-6

ONE "U" POST PER SIGN

407 QUANTITY REQ'D 4

36 X 36
R5-1

MOUNT BEHIND SIGN 415
IN 1 INSTALLATION

ONE "U" POST PER SIGN

408 QUANTITY REQ'D 24

24 X 30
R4-7

ONE "U" POST PER SIGN

409 QUANTITY REQ'D 12

18 X 18
OM1-3

MOUNT BELOW SIGN 408
IN 12 INSTALLATIONS

410 QUANTITY REQ'D 5

36 X 36
R3-7R

ONE "U" POST PER SIGN

411 QUANTITY REQ'D 9

18 X 30
R4-7c

ONE "U" POST PER SIGN

412 QUANTITY REQ'D 6

36 X 36
R3-4

ONE "U" POST PER SIGN

413 QUANTITY REQ'D 6

54 X 18
R6-1L

TWO "U" POSTS PER SIGN

414 QUANTITY REQ'D 14



54 X 18
R6-1R

TWO "U" POSTS PER SIGN

415 QUANTITY REQ'D 24

36 X 36
R1-1

ONE "U" POST PER SIGN

416 QUANTITY REQ'D 18

24 X 24
R3-2

MOUNT BELOW SIGN 415
IN 18 INSTALLATIONS

417 QUANTITY REQ'D 3



48 X 24
W1-7

TWO "U" POSTS PER SIGN

418 QUANTITY REQ'D 1



36 X 36
W6-3

ONE "U" POST PER SIGN

419 QUANTITY REQ'D 7

30 X 30
W14-2

ONE "U" POST PER SIGN

420 QUANTITY REQ'D 1

36 X 36
R3-7L

ONE "U" POST PER SIGN

TYPE 'E' SIGNS

9/29/2014
U:\U3615B\Traffic\Signing\CADD\Signing_Layout_Plans\U-3615B_sign_I-3.dgn
rhennein