DocuSign Envelope ID: B90AB89D-86B4-4A96-AB7A-BF2296D38917

T.I.P.: U-3615B

CONTRACT: C203256

TIP NO.	SHEET NO.
U-3615B	SIGN-1

APPROVED: DocuSigned by: Betsy L. Watson 35E67B834F8743F...

DATE: 10/1/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 29449 ENGINEER BETSY L. WATSON

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
GUILFORD COUNTY

LOCATION: HIGH POINT – SR 1820 (SKEET CLUB RD) FROM EAST OF SR 1818 (JOHNSON ST) TO WEST OF NC 68 (EASTCHESTER DR)

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.50	ARROWS AND SHIELDS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

GENERAL NOTES

- SIGNS FURNISHED BY STATE.
- ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4072000000	903	SUPPORTS, 3-LB STEEL U-CHANNEL	2805	L.F.
4096000000	904	SIGN ERECTION, TYPE D	10	EA.
4102000000	904	SIGN ERECTION, TYPE E	166	EA.
4108000000	904	SIGN ERECTION, TYPE F	10	EA.
4116100000	904	SIGN ERECTION, RELOCATE, TYPE E	6	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	109	EA.
4192000000	907	DISPOSAL OF SUPPORT, U-CHANNEL	5	EA.
4238000000	907	DISPOSAL OF SIGN, D,E,OR F	5	EA.

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2-2A	E AND F SHEETS
SIGN-3-3A	SIGN DESIGNS
SIGN-4-10	SIGN DETAIL SHEETS

PLAN REVIEWED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

SUSAN KUNZ — SIGNING & DELINEATION REGIONAL ENGINEER

JAMES HAMBRIGHT — SIGNING & DELINEATION DESIGN ENGINEER

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION SIGNING AND DELINEATION UNIT

PLAN PREPARED BY:

BETSY L. WATSON, P.E. — TRAFFIC ENGINEER

ROSI R. HENNEIN — TRANSPORTATION TECHNICIAN

Stantec

Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27606
Tel. (919) 851-6866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672

9/29/2014
U:\U3615B\Traffic\Signing\CADD\Signing_Layout_Plans\U-3615B_sign_1-3.dgn
rhennein