TIP NO.	SHEET NO.
B-4565	SIGN-1

APPROVED: DocuSigned by: Ayman Alqudwah F32AC5CAF965472...

DATE: 10/21/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 028387 ENGINEER AYMAN I. ALQUDWAH

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
LENOIR COUNTY

LOCATION: BRIDGES 42,43,26 AND 28 OVER THE NEUSE RIVER AND OVERFLOW

ON US 70/258 BUSINESS (SOUTH QUEEN STREET)

T.I.P.: B-4565

CONTRACT: C203533

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.10	TYPE 'A' SIGNS
901.50	ARROWS AND SHIELDS
901.70	SIGN STRINGERS AND SUPPORT SPACING
901.80	SIGN MOUNTING DETAILS - FOR TYPE A AND TYPE B SIGNS
903.10	GROUND MOUNTED SIGN SUPPORTS
903.20	WOOD SIGN SUPPORTS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS

GENERAL NOTES

. SIGNS FURNISHED BY STATE

. ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO WOOD POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER

. ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.

. THE BACKGROUND FOR TYPE D, E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

. SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

. DO NOT BEGIN FABRICATION FOR TYPES A & B SIGNS MOUNTED ON OVERHEAD STRUCTURES OR STEEL SUPPORTS UNTIL "S" DIMENSIONS HAVE BEEN FIELD VERIFIED.

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4048000000	902	REINFORCED CONCRETE SIGN FOUNDATION	1	C.Y.
4060000000	903	SUPPORTS, BREAKAWAY STEEL BEAM	388	LB.
4082000000	903	SUPPORTS, WOOD	410	L.F.
4096000000	904	SIGN ERECTION, TYPE D	4	EA.
4102000000	904	SIGN ERECTION, TYPE E	11	EA.
4108000000	904	SIGN ERECTION, TYPE F	5	EA.
4110000000	904	SIGN ERECTION, TYPE B (GROUND MOUNTED)	1	EA.
4158000000	907	DISPOSAL OF SIGN SYSTEM, WOOD	27	EA.

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2	SIGN DESIGNS
SIGN-2A	TYPE "A" GROUND MOUNTED SIGNS
SIGN-2B	GROUND MOUNTED SIGN SUPPORTS
SIGN-3-3A	E AND F SHEETS
SIGN-4-5	SIGNING PLAN SHEETS

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

A. I. ALQUDWAH, P.E. SIGNING & DELINEATION REGIONAL ENGINEER

BARRY NOWLIN SIGNING & DELINEATION PROJECT DESIGN TECHNICIAN

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

10/21/2014
R:\Traffic\Signing\CADD\Signing Layout Plans\B-4565_Engseed 6-11-12.dgn
User:bnowlin