PROJ. REFERENCE NO.	SHEET NO.
B-4565	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0
11+09.00	1	0
11+50.00	17	2
12+00.00	27	2
12+50.00	27	2
13+00.00	28	2
13+50.00	31	9
14+00.00	30	22
14+50.00	21	35
15+00.00	17	84
15+50.00	64	165
16+00.00	127	244
16+25.00	35	81
16+50.00	0	96
17+00.00	0	481
17+50.00	0	543
17+74.98	0	360
17+75.00	0	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
22+60.00	0	0
22+60.02	0	0
23+00.00	0	626
23+50.00	0	594
24+00.00	0	424
24+50.00	0	295
25+00.00	0	237
25+50.00	0	195
26+00.00	0	185
26+50.00	0	192
27+00.00	0	219
27+50.00	0	250
28+00.00	0	308
28+26.42	0	189

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
30+87.58	0	0
31+50.00	0	1026
32+00.00	0	834
32+50.00	6	788
33+00.00	15	512
33+50.00	22	240
34+00.00	22	167
34+50.00	22	161

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+51.23	0	0
12+75.00	7	7
13+00.00	14	0
13+25.00	21	0
13+50.00	34	0
13+75.00	34	0
14+00.00	22	0
14+25.00	11	0
14+50.00	17	0
14+75.00	32	0
15+00.00	24	0

Station Drive	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+85.75	0	0
13+00.00	9	0
13+50.00	30	0
14+00.00	26	0
14+50.00	24	0
14+86.45	16	0

Station L (DDE)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+00.00	0	0
17+50.00	42	0
17+60.00	10	0

CROSS-SECTION INDEX OF SHEETS

CHAIN	SHEETS
-L-	X-1 THRU X-8
-Y1-	X-9 THRU X-10
-DRIVE-	X-11