PROJECT REFERENCE NO.	SHEET NO.
B-5113	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	10+40	11+00	RT	45
4	-L-	11+00	12+50	RT	105
			SUBTOTAL		150
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					4,250
			TOTAL		4,400
			SAY		4,400

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	11+50	14+00	LT	175
			SUBTOTAL		175
ADDITIONAL PSRM TO BE INSTALLED					175
			TOTAL		175
			SAY		175