PROJ. REFERENCE NO.	SHEET NO.
B-5150	X-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station Det	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+37.47	0	0	16+70.00	2	9
11+50.00	11	10			
11+75.00	29	28			
12+00.00	19	21			
12+25.00	10	6			
12+50.00	18	0			
12+75.00	29	0			
13+00.00	30	0			
13+25.00	13	25			
13+50.00	0	72			
13+75.00	0	126			
14+00.00	0	186			
14+25.00	0	249			
14+50.00	0	327			
14+75.00	0	395			
15+00.00	0	428			
15+25.00	0	468			
15+50.00	0	477			
15+75.00	0	435			
16+00.00	0	369			
16+25.00	0	250			
16+50.00	46	125			
16+75.00	164	50			
17+00.00	216	25			
17+25.00	152	16			
17+50.00	83	9			
17+75.00	31	4			
18+00.00	4	2			
18+25.00	3	2			
18+50.00	3	3			
18+50.00	0	0			

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+00.00	0	0
12+25.00	2	1
12+50.00	3	1
12+75.00	2	0
13+00.00	7	3
13+25.00	12	9
13+50.00	12	24
13+75.00	18	37
14+00.00	24	40
14+25.00	18	173
14+50.00	7	475
15+00.00	3	1168
15+25.00	10	304
15+50.00	21	73
15+75.00	12	63
16+00.00	3	60
16+25.00	3	46
16+50.00	4	31