PROJECT REFERENCE NO.	SHEET NO.
B-5151	EC-03
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	15+00	18+00	RT	420
4	-L-	16+00	18+00	LT	280
				SUBTOTAL	700
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					300
				TOTAL	1000
				SAY	1000

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	11+00	13+50	RT	405
				SUBTOTAL	405
		ADDITIONAL PSRM TO BE INSTALLED			100
				TOTAL	505
				SAY	550