COMPUTED BY:	D. Petry	DATE:	1/23/2014
CHECKED BY:		DATE:	

PROJECT NO.	SHEET NO.
W-5107	3D-6

RD248621

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

Note: Invert Elevations indicated are for Bid Purposes only and shall not be used for project construction stakeout.
See "Standard Specifications For Roads and Structures, Section 300-5".

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48 INCHES & UNDER)

STATION / SIZE / THICKNESS OR GAUGE	LOCATION (LT, RT, OR CL)'	STRUCTURE NO. FROM	STRUCTURE NO. TO	TOP ELEVATION	INVERT ELEVATION	INVERT ELEVATION	SLOPE CRITICAL
-L- 134+65	LT.	1204	1201		149.30	149.23	
-L- 136+11	CL	1206					
SHEET TOTALS							
PROJECT TOTALS							

STATION	SIDE DRAIN PIPE (RCP, CSP, CAAP, HDPE, or PVC) 12"	15"	18"	24"	30"	36"	42"	48"	DO NOT USE RCP	DO NOT USE CSP	DO NOT USE CAAP	DO NOT USE HDPE
-L- 134+65												
-L- 136+11												
SHEET TOTALS												
PROJECT TOTALS		448		88	36							

STATION	C.S. PIPE 12" (.064)	15" (.064)	18" (.064)	24" (.064)	30" (.079)	36" (.079)	42" (.109)	48" (.109)
-L- 134+65								
-L- 136+11								
SHEET TOTALS								
PROJECT TOTALS		680						

STATION	R.C. PIPE CLASS III 12"	15"	18"	24"	30"	36"	42"	48"	R.C. PIPE CLASS IV 12"	15"	18"	24"	30"	36"	42"	48"
-L- 134+65						8										
-L- 136+11																
SHEET TOTALS						8										
PROJECT TOTALS		848	340	112	104	224				2504	652	364	220			

STATION		15" WELDED STEEL PIPE, 0.500" THK. (TRENCHLESS INSTALLATION)	30" WELDED STEEL PIPE, 0.500" THK. (TRENCHLESS INSTALLATION)	36" WELDED STEEL PIPE, 0.500" THK. (TRENCHLESS INSTALLATION)			ENDWALLS STD. 838.01 838.11 OR STD. 838.80 (UNLESS NOTED OTHERWISE) CU. YARDS R.C.P.	C.S.P.	QUANTITIES FOR DRAINAGE STRUCTURES PER EACH (0' THRU 5.0')	*TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. 'A' + (1.3 X COL.'B') LIN. FT. A 5.0' THRU 10.0'	B 10.0' AND ABOVE	C.B. STD. 840.01 OR STD. 840.02	FRAME, GRATES, AND HOOD STANDARD 840.03 TYPE OF GRATE E	F	G	CONCRETE TRANSITIONAL SECTION DROP INLET	CATCH BASIN
-L- 134+65																	
-L- 136+11																	
SHEET TOTALS																	
PROJECT TOTALS		368	192	180				2.8	82	23.03	4	9	4	1	4	21	
							SAY	3		28							

STATION	D.I. STD. 840.14 OR STD. 840.15	D.I. FRAME WITH TWO GRATES STD. 840.16	G.D.I. TYPE "A" STD. 840.17 OR 840.26	G.D.I. TYPE "B" STD. 840.18 OR 840.27	G.D.I. TYPE "D" STD. 840.19 OR 840.28	G.D.I. FRAME WITH GRATE STD. 840.20	G.D.I. FRAME WITH TWO GRATES STD. 840.22	G.D.I. (N.S.) FRAME WITH GRATE STD. 840.24	G.D.I. (N.S.) FRAME WITH TWO GRATES STD. 840.24	J.B. STD. 840.31 OR 840.32	FLOWABLE FILL, CY.	T.B.D.I. STD. 840.36	STEEL GRATES AND FRAME STD. 840.37	REPAIR EX. DI SEE SPECIAL PROVISIONS
-L- 134+65														
-L- 136+11											4			
SHEET TOTALS											4			
PROJECT TOTALS			1	14	1		16				58	57	57	8

STATION	CS PIPE ELBOWS NO. & SIZE	CONC. & BRICK PIPE PLUG, C.Y. STD. 840.71	CONC. COLLARS CL. "B" C.Y. STD. 840.72	PIPE REMOVAL LIN. FT.	REMARKS
-L- 134+65					
-L- 136+11			0.262	17	REMOVE DI & 15" PIPE
SHEET TOTALS			0.262	17	
PROJECT TOTALS	20 @ 15"	*1	3.843	1099	*CONTIGENCY
	SAY	1	4		

ABBREVIATIONS

C.B.	CATCH BASIN
N.D.I.	NARROW DROP INLET
D.I.	DROP INLET
G.D.I.	GRATED DROP INLET
G.D.I.(N.S.)	(NARROW SLOT)
J.B.	JUNCTION BOX
M.H.	MANHOLE
T.B.D.I.	TRAFFIC BEARING DROP INLET
T.B.J.B.	TRAFFIC BEARING JUNCTION BOX