PROJ. REFERENCE NO.	SHEET NO.
W-5107	X-1D

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station -Y6- LPB (CON'T)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+00.00	664	496
13+50.00	282	1303
14+00.00	143	1871
14+50.00	60	2169
15+00.00	25	2226
15+50.00	23	2252
16+00.00	19	2317
16+50.00	18	2439
17+00.00	9	2482
17+50.00	0	2477
18+00.00	0	2410
18+50.00	0	1832
19+00.00	29	1125
19+50.00	48	846
20+00.00	31	914
20+50.00	20	1295

Station -Y6LPC-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+78.00	0	0
11+00.00	169	5
11+50.00	406	8
11+75.00	178	0
12+20.00	301	0
12+50.00	204	0
13+00.00	235	3
13+50.00	130	34
14+00.00	77	121
14+50.00	50	237
15+00.00	36	307
15+50.00	26	333
16+00.00	29	333
16+50.00	35	297
17+00.00	94	223
17+50.00	283	127
18+00.00	511	65
18+50.00	361	57

Station -Y6LPCA-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+28.67	0	0
11+60.00	105	0

Station -SR1-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
10+96.44	0	245
11+50.44	0	438
12+09.47	0	607
12+61.40	0	762
13+09.65	0	936
13+55.58	0	1254
14+10.79	0	1690
14+63.41	0	1604
15+19.45	0	1721

Station -SR1- (CON'T)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+73.77	0	1423
16+07.00	0	754
16+52.20	0	797
16+92.81	35	394
17+35.60	65	114
17+75.71	68	3
18+05.00	70	0
18+40.00	71	0

Station -SR2-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+65.00	0	0
11+00.00	19	104
11+39.88	20	159
11+80.91	19	230
12+20.00	19	304
12+63.28	11	424
13+24.44	0	784
14+00.00	0	0
15+00.00	0	0
16+00.00	0	0
20+17.02	0	0
20+68.92	109	199
20+97.78	112	0
21+15.49	70	0
21+57.89	94	0
21+98.83	31	15

Station -SR3-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+75.00	0	0
11+00.00	8	42
11+50.00	14	34
11+86.21	38	4

Station -SR4-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+30.00	0	0
10+63.78	132	1
11+13.00	303	19
11+59.00	246	34

Station -DW1-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+25.00	5	0
10+50.00	10	0
10+75.00	9	0
11+00.00	7	0
11+25.00	6	0
11+50.00	5	1
11+75.00	2	4
12+00.00	0	10
12+25.00	0	33

Station -DW2-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+25.00	4	0
10+50.00	5	1
10+75.00	3	2
11+00.00	2	2
11+25.00	3	1
11+50.00	6	1
11+75.00	4	10
11+83.75	0	7

Station -DW5-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
10+75.00	1	26

Station -DW7-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+25.00	0	0
10+50.00	72	1
11+00.00	143	20
11+50.00	54	20

Station -Y1LPC-	Undcut. (cu. yd.)
14+00.00	0
14+50.00	170
14+88.86	200
15+25.00	300
15+74.00	330

Station -Y1RPC-	Undcut. (cu. yd.)
15+05.00	0
15+55.00	0
16+00.00	30
16+50.00	100
17+00.00	90
17+50.00	100
18+00.00	120
18+50.00	130
19+00.00	150
19+50.00	270
20+00.00	350
20+50.00	300
21+00.00	360

Station -Y6LPC-	Undcut. (cu. yd.)
10+78.00	70
11+00.00	40
11+50.00	110
11+75.00	50
12+20.00	120
12+50.00	120
13+00.00	170
13+50.00	160
14+00.00	120
14+50.00	40

Station -Y6LPCA-	Undcut. (cu. yd.)
11+28.67	300
11+60.00	200