PROJ. REFERENCE NO.	SHEET NO.
W-5107	X-1C

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

STATE OF NORTH CAROLINA

DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station -L- MEDIAN (CON'T)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
62+00.00	4	4
62+50.00	3	4
63+00.00	3	4
63+50.00	7	2
65+50.00	49	8
66+00.00	9	6
66+50.00	7	6
67+00.00	13	5
67+50.00	14	7
68+00.00	15	5
Station -L- MEDIAN	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
78+50.00	0	0
79+00.00	9	2
79+50.00	14	2
80+00.00	16	2
80+50.00	15	2
81+00.00	13	1
81+50.00	10	1
82+00.00	6	0
82+50.00	4	0
83+00.00	8	0
83+50.00	12	1
84+00.00	13	2
84+50.00	15	2
85+00.00	16	2
85+50.00	16	3
86+00.00	13	2
86+50.00	13	1
87+00.00	13	1
87+50.00	6	3
Station -L- MEDIAN	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
93+00.00	0	0
93+50.00	9	9
94+00.00	10	5
94+50.00	5	6
95+00.00	4	4
95+50.00	4	5
96+00.00	6	5
96+50.00	8	6
97+00.00	11	3
97+50.00	14	0
98+00.00	13	2
98+50.00	11	6
99+00.00	11	7
99+50.00	12	9
100+00.00	13	10
100+50.00	13	9
101+00.00	10	7
101+50.00	6	5
102+00.00	2	10

Station -L- MEDIAN (CON'T)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
102+50.00	0	15
103+00.00	0	16
103+50.00	0	15
104+00.00	0	15
104+50.00	0	15
105+00.00	0	16
105+50.00	0	18
106+00.00	0	17
106+50.00	0	13
107+00.00	0	13
107+50.00	0	16
108+00.00	0	18
108+50.00	0	14
109+00.00	0	10
109+44.40	0	10
109+95.00	0	13
110+45.10	0	14
110+70.00	0	7
111+15.40	0	15
111+50.00	0	13
112+00.00	0	17
112+50.00	3	15
113+00.00	5	12
113+50.00	6	10
114+00.00	5	10
114+50.00	4	11
115+00.00	5	12
115+50.00	3	6
116+00.00	0	0
116+50.00	0	0
117+00.00	4	1
117+50.00	6	1
117+75.00	3	1
118+00.00	3	1
118+50.00	5	1
119+00.00	5	2
119+50.00	4	3
120+00.00	2	3
120+50.00	1	5
121+00.00	1	6
121+50.00	3	3
Station -L- MEDIAN	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
127+50.00	0	0
128+00.00	6	6
128+50.00	7	5
129+00.00	8	4
129+50.00	7	3
130+00.00	8	1
130+50.00	10	0
131+00.00	13	0
131+50.00	17	0
132+00.00	18	0

Station -L-MEDIAN (CON'T)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
132+50.00	17	0
133+00.00	15	0
133+50.00	12	0
134+00.00	10	0
134+50.00	7	7
135+00.00	4	12
135+50.00	5	9
136+00.00	6	10
136+50.00	6	10
137+00.00	4	7
137+50.00	2	5
138+00.00	2	6
138+50.00	1	8
Station -Y1- BEGIN	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
13+70.00	0	0
14+00.00	38	2
14+50.00	148	8
15+00.00	181	12
15+50.00	206	11
16+00.00	219	8
16+50.00	211	9
17+00.00	210	10
17+50.00	217	10
18+00.00	243	8
18+50.00	288	4
19+00.00	339	8
19+25.00	165	10
20+60.00	581	792
21+00.00	337	626
21+50.00	739	1315
22+00.00	749	1843
22+50.00	360	2360
23+00.00	0	3146
23+49.99	0	4156
24+00.00	0	5299
24+50.00	0	6894
25+00.00	0	8363
25+50.00	0	9596
25+99.99	0	8986
26+49.99	0	7535
27+00.00	0	6920
27+50.00	0	6251
27+71.80	0	2647
Station -Y1- END	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
30+69.80	0	0
30+75.00	0	408
31+00.00	0	2120
31+50.00	0	4621
32+00.00	0	4430
32+50.00	0	3798

Station -Y1- END (CON'T)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
33+00.00	0	3050
33+50.00	0	2375
34+00.00	0	1806
34+50.00	79	1340
35+00.00	82	934
36+70.00	175	1441
37+00.00	70	66
37+50.00	141	89
38+00.00	133	74
38+50.00	108	68
39+00.00	97	65
39+50.00	129	62
40+00.00	129	63
40+50.00	76	52
41+00.00	51	30
41+50.00	46	19
42+00.00	46	11
42+10.00	5	1
Station -Y1LPA-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
12+00.00	0	0
12+50.00	210	28
12+98.00	253	4
13+50.00	287	2
Station -Y1LPC-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
14+00.00	0	0
14+50.00	36	1240
14+88.86	84	415
15+25.00	74	65
15+74.00	77	21
Station -Y1RPA-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
13+51.58	0	0
13+97.00	134	81
14+45.00	181	101
14+93.00	202	69
15+40.00	243	53
15+90.00	302	120
16+37.00	368	119
16+83.00	469	66
17+36.00	447	45
17+95.00	492	26
18+50.00	554	21
19+00.00	453	29
Station -Y1RPC-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
15+05.00	0	0
15+55.00	549	234
16+00.00	518	244

Station -Y1RPC- (CON'T)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+50.00	583	210
17+00.00	631	75
17+50.00	710	4
18+00.00	772	0
18+50.00	793	0
19+00.00	864	0
19+50.00	1054	0
20+00.00	1244	0
20+50.00	1699	0
21+00.00	1485	0
Station -Y1RPD-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
13+96.00	0	0
14+55.00	124	45
15+00.00	66	170
15+40.00	87	328
15+70.00	87	389
16+10.00	134	799
16+60.00	89	1322
16+95.00	0	1091
17+25.00	0	1167
17+63.00	0	1821
18+00.00	0	1984
18+50.00	0	3025
19+00.00	0	3380
19+52.00	0	3682
20+00.02	0	2968
Station -Y2-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
11+50.00	0	0
12+00.00	1	2
12+50.00	1	11
13+00.00	4	45
13+50.00	12	142
14+00.00	22	306
14+50.00	28	450
Station -Y3-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
13+30.00	0	0
13+50.00	3	10
14+00.00	17	72
14+50.00	33	104
15+00.00	56	116
15+50.00	117	219
Station -Y6- BEGIN	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
12+69.00	0	0
13+00.00	36	1
13+50.00	111	3
14+00.00	97	7

Station -Y6- BEGIN (CON'T)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+50.00	149	19
15+00.00	216	18
15+50.00	158	13
16+00.00	106	26
16+37.82	64	54
17+50.00	175	736
18+00.00	265	665
18+50.00	459	869
19+00.00	246	1080
19+25.00	0	667
19+50.00	0	775
20+00.00	0	1793
20+50.00	0	2108
21+00.00	0	2382
21+50.00	0	3110
22+00.00	0	4094
22+50.00	60	4300
Station -Y6- END	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
24+56.45	0	0
24+70.00	0	1238
25+00.00	0	3009
25+50.00	0	5583
26+00.00	0	5827
26+50.00	0	5525
27+00.00	0	4647
27+50.00	0	3794
28+00.00	0	3129
28+50.00	0	2663
29+50.00	0	4000
30+00.00	11	1239
30+50.00	39	809
31+00.00	51	551
31+50.00	27	440
32+00.00	15	292
32+50.00	34	123
33+00.00	66	55
33+50.00	108	14
34+00.00	138	4
34+25.00	37	0
Station -Y6LPBA-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
10+75.00	0	0
11+30.00	552	25
Station -Y6LPB-	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
11+00.00	0	0
11+30.00	637	10
11+80.11	1464	0
12+00.00	623	0
12+50.00	1206	10