PROJECT NO.	SHEET NO.	TOTAL NO.
12CR.10551.13 12CR.20551.21	8	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1 .5" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	MILLED RUMBLE STRIPS (STD. 665.01) LF
12cr.10551.13	Lincoln	1	US 321 (NB & SB LANES)	FROM A PT. 2000' N. OF NC 27 RAMPS TO CATAWBA CO	3,4	4	NO	NO	5.63	56	1,250		16.50	201,600	1,250				17,807	1,250	1,132	1,850	119,250
TOTAL FOR PROJ NO. 12cr.10551.13									**5.63**		**1,250**		**16.50**	**201,600**	**1,250**				**17,807**	**1,250**	**1,132**	**1,850**	**119,250**
12cr.20551.21	Lincoln	2	SR 1389 (FAIRFIELD FOREST)	FROM NC 16 TO SR 1456	1	2	NO	NO	1.47	20	150	60	2.94		450		1,531	100			98	300	
12cr.20551.21	Lincoln	3	SR 1321 (HILL ROAD)	FROM NC 27 TO 1001	1,2	2	NO	NO	2.53	20	250	100	5.06		450	500	2,541	250			241	750	
12cr.20551.21	Lincoln	4	SR 1323 (KEENER RD)	FROM SR 1001 TO SR 1321	1	2	NO	NO	1	18	100	40	2.00		400		983	200			72	200	
12cr.20551.21	Lincoln	5	SR 1456 (LAKESHORE RD S.)	FROM NC 16 TO SR 1389	1	2	NO	NO	3.82	18	375	100	7.64		400		3,753	500			258	900	
TOTAL FOR PROJ NO. 12cr.20551.21									**8.82**		**875**	**300**	**17.64**		**1,700**	**500**	**8,808**	**1,050**			**669**	**2,150**	
GRAND TOTAL									**14.45**		**2,125**	**300**	**34.14**	**201,600**	**2,950**	**500**	**8,808**	**1,050**	**17,807**	**1,250**	**1,801**	**4,000**	**119,250**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	4457000000-N TEMP TRAFFIC CONTROL LS	4510000000-N LAW ENFORCE-MENT HR	4688000000-E 6" X 90M WHITE THERMO LF	4688000000-E 6" X 90M YELLOW THERMO LF	4690000000-E 6" X 120M WHITE THERMO LF	4697000000-E 8" X 120 M WHITE THERMO LF	4700000000-E 12" X 90 M WHITE THERMO LF	4705000000-E 16" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO RXR 120 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4810000000-E 4" WHITE PAINT LF	4810000000-E 4" YELLOW PAINT LF	4815000000-E 6" WHITE PAINT LF	4815000000-E 6" YELLOW PAINT LF	4825000000-E 12" YELLOW PAINT LF	4905000000-N SNOW PLOWABLE MARKERS EA
12cr.10551.13	Lincoln	1	US 321 (NB & SB Lanes & Ramps)	FROM A PT. 2000' N. OF NC 27 RAMPS TO CATAWBA CO	3,4	4	5.63	56	566	1	100	67,500	66,500	17,500		2,650		30		6	6	12			85,000	66,500	2,650	890
TOTAL FOR PROJ NO. 12cr.10551.13							**5.63**		**566**	**1**	**100**	**67,500**	**66,500**	**17,500**		**2,650**		**30**		**6**	**6**	**12**			**85,000**	**66,500**	**2,650**	**890**
												134,000								**24**				**151,500**			
12cr.20551.21	Lincoln	2	SR 1389 (FAIRFIELD FOREST)	FROM NC 16 TO SR 1456	1	2	1.47	20	350	*					125			15					31,500	30,000				
12cr.20551.21	Lincoln	3	SR 1321 (HILL ROAD)	FROM NC 27 TO 1001	1,2	2	2.53	18	224	*							100	50	4				53,350	53,350				
12cr.20551.21	Lincoln	4	SR 1323 (KEENER RD)	FROM SR 1001 TO SR 1321	1	2	1	18	134	*													21,500	21,250				
12cr.20551.21	Lincoln	5	SR 1456 (LAKESHORE RD S.)	FROM NC 16 TO SR 1389	1	2	3.82	18	366	*													80,675	80,250				
TOTAL FOR PROJ NO. 12cr.20551.21							**8.82**		**1,074**	*					**125**		**100**	**65**	**4**				**187,025**	**184,850**				
																							371,875					
GRAND TOTAL							**14.45**		**1,640**	**1**	**100**	**67,500**	**66,500**	**17,500**	**125**	**2,650**	**100**	**95**	**4**	**6**	**6**	**12**	**187,025**	**184,850**			**2,650**	**890**
												134,000								**24**			**371,875**		**151,500**			