PROJECT NO.	SHEET NO.	TOTAL NO.
I-5372	4	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	MILLING ASPHALT PAVEMENT, 1-1/2" DEPTH SY	MILLING ASPHALT PAVEMENT, 0" TO 1 1/2" DEPTH SY	INCIDENTAL MILLING SY	ASPHALT CONC SURFACE COURSE, TYPE S9.5C TON	ASPHALT BINDER FOR PLANT MIX TON	MILLED RUMBLE STRIPS (ASPHALT CONCRETE) LF	GUARDRAIL ANCHOR UNITS, TYPE 350 EA	GUARDRAIL ANCHOR UNITS, TYPE M-350 EA	REMOVE & RESET EXISTING GUARDRAIL LF	SEEDING & MULCHING AC
46191.3.FS1	Madison	1	FUTURE I-26 EASTBOUND	FROM BRIDGE 550 OVER SR 1352 TO BUNCOMBE CL	1,2	2	MD	NO	NO	4.1	40	7.53	24,600	8,450	1,000	11,899	702	43,296	2.00	2.00	6,450.00	5.48
		2	FUTURE I-26 WESTBOUND	FROM BUNCOMBE CL TO BRIDGE 549 OVER SR 1352	1,2	2	MD	NO	NO	4.1	40	7.53	12,650	6,500	1,000	10,733	633	43,296	2.00	2.00	11,050.00	5.48
TOTAL FOR PROJ NO. 46191.3.FS1										**4.1**		**15.06**	**37,250**	**14,950**	**2,000**	**22,632**	**1,335**	**86,592**	**4.00**	**4.00**	**17,500.00**	**10.96**
GRAND TOTAL										**4.1**		**15.06**	**37,250**	**14,950**	**2,000**	**22,632**	**1,335**	**86,592**	**4.00**	**4.00**	**17,500.00**	**10.96**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-N LAW ENFORCEMENT HR	4725000000-E THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) MERGE ARROW EA	4847100000-E POLYUREA PAVEMENT MARKING LINES (6") WHITE (HIGHLY REFLECTIVE ELEMENTS) LF	4847100000-E POLYUREA PAVEMENT MARKING LINES (6") YELLOW (HIGHLY REFLECTIVE ELEMENTS) LF	4847120000-E POLYUREA PAVEMENT MARKING LINES (12") WHITE (HIGHLY REFLECTIVE ELEMENTS) LF	4905000000-N SNOWPLOWABLE PAVEMENT MARKERS EA
46191.3.FS1	Madison	1	FUTURE I-26 EASTBOUND	FROM BRIDGE 550 OVER SR 1352 TO BUNCOMBE CL	1,2	2	MD	4.1	40	350	1	82	6	28,200	21,648	2,000	475
		2	FUTURE I-26 WESTBOUND	FROM BUNCOMBE CL TO BRIDGE 549 OVER SR 1352	1,2	2	MD	4.1	40				6	27,800	21,648	2,900	565
TOTAL FOR PROJ NO. 46191.3.FS1								**4.1**		**350**	**1**	**82**	**12**	**56,000**	**43,296**	**4,900**	**1,040**
														99,296			
GRAND TOTAL								**4.1**		**350**	**1**	**82**	**12**	**56,000**	**43,296**	**4,900**	**1,040**
														99,296			