PROJECT REFERENCE NO.	SHEET NO.
W-5316	SIGN-1

APPROVED: DocuSigned by: Ronald W. King 0695D7A9577C4DC...

DATE: 12/8/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 022959 ENGINEER RONALD W. KING

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
ROWAN COUNTY

LOCATION: US 52 AT THE INTERSECTION WITH SR 2342 (GOLD KNOB ROAD), SR 2319 (CRESCENT ROAD), AND SR 2382 (ANTHONY ROAD)

T.I.P.: W-5316

CONTRACT: C203561

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS
1264.02	OBJECT MARKERS INSTALLATION

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4102000000	904	SIGN ERECTION, TYPE E	11	EA.
4096000000	904	SIGN ERECTION, TYPE D	2	EA.
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	205	L.F.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8	EA.

GENERAL NOTES

- SIGNS FURNISHED BY STATE
- ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

TYPE "E" SIGNS

401 QUANTITY REQ'D 2

36" X 36"
R1-1

ONE "U" POST PER SIGN

402 QUANTITY REQ'D 2



30" X 30"
W2-1

ONE "U" POSTS PER SIGN

403 QUANTITY REQ'D 2

18" X 18"
W13-1P

MOUNT BELOW SIGN 402

404 QUANTITY REQ'D 2

24" X 30"
R2-1

ONE "U" POST PER SIGN

405 QUANTITY REQ'D 1

24" X 30"
R2-1

ONE "U" POST PER SIGN

406 QUANTITY REQ'D 1

30" X 30"
W14-1

ONE "U" POST PER SIGN

407 QUANTITY REQ'D 3

18" X 18"
OM4-3

ONE "U" POST PER SIGN

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

R. B. ROACH, PE SIGNING & DELINEATION REGIONAL ENGINEER

A. H. GRADY, EI SIGNING & DELINEATION PROJECT DESIGN ENGINEER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET AND "E" SIGNS
SIGN-2	SIGN DESIGNS
SIGN-3	SIGNING PLAN SHEETS

12/8/2014
R:\TIPProjects-W\W5316\Traffic\Signing\CADD\Signing Layout Plans\W-5316 SIGNING SHEETS.dgn
jsergalopo