PROJECT NO.	SHEET NO.	TOTAL NO.
10CR.10901.40,ETC	24	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	AGGREGATE SHOULDER BORROW ALLOWED	LENGTH MI	WIDTH FT	BORROW CY	SOIL CEMENT BASE (FULL DEPTH RECLAMATION) SY	PORTLAND CEMENT FOR SOIL CEMENT BASE TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	2.5" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	INTERMEDIATE COURSE, I19.0C TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ASPHALT SURFACE TREAT-MENT, SPLIT SEAL SY	RETROFIT EXISTING CURB RAMP EA	6" DRIVE-WAYS SY	ADJ. OF CATCH BASINS EA	ADJ. OF MAN-HOLES EA	ADJ. OF METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	STONE FOR EROSION CONTROL, CLASS B TN	SEDIMENT CONTROL STONE TN	WATTLE LF	POLYACRYLAMIDE (PAM) LB
10CR.20901.115	Union	21	SR 1008 WAXHAW-INDIAN TRAIL RD	FROM SR 2819 (GOLDEN POND RD) TO ROUNDABOUT **MILEPOST 9.6 TO 7.96**	16	2	2WU	NO	NO	YES	1.64	21	310			105	3.3				272			1,960	630			159	857			375			7	246	33	17	246	1
10CR.20901.116	Union	22	SR 1367 UNIONVILLE-INDIAN TRAIL RD	FROM PAVEMENT JOINT EAST OF SR 1508 POPLIN ROAD TO SR 1514 (ROCKY RIVER RD) **MILEPOST 5.6 TO 4.66**	13,16	2	2WU	NO	NO	YES	0.94	31	88			120	1.0	320		3,300	138			1,400	220			98	466			100			1	75	10	5	75	1
10CR.20901.117	Union	23	SR 1003 WHITE STORE RD	FROM SR 1957 (OLD MONROE MARSHVILLE RD) TO SR 1937 (OLD PAGELAND-MONROE RD) **MILEPOST 10.99 TO 6.09**	16	2	2WU	NO	NO	YES	4.9	22	896			360	9.8				290			5,700	2,156			482	2,695			125				735	98	49	735	2
10CR.20901.118	Union	24	SR 1735 EAST UNION ST	FROM PAVEMENT JOINT @ NC 205 TO SR 1719 (MARSHVILLE-OLIVE BRANCH RD) **MILEPOST 4.1 TO 3.87**	17	2	2WU	NO	NO	NO	0.23	37						4,934						478				29	127				1	3						
		25	SR 1735 EAST UNION ST	FROM SR 1719 (MARSHVILLE-OLIVE BRANCH RD) TO PAVEMENT JOINT @ END OF CURB AND GUTTER **MILEPOST 3.87 TO 3.45**	17	2	2WU	NO	NO	NO	0.42	36						8,860						819				49	231				1	6	5					
TOTAL FOR PROJ NO. 10CR.20901.118											0.65							13,794						1,297				78	358				2	9	5					
10CR.20901.119	Union	26	SR 1005 WHITE ST	FROM US 74 TO EAST MAIN ST. **MILEPOST 14.203 TO 14.3**	17	2	2WU	NO	NO	NO	0.09	20						1,184						110				7	48				1	2	1					
10CR.20901.120	Union	27	SR 1631 LAWYERS RD	FROM NC 200 TO SR 1631 (MCINTRYE RD) **MILEPOST 0 TO 3.0**	15	2	2WU	NO	NO	NO	3	23									858						2,532	170											
		28	SR 1388 WILL PLYLER RD	FROM SR 1315 (NEW TOWN RD) TO SR 1008 (WAXHAW-INDIAN TRAIL RD) **MILEPOST 0 TO 0.68**	15	2	2WU	NO	NO	NO	0.68	23									256						556	37											
		29	SR 1681 OLD CAMDEN RD	FROM SR 1627 (NEW SALEM RD) TO NC 200 NORTH **MILEPOST 2.8 TO 2.1**	15	2	2WU	NO	NO	NO	0.7	21									234						785	53											
		36	SR 1528 FRIENDLY BAPTIST CHURCH RD	FROM SR 1004 (LAWYERS RD) TO SR 1504 (RIDGE RD) **MILEPOST 0 TO 1.42**	15	2	2WU	NO	NO	NO	1.42	20									223						1,005	67											
TOTAL FOR PROJ NO. 10CR.20901.120											5.8										1,571						4,878	327											
10CR.20901.121	Union	30	SR 1613 CJ THOMAS RD	FROM PAVEMENT JOINT @ US 601 NORTH TO SR 1367 (UNIONVILLE-INDIAN TRAIL RD) **MILEPOST 1.14 TO 0**	19	2	2WU	NO	NO	NO	1.14	18				50					249						878	59			25			2	342	35	18	342	1
		31	SR 1613 CJ THOMAS RD	FROM US 601 NORTH TO SR 1504 (RIDGE RD) **MILEPOST 1.2 TO 2.7**	19	2	2WU	NO	NO	NO	1.5	18				85					240						1,646	110			50			2	450	45	23	450	1
TOTAL FOR PROJ NO. 10CR.20901.121											2.64					135					489						2,524	169			75			4	792	80	41	792	2
10CR.20901.122	Union	32	SR 1530 PENNIGAR RD	FROM SR 1529 (DUNCAN RD) TO PAVEMENT JOINT @ US 601 NORTH **MILEPOST 1.13 TO 0**	19	2	2WU	NO	NO	NO	1.13	17				160					223						818	55			250				339	34	17	339	1
10CR.20901.123	Union	33	SR 1937 OLD PAGELAND-MARSHVILLE RD	FROM OLD US 74 (SR 1740) TO PAVEMENT JOINT @ BRIDGE **MILEPOST 12.36 TO 10.24**	20	2	2WU	NO	NO	NO	2.12	19				100					243						1,600	107			50			2	636	64	32	636	2
10CR.20901.124	Union	34	SR 2161 CIRCLE S RANCH RD	FROM SR 2146 (PLYLER MILL RD) TO SR 2160 (WALT GAY RD) **MILEPOST 0 TO 1.3**	20	2	2WU	NO	NO	NO	1.3	19				60					234						970	65			325				390	39	20	390	1
10CR.20901.125	Union	35	SR 2130 ARMFIELD MILL RD	FROM 2115 (STACK RD) TO SR 2125 (JACK DAVIS RD) **MILEPOST 0 TO 2.44**	20	2	2WU	NO	NO	NO	2.44	19				85					252						1,860	125							732	74	37	732	2
10SP.20905.1	Union	30	SR 1613 CJ THOMAS RD	FROM PAVEMENT JOINT @ US 601 NORTH TO SR 1367 (UNIONVILLE-INDIAN TRAIL RD) **MILEPOST 1.14 TO 0**	19	2	2WU	NO	NO	NO	(1.14)	18		14,758	473															13,416										
		31	SR 1613 CJ THOMAS RD	FROM US 601 NORTH TO SR 1504 (RIDGE RD) **MILEPOST 1.2 TO 2.7**	19	2	2WU	NO	NO	NO	(1.5)	18		19,070	611															17,336										
TOTAL FOR PROJ NO. 10SP.20905.1														33,828	1,084															30,752										
10SP.20905.2	Union	32	SR 1530 PENNIGAR RD	FROM SR 1529 (DUNCAN RD) TO PAVEMENT JOINT @ US 601 NORTH **MILEPOST 1.13 TO 0**	19	2	2WU	NO	NO	NO	(1.13)	17		14,599	453															13,272										
10SP.20905.3	Union	33	SR 1937 OLD PAGELAND-MARSHVILLE RD	FROM OLD US 74 (SR 1740) TO PAVEMENT JOINT SOUTH OF SR 1947 FAULKS CHURCH ROAD **MILEPOST 12.36 TO 10.24**	20	2	2WU	NO	NO	NO	(2.12)	19		28,546	971															26,064										
10SP.20905.4	Union	34	SR 2161 CIRCLE S RANCH RD	FROM SR 2146 (PLYLER MILL RD) TO SR 2160 (WALT GAY RD) **MILEPOST 0 TO 1.3**	20	2	2WU	NO	NO	NO	(1.3)	19		17,238	638															15,739										
10SP.20905.5	Union	35	SR 2130 ARMFIELD MILL RD	FROM SR 2115 (STACK RD) TO SR 2125 (JACK DAVIS RD) **MILEPOST 0 TO 2.44**	20	2	2WU	NO	NO	NO	(2.44)	19		32,873	1,200															30,014										
10SP.20905.6	Union	16	SR 1343 COX ROAD	FROM PAVEMENT JOINT @ NC 84 TO SR 1344 WEDDINGTON-MATTHEWS ROAD **MILEPOST 0 TO 1.12**	20	2	2WU	NO	NO	NO	(1.12)	24		15,981	560															15,200										
GRAND TOTAL											**41.41**		**6,701**	**143,065**	**4,906**	**2,254**	**39.5**	**171,054**	**45,024**	**3,300**	**5,523**	**16,202**	**7,058**	**25,714**	**3,701**	**16,384**	**13,648**	**4,783**	**15,157**	**131,041**	**3**	**2,450**	**3**	**27**	**51**	**6,685**	**756**	**382**	**6,685**	**23**