8/17/99

PROJ. REFERENCE NO.	SHEET NO.
I-0914BB	PMP-1A

FINAL PAVEMENT MARKING SCHEDULE

MATERIAL	SYMBOL	DESCRIPTION
PAVEMENT MARKING		
POLYUREA (4″) HIGHLY REFLECTIVE ELEMENTS		
	V8	WHITE MINISKIP (2′/6′ SP)
	VA	WHITE EDGELINE
	VD	WHITE MINISKIP (3′/9′ SP)
	VI	YELLOW DOUBLE CENTER
POLYUREA (6″) HIGHLY REFLECTIVE ELEMENTS		
	V6	WHITE EDGELINE
	V7	YELLOW EDGELINE
	V11	WHITE MINISKIP (2′/6′ SP)
	VJ	WHITE SKIP (10′)
	VK	WHITE MINISKIP (3′/9′ SP)
POLYUREA (8″) HIGHLY REFLECTIVE ELEMENTS		
	VN	WHITE GORELINE
POLYUREA (12″) HIGHLY REFLECTIVE ELEMENTS		
	VS	WHITE GORELINE
	VT	WHITE SOLID LANE LINE
THERMOPLASTIC SYMBOLS (90 MILS) HIGHLY REFLECTIVE ELEMENTS		
	UN	24″ YIELD LINE TRIANGLE
	UP	MERGE ARROW
THERMOPLASTIC (24″, 120 MILS) HIGHLY REFLECTIVE ELEMENTS		
	T2	WHITE STOP BAR

LEGEND

GENERAL

DIRECTION OF TRAFFIC FLOW

NORTH ARROW

PROPOSED PVMT. ---------- EXIST. PVMT.

PAVEMENT MARKINGS

PAVEMENT MARKING SYMBOLS

HNTB

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

APPROVED: DocuSigned by: Rhonda B. Early 3-E3-AF-AC-D8F-8A DATE: 11/4/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 023521 ENGINEER RHONDA B. EARLY

PAVEMENT MARKING SCHEDULE AND LEGEND

4:40pl2 PM
.:\PMP_Plans\I0914BB_pmp01.dgn
.$$$$USERNAME$$$$