STANDARD MILEMARKER DESIGN



INSTALLATION NOTE:
INSTALL ON 3 LB. U-CHANNEL POST 4' ABOVE EDGE OF TRAVEL LANE (EDGELINE) ELEVATION. INSTALL AT SHOULDER POINT OR MAX OF 15' FROM EDGE OF TRAVEL LANE, UNLESS OTHERWISE APPROVED BY ENGINEER.

TIP NO.	SHEET NO.
I-0914BB	SIGN-4B

APPROVED: DocuSigned by: Charles A. Johnson, III 59A1565B47F54A6...

DATE: 11/3/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 20675 ENGINEER CHARLES A. JOHNSON III

	NORTH 85 MILE 224 .5 18" X 60" ONE "U" POST PER SIGN	NORTH 85 MILE 227 18" X 54" ONE "U" POST PER SIGN	NORTH 85 MILE 229 .5 18" X 60" ONE "U" POST PER SIGN	NORTH 85 MILE 232 18" X 54" ONE "U" POST PER SIGN		
	NORTH 85 MILE 225 18" X 54" ONE "U" POST PER SIGN	NORTH 85 MILE 227 .5 18" X 60" ONE "U" POST PER SIGN	NORTH 85 MILE 230 18" X 54" ONE "U" POST PER SIGN	NORTH 85 MILE 232 .5 18" X 60" ONE "U" POST PER SIGN		
	NORTH 85 MILE 225 .5 18" X 60" ONE "U" POST PER SIGN	NORTH 85 MILE 228 18" X 54" ONE "U" POST PER SIGN	NORTH 85 MILE 230 .5 18" X 60" ONE "U" POST PER SIGN	NORTH 85 MILE 233 18" X 54" ONE "U" POST PER SIGN		
	NORTH 85 MILE 226 18" X 54" ONE "U" POST PER SIGN	NORTH 85 MILE 228 .5 18" X 60" ONE "U" POST PER SIGN	NORTH 85 MILE 231 18" X 54" ONE "U" POST PER SIGN	NORTH 85 MILE 233 .5 18" X 60" ONE "U" POST PER SIGN		
	NORTH 85 MILE 226 .5 18" X 60" ONE "U" POST PER SIGN	NORTH 85 MILE 229 18" X 54" ONE "U" POST PER SIGN	NORTH 85 MILE 231 .5 18" X 60" ONE "U" POST PER SIGN			

HNTB
HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

MILEMARKERS (NORTHBOUND DIRECTION)