TIP NO.	SHEET NO.
I-0914BB	SIGN-4

APPROVED: DocuSigned by: Charles A. Johnson, III 59A1565B47F54A8...

DATE: 11/3/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 20675 ENGINEER CHARLES A. JOHNSON III

(401) QUANTITY REQ'D 9



48" X 60"
R2-1

TWO "U" POSTS PER SIGN

(402) QUANTITY REQ'D 12

36" X 24"
R5-1A

ONE "U" POST PER SIGN

(403) QUANTITY REQ'D 14

36" X 36"
R1-1

ONE "U" POST PER SIGN

(404) QUANTITY REQ'D 12

36" X 36"
R5-1

MOUNT ON BACK OF SIGN 403 IN 12 INSTALLATIONS

(405) QUANTITY REQ'D 6

54" X 18"
R6-1(R)

TWO "U" POSTS PER SIGN

(406) QUANTITY REQ'D 6

54" X 18"
R6-1(L)

MOUNT ON BACK OF SIGN 405 IN 6 INSTALLATIONS

(407) QUANTITY REQ'D 7



48" X 48"
W4-1(R)

TWO "U" POSTS PER SIGN

(408) QUANTITY REQ'D 1

48" X 54"
R5-15

TWO "U" POSTS PER SIGN

(409) QUANTITY REQ'D 1

48" X 24"
R5-16

MOUNT BELOW SIGN 408 IN 1 INSTALLATION

(410) QUANTITY REQ'D 1



48" X 36"
R5-17

TWO "U" POSTS PER SIGN

(411) QUANTITY REQ'D 1

30" X 30"
W1-2L

ONE "U" POST PER SIGN

(412) QUANTITY REQ'D 1



48" X 24"
W1-7

TWO "U" POSTS PER SIGN

(413) QUANTITY REQ'D 1



36" X 36"
R1-2

ONE "U" POST PER SIGN

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

TYPE "E" SIGNS